Presented to

The Observatory, Madras

THE ROYAL SOCIETY

CALL NO 5222.

ROY

LIBRANY

KOD-INANAL

CORRESPONDENCE

CONCIRNING THE

GREAT MELBOURNE TELESCOPE.

IN THREE PARIS

1852 - 1870

Printed for private circulation only, by order of the Council of the Loyal Society

IONDON

CRIVILD BY INVIOR AND ILANCIS TID HON COULT, ILITE SPRITE

1871



CONTENTS

PART I

1852-1853

Extract from Council Minutes of the Royal Society (Nov. 25, 1862)

CORRESPONDENCE	D
	Page 1
M1 Nasmyth to the Lul of Rosse	3
The Earl of Rosse to Colonel Sabine Sin David Brewster to Mr Weld	5
	6
Mi C P Smyth to Capt Smyth	10
Mi C P Smyth, Appendix	12
M1 Airy to Mr Bell Rev D1 Robinson to the Earl of Rosse	13
	15
Mr Nasmyth to the Earl of Rosse	15
Mr Lassell to Mr Bell	18
Sii J W Lubbock to Mi Bell Sii John Heischel to Mr Bell	19
Lev Dr Robinson to Mi Bell	24
	27
M ₁ E J Cooper to M ₁ Bell	30
M1 Any to Mr Bell I On the general course of conduct of the Committee	30
II On the Site	31
III On the Telescope and its mounting	31
IV On the Exhibition of Results	33
Rcy D1 Robinson to the Earl of Rosse	33
The Last of Rosse—Memorandum	35
Sir William Denison to Colonel Sabine (Extract)	30
Rev Dr Robinson to Colonel Sabine	36
M ₁ Nasmyth to Mr Bell	37
M ₁ Lassell to M ₁ Bell	41
I ord Wrottesley to Mr Bell	44
Extract from Minutes of the Committee of the Loyal Society on the	
Southern Telescope (July 5, 1853)	4.5
Woodcuts, pp 2 32, 38	· L .
Supplement	
Rev Dr Robinson to Colonel Sabine (July 29, 1853)	
Rev Dr Robinson to Cotoner Sabine (July 25, 1093)	

٧

PART II

CORRESPONDENCE

1862-1863

	Page
General Sabine to Mr Lassell	
Mr I lliot to the Secretary of the Royal Society	4
Governor Sn H Bully to the Duke of Newcastle	E
Prof Wilson to Sii H Baikly	ϵ
Extract from Minutes of a Meetin, of the Board of Visitors to	
the Observatories, July 15, 1862	(
Mr Lassell to General Sabine	7
Pev Di Pobinson to General Sabine	11
Su J Herschel to General Sabine	11
The Farl of Rosse to General Sabine	14
Pev Di Robinson to General Sabine	15
Mi Lassell to General Sabine	17
The Earl of Poss. to General Sabine	18
The Earl of Posse to General Sabine	19
Sir J Heischel to General Sabine	19
Rev Dr Pobinson to General Sabine	22
Mr Glubb to Rev Dr Pobinson	23
References to Plate	27
I he Earl of Rosse to General Sabine	28
Extract from Minutes of Council of the Royal Society (Dec 18	
1862)	29
Mr De La Rue to General Sabine	31
511 J Herschel to General Sabine	34
The Earl of Rosse to General Sabine	34
Mr De La Rue to General Sabine	35
Rev Di Robinson to General Sabine	36
Sir J Heischel to General Sabine	38
Mr Lassell to General Sabine	29
Mr De La Pue (extract) to General Sabine	39
Plates, pp 8, 26	
Woodcuts, pp 21, 24, 25	

PART III

CORRESPONDENCE

1863-1870

General Sabine to Prof Wilson	7
General Sabine to the Duke of Newcastle	1
General Sabine to Prof Wilson	2
	2
Mr Elliot to the Secretary of the Royal Society	3
	v

CONTENTS

O	rige
Governor Sir C Darling to Mi Cuidwell	3
Prof Wilson to the Chief Scenetary	4
Extract from Minutes of a Meeting of the Board of Visitors of the	
Obscivitory (June 21, 1864)	4 5
General Sabine to Mi Elliot	6
Governor Sin C II Dailing to Mi Cardwell	6
Prof Wilson to General Sabine	8
Prof Wilson to Major Pasley	9
Rev Di Lobinson to General Sabine	,
Latract from Minutes of Council of the Royal Society (March	9
19, 1868), and Report of Committee Mi Lassell to General Sabine (separate Report)	12
Mi Ellery to Su Edward Subme	14
Mi Ellery to the Astronomer 1 oyal (Extract)	15
Pev Di I obinson to Mi De I a Luc	15
M1 Le Sueur s Account of the removal of the Telescope to Au	
strain, and of the first Olservations made therewith	16
Mi Verdon to Sir Edward Sabine	22
Mi Ellery to Sii Edward Sabine	23
Chief Secretary MacPherson to Mr Verdon	24
Report by M1 Ellery the Government Astronomer	25
Rev Dr Pobinson to Sir Edward Sabine	26
Mi De I 2 Rue to Sii Edward Sabine	30
Sn Edward Sabine to Mr Verdon, with enclosures from Rev Dr	
Kobinson and Mi De La Kue	31
Key Di Kobinson to Su I dwud Sabine	32
Mr Verdon to Sn Edward Sabine	32
he port of the (overnment Astronomer (March 31, 1870)	33
Mi Grubb's I (marks on the Specula of the Great Melbourne le-	
lescope, and the Melbourne Leports connected therewith (Ex-	
c(1pt)	38
Sii I Tdwaid Sabine to Mi Veidon, with five enclosures, viz	40
M1 Me111116ld to S11 Ldward Sabine	41
Mi Seveni to Mi Mennifield	41
Mr De I a Rue to Su Ldwud Sabine	43
Sn J Herschel to Sir Edward Sabine	43
Pev D1 Robinson to S11 Fdward Subme	45
Sir I dward Subme to Mr Verdon (Extracts)	40
Sin I dward Sabine to Prof. Stokes	47
Sn I dward Sabine to Prof Stokes	47
Mr Le Sueur to Prof Stokes	48
Abstract of the Pev Dr Robinson's Description of the Great Mel	,,
bourne Telescope, Sept 1871 (with Plates)	49

ł			

[For private circulation only |

THE ROYAL SOCIETY

CORRESPONDENCE

OF

THE SOUTHERN TELESCOPE COMMITTEE

At a Council of the Royal Society (November 25, 1852) —
The following Resolution of the Council of the British Association
was read —

That it is expedient to proceed without delay with the establish ment in the Southern Hemisphere of a Telescope not inferior in power to a three feet reflector—and that the President of the British Association—with the assistance of the following gentlemen—viz—The Earl of Rosse—Di Robinson, Lord Wrottesley—J C Adams—Esq—The Astronomer Royal—J Nasmyth—Esq—W—Lassell—Esq—Sir—D—Brewster—and E—J—Cooper—Esq—be requested to take such steps as they shall deem most desirable—to carry out the preceding resolution

Whereupon it was Resolved —That the President and Council agree with the British Association in considering it desirable to proceed without delay in obtuining the establishment of a telescope of very great optical power for the observation of Nebulæ in a convenient locality in the southern hemisphere and that a Committee be appointed to take such steps as they deem most desirable to carry out this resolution. The Committee to consist of the President Officers and Council of the Royal Society with the addition of the following gentlemen. Lord Wrottesley, Dr. Robinson, J. C. Adams, E. q. The Astronomer Royal, J. Nasmyth, Esq. W. Las sell. Esq. Sir David Brewster, E. J. Cooper, Esq. Sir John Herschel. Sir John Lubbock, and the Dean of Ely.*

The following Correspondence which has taken place amongst the Members of the Committee then appointed is printed by order of the President of the Royal Society

^{*} The name of John Phillips Esq was added at a subsequent Meeting of the Council

CORRESPONDENCE

Mr Nasmyth to the Earl of Rosse


My Lord

Bridgewater Foundry Patricroft near Manchester Dec 15 1852

With respect to the system of mounting such an instrument as is proposed I should vastly prefer the equatorial and do not think that even in respect to expense it would prove so much more costly than the altitude and azimuth and decidedly superior as to general steadiness and ease of management and for securing by clock work move ment perfect tranquility to the observer who I would propose to place in a very snug box or box seat slung to the eye piece socket. After selecting his object he would have nothing to do but sit at his work carried along with the instrument and the object ever in the field. As the powers requisite to use up all the light of a four foot metal must be seldom much under 360 to 400 were we to attempt to follow the object by other than equatorial clock motion. I fear there would be little of that tranquility so requisite in making careful observations and sketches with so powerful an instrument

The following rude sketch is somewhat like the way in which it appears to me such an in trument should be mounted. The polar axis is a strong frame of cast iron between the sides of which the telescope tube swings the observer is in his snug box slung to the eye piece socket so as to sit always on a horizontal seat whatever may be the position of the instrument the seat of his box being universal for that object the tube to revolve in the square socket bore A so as to give means of correcting the ciew of the tube consequent on the equatorial arrangement and in that way keep eye piece ob server and metal always in one constant or nearly constant parallel I would recommend my? plan of having the metal in a hinged cast iron cell so that by a small windless at B you can let back the cell

on the hinge C and get in to wipe it or cover it with the utmost care. I find this a most handy system



With sufficient mass of material in the frame or polar axis I should would be at all fitted for observation the observer might close his shutters and be as snug as at his own parlour fireside for when once he had sat down to his work on the object then in hand with the clockwork in gear he need not trouble his attendant for the next three hours if he select such objects as are near the meridian With respect to the cost of such an instrument I have made a rough esti mate of what appears to me would be a fair price for so out of the way and anxious a job including a suitable polishing machine which I conceive to be absolutely requisite I should say the maker who ever he may be ought to have £3000 at the least I include in this two metals of not less than 6 inches thick ground on the back to the same curve as the face supported of course on your Lordship s admirable plan of say 81 self adjusting points or friction ball would fain have had the focal length equal to 9 or at least 8 dia meters of the metal

If we could prevail upon Mesars Maudsley to undertake this work I think we could supply them with all the information as to casting grinding and polishing which they would stand in need of (Signed) James Nasmyth

To the Right Honourable The Earl of Rosse &c &c

The Earl of Rosse to Colonel Sabine

Castle Parsonstown December 18th 1852

DEAR SABINE

The equatorial mounting as proposed by Nasmvth would be de cidedly preferable to the altitude and izimuth mounting of our three feet telescope provided it was steady. The worst consequence to be apprehended should there be a want of steadiness, is impaired definition Of course with an unsteady instrument micrometer work would be very unsatisfactory but that comparatively is a subordinate Nasmyth's mounting is in principle what has been consider ition called the English mounting a long polar axis being employed instead of a short bearing So far as I am aware no large instrument so con structed is stendy except the Liverpool equatorial In the case of the Liverpool equatorial the weight of the tele cope bears a very small proportion to the weight of the polar was and that in my opinion is the reason why it is steady I am spealing merely by guess but I should think the weight of the telescope is probably not more than 16th the weight of the polar axis On this point and I thinl it a very important one precise information could easily le obtained The equatorial here is on the English plan and is I believe the largest instrument of the kind It is not perfectly stendy and I am sure it would not work satisfactorily in the open air The speculum is 18 inches aperture and 10 feet focus the polar axis is 14 feet long and 31 feet largest dinmeter made of wood like a cask staves are very strong and were impregnated with sulphate of cop per then baked and closely hooped. After hooping the whole was baked and the hoops re driven The ends are of oak in alter nate layers 12 inches thick glued and bolted together to which the staves are attached by thirty dozen of screws aided by glue whole was covered with a cement of bees wax resin whiting and spirit of turpentine to protect it from hygrometric action of the declination axis is contained in a copper pipe which makes air tight joints with the polar axis so that damp air is excluded The polar axis was turned to receive its fittings and so well has it kept its figure that it now runs as true in its bearings as it ever did Its stiffness is so great that a small telescope magnifying about fifteen times, having been fixed to one extremity and looking at a fine mark fixed at the other extremity (so as to test flexure) when the polar axis with its full load was turned round 180° the flexure was imperceptible With this great strength however the torsion is suf ficient to produce considerable unsteadiness in right ascension in handling the instrument I he declination axis on the other hand is but $3\frac{1}{2}$ inches thick at the bearing close to the telescope and yet no instrument can be freer from tremor in declination. In the one case the telescope is 7 feet from each bearing and in spite of enor mous strength we have torsion and tremor in the other case it is scarcely 3 inches und there is no perceptible tremoi or torsion though the axis is compuratively feeble. The weight of the telescope m w be to the weight of the polir axis as about 1 to 4

Nasmyth's mounting the telescope can scarcely be less than 12 feet from each bearing and in my opinion nothing but enormous mass can prevent tor ion and so much unsteadiness as will render the instrument of little value in the open air. It will be necessity to form at lea to me rude conception of what the mass should be unfortunately in these motions we cannot afely trust to mere dyna mical considerations there is much which is very obscure and we must as it were feel our way. As the size of instrument increases the proportionate strength of materials aiminishes it would not therefore be safe to infer that a polar axis sixteen times heavier than the telescope would be sufficient There may however be an ex cess of strength in the Liverpool polar axis and probably this ques tion might be tested by loading the telescope if the telescope is strong enough to bear this rough treatment without injury po e the same proportions as the Liverpool equatorial should be con sidered afe which I have assumed to be as 1 16 roughly speaking the weight of the telescope may be somewhat as follows -

Speculum Box and levers Tube	Tons $1\frac{1}{2}$ $\frac{1}{2}$ 4	
	6	
	16	
	96 tons	weight of polar axis

This at £20 per ton including patterns and millwright's work would be £1920 as the cost of the polar axis. The brass circle and clock would I should thind be at least £200 or £300 more the tube and fittings perhaps £500 and the two specula £1000. The polishing machinery with a one horse steam engine to drive it would cost perhaps £300.

There should be an unusually large mugin for contingences so that I think it would be carcely safe to estimate the cost at less than $\pounds 6000$

Were it determined to execute such an instrument it would be highly desirable that a good working model furnished with an excellent telescope should be made previously and tholoughly tested. The telescope itself should also in my opinion be put up near the maker in a temporary way and well tried at real work before it was sent out. In the event of failure the tube would answer for an

altitude and azimuth mounting An instrument mounted like my three feet telescope would cost I think about one half The equa tonal mounting if really successful is so much better than my plain stand that if he Government could be prevailed upon to incur the expense the experiment certainly ought to be tried I have just re ceived Mr Smyth's ingenious plan for mounting a large telescope equatorially but have not con idered it with the attention it deserves I fear the cost would be enormous and I scarcely think the mass could be sifely made materially less than in Nasmyth's I he distance between the pivots of the polar axis and the point to which the driving force would be applied is so considerable that there would be a strain which the form would not be well calculated to resist where there is much torsion I fear it would be difficult to control the Should the Messrs Maudsley be tremois to which it gives rise disposed to undertake the instrument Mr De la Rue could I am sure assist them in the polishing and when in I ondon I should of course be very happy to afford them any information in my power treme pie sure of business of different kinds has prevented me from writing to you as soon as I intended I should have been glad to try the experiment whether the movements of the observer placed as proposed by Mr Nasmyth would be likely to disturb the instru ment but the weather has rendered it impossible

(Signed) Rosen

Postscript

I omitted to add to my letter of yesterday that I thinl the German mounting is preferable to Nasmyth's and to every other which has been suggested. It has its disadvantages its small circles being objectionable still looking to the two great questions steadiness and expense I think it has greatly the advantage. I think it would be safer to speak with confidence about it than any other. I have not seen Mr Cooper's but I believe from what I have heard it is perfectly steady and the telescope is unusually heavy for its length and aperture. It is used in the open air with however some shelter from a wall. Mr Cooper's is the German mounting and I thinl it might in some measure be taken as a large working model.

Very truly &c

Rosse

Sir D Brewster to Mr Weld

St I conard's College St Andrews Dec 20th 18:2

DEAR SIR

I may mention to you what I thought it right to state to Lord Wrottesley that when I was on a visit to Lord John Russell list autumn I was describing to him Lord Rosses great telescope he of his own accord said Would it not be a right thing to send a large telescope to a southern climate? I replied Certainly but your Lordship would not give us money to do it and I added that I felt the disappointment particularly as I was President of

the British Association when it was refused. I ord John said that he had no recollection of the matter and I stated in a way not to be includerstood what I firmly believe is the truth that some interested per on had interposed on the occasion and prejudiced the frovernment against the scheme

It another application is made to the Government which of course, it will be I trust that the Committee will take care that it is made by per one who e hearts are really in the cause and that they will take one to meet my underhand opposition that may be made to it

the new etablishment and I look forward to results of the highest

I am den Sn

C K Wild Lsq.

I ver most truly yours
D. Briwsiir

W. C P Smyth to Capt Smyth

London December 22 18.2

My mar Lyimir

I inding that there is a greater length of time to spare than had been expected before the next Meeting of the Southern Tele cope (committee I tale advantage of the opportunity to write more tally on several of the topics which are to be considered. It may lead to a simplification of the question of I withdraw from the conditions mentioned in your letter of December 7th to Mr. Bell the process to the effect that the new establishment was not to be in terior to that of the Cape. There then only remain.

- 1 The mounting of the Telescope
- 2 The site of the Observatory
- I he publication of the results

The mounting of the Ielescope — The telescope is I believe to be a Newtonian reflector with in specture of 4 and a focal length of 30 feet. Its weight therefore will be very great, and a mounting of the distribute and examine construction would be the simplest mechanical olution of the problem of enabling it to be pointed to every part of the 1x

But in the precent case, where not only eye views of the nebular in required but recurate numerical measures of them also use in the pensible and should form the leading feature of the establishment the imple altitude and azimuth standwill not be found sufficient without it lea to the assistance of some additional directive upper that the equational motion such as that devised by Mr. Arry for some temporary tands at Greenwich

Were there however sufficient truth of movement obtuned by the emean and in a sufficiently simple manner for the purpose of moreometrical measure at would be found still more difficult to leep up the motion with that perfect uniformity through a long part dof time, which would be absolutely necessary in the applica tion of photographical processes to picturing the field of view This is a method too which it is of the highest importance to introduce and which though at present applicable to but a limited range of objects will without doubt be continually undergoing important extension

The very strict requirements of this latter mode of procuring results would seem to oblige us to adopt the parallactic form of mounting with clock work motion. In principle nothing can be better and in practice it has proved in various instances all that could be wished. Still it is apprehended that there would be great difficulty in applying it to so heavy an instrument as a 4 foot speculum.

On looling around we certainly find that no equatorial mounting strong enough for such a reflector has yet appeared but that is no proof that it is impossible. Often by discovering errors of principle in the older constructions of by employing stiffer materials and greater mass has the principle been found capable of extension to larger sizes. And the recent immense advances in the manufacture and the employment of both cast and wrought from may be talled as an assurance that a far more powerful parallactic instrument may now be produced than has ever yet been seen and I will enclose a plan of my own by which I have strong hopes that a mounting of almost any size and strength could be formed

The site for the Observatory —In addition to all the facilities for producing good observations afforded by the space penetrating power of a telescope, as well as by the style of its mounting much must always depend on the latitude of the stration selected and

more still on its elevation above the level of the sea

This arises mainly from the disturbing effects always present in a greater or less degree of the atmosphere increasing too with the aperture of the telescope as well as with the magnifying power employed. But by simply mounting up 1000 feet above the level of the sea the quantity of the atmosphere to be looked through in a zenith observation will be diminished by so large a portion as $\frac{1}{30}$ th of the whole

Thus there were easily observed with Bradley's zenith sector on the Cape Mountains (2000–2000 feet high) certain small stars of which nothing could afterwards be made at the Cape Observatory while with larger stars seen at both station the mount un observations were more accordant and in so far better than the others owing apparently to the momentary fluctuations of refraction decreasing in proportion to the rurity of the air

Elevation is also of importance in raising the observer above the mechanical impurities of the atmosphere such as fine dust, smoke and the vaporized particles of solid bodies well known under the familiar term of motes in the sunbeam. These rather than the gaseous constituents are what produce the general diffusion of light over the ky impeding photographic action and if abundant (ac cording to the experience of a friend in South Africa) preventing the attuinment of the highest polish on specula

If completely immersed in this dust we are not conscious of the

extent of its effect but on rising up the side of a mountain even on reputedly clear days we then plainly see the impure medium below All object within its leach are then observed to have their edges indistinct and thin the dark and bright parts confused together while the sharpness of the outlines the pungency of the light and the transparency of the shadows of anything above its range form a most striking contrast

When a star by night or a heliotrope by day was seen through this dusty matter at the Cape it was invariably blurred into a diffuse sort of nebula and the pace penetrating power of its light was greatly diminished while nebulæ proper were rendered invisible And if the medium was of more than ordinary density it was found to prevent even the largest heliotropes being seen at short distances though their light would otherwise penetrate with facility through far darker vapour when of the watery kind and through actual runneither of which seem to have any prejudicial effect on definition indeed the only good observing nights at the Cape were when dew was falling

From the very general distribution of this finely divided matter the lowest stratum of the atmosphere for a thickness of about 5000 feet on the average may be regarded as a dry and dut bearing repion above which commences a most and cloud bearing one and rises to a greater height than has yet been reached by man. From the result of two years experience on the S African mountains both a daily and an annual variation in quantity are manifested the dust being more abundant in the afternoon than in the forenoon and in the autumn than in the spring of in much the same ratio in which photographers experience a retardation of the chemical action of the solar rays owing very probably to the yellowish colour transmitted by the particles

They appear moreover to be confined as to their range of altitude in the summer to 3000 feet while in the winter they often rise above 1000 feet—an effect Professor Stokes has suggested of the viscidity of the gases composing the atmosphere and bearing the particles of matter combined with the effect of heat on that quality

From this partial sinking of the dust in summer there results a concentration of it near the surface of the earth in proportion to the warmth of the country and the season. Hence perhaps the remark able fact that the chemical action of the sun's rays i much weaken there notwithstanding the superabundance of light than it is in the temperate and le sillumined zone. This circumstance while it in crea es our difficulties at the level of the sea relieves us of them more and more completely on elevated situations in proportion as the heat is greater which conjoined to the more bearable temperature for the observer points out the advantage of employing an elevated situation in the tropics for the observation of nebulæ

Of the three plans already mentioned at the Committee viz

Cape Town in lat S	34°
Sidney Hobartown	34
HODRITOWN	42

none suit the above conditions very well either as regards latitude or elevation for they are none of them sensibly elevated above the level of the sea and it would be neces ary at least to abandon the towns and seek more appropriate sites in the adjoining country

But even with this modification nothing very favourable can be elicited for at the Cape the best position afforded is the Khamisberg with an inhabited summit 5000 feet high. But it is almost inaccess ibly beyond broad difficult tracts of desert land and is almost entirely deficient of building materials and labourers. Australia is put out of the competition by the effects of the gold discovery and in Van Diemen's Land though some circumstances are more favourable as the abundance of wood of convict libour and of good public roads yet the highest available table land there seems to be not much more than 2000 feet high

It therefore the utmost advantage is to be taken of natural circum stances to second the optical power of the telescope recourse must be had to other countries and of all in the Southern hemisphere the elevated plains of the Andes would appear to be the most favour able and might be adopted but for political difficulties. These however would fortunately offer no bar to employing the new Sana torium of Ceylon, where the height of at least 6000 feet could be

gained

Something might thus be lost on the three first stations as regards latitude for Southern objects but much would be gained in altitude and if photography is to be applied to the registration of telescopic phenomenal every other consideration should give way before this

most important one of elevation of site and for this reason

The atmosphere is never in so perfect a state that a highly magnified image in a telescope appears perfectly quiescent it is always fluctuating more or less with a variety of motions and alterations of shape. In ordinary observing the eye follows all these movements and is able to acquire the same exact idea of the star is it may of the masts and rigging of a ves el that is slowly heaving at sea though such motion during the formation of a camera photograph would prevent anything appearing beyond a bluried mass in the mean position of the hull for the time. As many of the optical tremors too of the atmosphere are so rapid as to be repeated many times in a second no improvement in photographical processes short of perfect in stantineity can remove this serious practical difficulty. And the only mode by which we can at least diminish it is by decreasing through elevation of site the quantity of the atmosphere through which we lool

The publication of the results — The establishment of any observatory by Government being for the benefit of science at large the speedy publication of the observations at stated intervals with all the needful calculations and reductions should be considered as an absolute requirement and more particularly is it the case in the instance now contemplated as it would form the least exceptionable and perhaps the only possible substitute for visitation and supervision

The numerical results might indeed be sent home from abroad and be printed by deputy—but this cannot be done with the draw ings—which will necessarily form a large part of the—results—and no one but the artist himself can efficiently revise an engraving after one of his own drawings

Either therefore the astronomer must come to England occasion ally and see his works through the piess or he must have the engriver with him at the observatory and the plate printer too for there is no good engraving to be performed without frequent proofs being pulled in the course of the work and as sufficiently good engravers and printers do not exist at present in the Southern hem sphere they would have to be sent out expressly for this purpose

In place of engraving we may however now take advantage of the improved photography of the present day on glass plates as a method of multiplying drawings with abundant accuracy and suffi

cient artistical perfection

Photography may be dearer than mechanical printing but considering that only a limited number of copies will be required and that the whole expense of engraving will be saved it may be found a saving on the whole

I remain

Your ever &c C PIAZZI SMYTH

Capt W H Smyth R N F R S

APPLNDIX

Note on a Method of Constructing an Equatorial Mounting for a large Reflector By C Piazzi Smyth

When the focal length of the telescope is short the stand should be of cast metal and ought to be placed under a revolving roof. But if a greater length be decided on the dome may be dispensed with for according to the experience of Lord Rosse the wind does not shake the larger of his several telescopes in a more rapid proportion than the surface probably on account of the weight increasing with their size.

The observer himself however should be protected from the weather as no accurate measurements can be taken by any one exposed immediately to the tempestuous gales which blow with clear skies at the Cape and other places in similar latitudes. The tele scope tube moreover should be fastened at both ends as in the altitude and azimuth stands at Birr Castle so that the wind may have no leverage over the fixings

Then by adopting a construction of wrought iron plates to be put together on the spot with ied hot rivets as in the cale of the Britannia tubular bridge a parallactic mounting for a telescope of any size say 100 feet long may be made in the following manner and with the full preservation of all the above mentioned conditions

1st Let the fundamental portion of the polar rais be a wheel

100 feet in diameter with a very strong hollow rim made of plate iron 1 inch thicl with radial stops and 7 feet broad by 15 deep (in the plane of the wheel) Four strong spol es made also of wrought plates to carry a cast and turned ring 10 feet in diameter as the nave of this wheel which will be also employed as the declination circle. The polar axis pivots to be tubular 3 feet in diameter and to be fastened on the 11m of the wheel by broad bases, the whole being bound together by tires of malleable iron put on red hot.

2nd To strengthen the above laterally as well as to afford the means for clamping and giving clow motion in right ascension let there be fixed to the back of it an equational semicircle of the same tubular construction and with the same radius and let the

driving clock act upon its periphery

3rd For further strength in inclined positions let there be two six hour quadrants—connecting the middle of the equatorial semicircle with the rim of the declination wheel at the polar axis pivot

points

4th The declination axis to be a conical tube 3 feet in diameter at one end and 10 feet at the other with a broad outward flange in addition and long enough to reach from the outward face of the declination circle through the whole structure to the junction of the equatorial semicircle and the six hour quadrants there to be held in by a powerful screw

5th The telescope tube to be double and of 1 inch wrought iron

plate with longitudinal ribs riveted between

6th This cylindrical tube to be enclosed within a prismoidal one by one whose flit surfaces may be attriched to the flange of the declination axis. The angular coiners of the outer tube to be fitted at short intervals in its length with stops so arranged with large central apertures as to form enclosed ladders whereby the observer may climb up from the speculum end of the telescope to the eye piece end. There the prismoid if tube may be expanded into a small room which will screen the observer from the weither and may be so ventilated up one side of the casing between the tubes and down the other that no herted air shall pass over the mouth of the tele scope.

7th The face of the declination circle will bear graduated arcs of turned metal for pointing the telescope by and a rack edge to be woil ed in by a pinion which may be turned for the observing room

to give motion in declinition

8th An irc of turned metil with a toothed edge is also to be fastened to the rim of the equatorial semicircle for the driving clock to act upon—and this being elevated on a pier to the level of the centre of the polar axis—and placed east or west so as to act at six hours distance from the meridian allows of an uninterrupted motion in every direction

This new form of equatorial will thus be firm and stiff in every direction—its long polar axis and small terminal pivots at either end will ensure great truth of inovement in right ascension—The driving clock will act with ease on so large an hour circle—whose plane too

passing through the bearing centie of the telescope reduces the length of the polar axis affected by torsion to a zero scope moreover is clamped at both ends and to as firm a declina tion circle as could be desired while the protection and security given to the observer with the power of directing his in trument without descending from his post the ease and certainty of setting to the faintest object and the command of the whole sky uninter rupted by any mechanical difficulties of reversal on passing the meri dian or otherwise render this parallectic mounting is convenient for use as it is safe and trustworthy on account of its strength and its composition wholly of metal

Mr Any to Mr Bell

DEAR SIR

Poyal Observatory Greenwich December 24th 18.2

Since the meeting of the Southern Tele cope Committee I have repeatedly considered the subject of equatorial mounting of the telescope And I think the probability of this being made practi cable and efficient is so great that I trust that the Committee may be induced to suspend any politive decision until they shall have discus ed special plans

I hope to be able to prepare a model in time for exhibition to the Committee meantime I may explain that the principles which I propose to adopt are the following (of which the first and second have been long entertained by me as necessary for the afe and con

venient u e of a large reflector)

The mounting as regards the support of weight of the tele scope and the keeping of the same edge of the speculum always at the bottom is to be strictly that of an altitude and azimuth instru ment

2 An equatorial construction is to be used not for supporting

any part of the weight but for guiding the telescope

3 This is to be o connected with clock work that the telescope will move truly in hour angle without requiring any adjustment of the clock work for different polar distances

4 The eye piece and micrometer work are to receive a motion exactly corresponding to the rotation of the meridian as seen in an altitude and azimuth instrument so that the micri meter wire once placed to make a certain angle to the meridian will remain maling the same angle with the meridian

> Believe me deal Sir Faithfully yours

> > G B AIRY

Thomas Bell Esq Secretary of the Southern Telescope Committee

Dr Robinson to the Larl of Rosse

Observatory December 28th 1852

My DEAR LORD

Colonel Sabine has sent me Mr Nasmyth's letter on the subject of the southern reflector and your remarks on it

If I comprehend Mr N s drawing rightly his polar axis consists of two parallel frames united at top and bottom by two transverse pieces between which the telescope is suspended. There seems no provision for seeing any part of the sky near the pole and I think the axis would be peculiarly liable to toision. The idea of turning the whole telescope round its axis involves I think some difficulty. It must be provided with two systems of rollers which under the open air may not always act well and it may perhaps be easier to mal \$\epsilon\$ the small speculum and eye piece revolve

I quite agree with Mr N in wishing not to shorten the focus beyond your proportion of 9 diameters. I have succeeded very well (15 inches) in 7 2 but with far greater difficulty than with 9. In deed even when the process failed so far that the whole aperture was not good the proportional part of it was mostly excellent. I hope therefore that the 4 foot may not be attempted with less focus

than 36 feet

I enclose you a tracing (which return when you have lool ed at it) of two schemes which were discussed by Grubb and myself in refer ence to the southern reflector some years since In that marked R I proposed to make the speculum box itself the declination axis pio viding it with journals and a circle and to have a hort and massive polar axis The tube above the box was to be merely an open ske leton framed so as to be stiff enough to support the ocul u part and small mirror This would bring the centic of gravity very near the Grubb did not like this and suggested another murked speculum The polar axis here has its upper bearing about 6 feet diameter but is cut at top so as to let the tube pass in for reaching the pole This would a little woul en the axis there but from its great dia meter the strength would be abundent. It would also interfere with the motion of the instrument at more than five hours from the meridian

I think none can gains by your remails as to the advantage of an equatorial movement. Worl such as we contemplate is ficilitated almost beyond estimation, when the object to be drawn is kept im moveable in a given part of the field and the fatigue of ignalling or shouting to the assistants when the movement is by hand absorbs no small portion of the observer's powers.

And I think your preference of the German form over the English admits of as little dispute that one of the latter form may be stendy if an enormous mass be given to its moving parts is obvious but it must be remembered that such mass increases most materially the difficulty of using it and that the increased friction must cause great additional strain on the moving parts. It is probable that the metal of the Liverpool mounting if applied in a way

similar to Mr Cooper's institument would carry a three feet reflector I have been told it weighs six tons. Now the weight of Mr Cooper's is—

	Cwt
The equatorial part	25 95
Tube object glass eye tube	$9 \ 12$
Counterpoise	$12 \ 42$

Of the first the polar axis is about 18 cwt or twice the weight of the telescope. Now I have been familiar with this instruments working during many years it is very easily moved and perfectly steady. The shelter of the lower half of its tube by the surrounding wall in my opinion rather increases the power of the wind on the upper part to shake as its pressure is unbalanced. In the case of a reflector the influence of the wind would be much lessened by maling its tube a skeleton and I think that instead of the counterpoise there might be put at the other end of the axis an apparatus for supporting the observer. He should be counterpoised to that the frame could be lowered to get him into his chair then raised and clamped in his place. Mr. Cooper's equatorial cost 1 think about £400.

The Germans themselves are quite satisfied with Reichenbach's construction and that of Munich is I know used in the open air Their polar axes are solid and made of steel but it is certainly better to throw the material into a tube. Short bearings seem to be the secret it is scarcely possible to make a stronger axis than that of your equatorial but the length makes it twist. Need a polar axis be longer than the mandrel of a lathe? I forgot to mention that Grubb is getting ready two equatorials for the Dublin Exhibition one a model of that noticed above with a 15 inch reflector the other an improvement of Mr Cooper's, with an 8 inch achromatic of his own grinding. I will report to you or perhaps try them with you

T R ROBINSON

The Earl of Rosse

PS Of course anything from Airy must be considered but I don t expect much improvement on the equitorial Before I had my equatorial mounting for the reflector, I found that with the old 9 inch Herschel which I found here and its rickety stand I could take no measures with the micrometer and in 1830 I made an alteration which may possibly be what Airy is devising. The telescope was set on a circle revolving on balls by a joint something like your 6 feet one and was counterpoised But the horizontal slide of Herschel's stand was connected with a circle by means of which it could be in clined to the angle of position and clamped there I his angle was got by a table of double entry of which the arguments were the azimuth and altitude, both given by the instrument The slide screw gave the movement it acted very fairly as a substitute for the length of the rack about 30 minutes at the equator but as you may suppose I was not sorry to get a true equatorial I really do not see any insuperable difficulty about the mounting. A common turn table with it, edge on rollers would bear forty tons, and there would be no great trouble in setting strong standards on it to curry the tube. Remember that one does not wint the delicacy of a meridian circle here, only motion.

Mr Nasmyth to the Larl of Rosse

Budgewater Foundry Patricroft near Manchester December 30th 1852

Having made out a more careful drawing* of what appears to me would be the most suitable construction for the proposed 4 foot reflector I take the liberty to send it you as it may so far tend to establish the best arrangement for such an instrument

I am very fain to have it mounted equatorially, as there are such vast advantages in that construction for the steady observation of any selected object of which it may be desirable to male careful drawings and as when once the instrument was set upon the object in question the clock work apparatus would do the rest. The clock would require to be of very considerable power but I see no diffi culty on that head By having suitable means whereby the assistant could cause the tube to revolve in the square frame cage the eye piece can be kept horizontal at all times which would also be equally advantageous for the easy set of the metal on its under edge bed The jointed cell for the metal is a very handy arrangement whether for opening the clock for sliding in the disc of zinc is the protector or for the easy removal of the cell and metal by truck and railway to the polisher when it is required A truck with an elevating top would do this very handily The three elevating screws would be found very handy in getting the cell into connection with the joint on the tube the truck might be so arranged as to run direct into the polishing machine and so avoid all the risk and trouble of trans ferring the cell from it to the machine. The tube would require a chain to retain its position when the counterpoise action of the cell and metal was removed Pray excuse this very hasty letter believe me I am

To the Right Honourable The Earl of Rosse

My Lord

Yours most respectfully
James Nasmyin

Mr Lassell to Mr Bell

Valletta December 30th 1852

DEAR SIR

I was preparing some reply to the circular of the Southern Iele scope Committee dated the 1st instant which has been forwarded to me here when I received your second circular of the 15th instant

^{*} May be seen at the Royal Society's Apartments

It appears to me that the question now we is quite a new aspect and it will be for the Committee to determine whether they will carry out their original purpose of erecting an eminently large telescope in the southern hemisphere with every appliance which their united wisdom can secure—or whether they will as a preliminary step elect an observer and commit to him the conduct arrangement and carry ing out of the whole affair

Concluding that they will adopt the former resolution rather than consign so great an undertaking to any single individual however able and accomplished I yet ee all but insuperable difficulties in

adequately realizing so grand a scheme

If there were any manufactory in the world which could furnish completely mounted a 30 inch object glass of similar quality to the 15 inch Munich glasse. I hould say the best thing would be to give the order at once. But as that is not the case the proposed reflector of 4 feet diameter is the best that can be chosen (in my judgement) though I would rather not shorten the focus beyond 35 feet conceiving it to be difficult to get the figure otherwise good quite up to the edge and it seems to me unwise to incur all the difficulties of a colossal telescope and then be obliged to cut down its dimensions

I know something of the efficiency of a 2 foot reflector when brought up (I believe) extremely near to perfection in its figure and furnished with a convenient and steady equatorial mounting driven by clock work It would not be worth while for the Committee to erect a telescope which should not be at least in comparative effi ciency to this as two to one and in order to render the 4 foot equal to this it must have the same conveniences of mounting for any deficiency in this respect will really have the effect of a reduction of the size and power of the telescope I have seen a sletch of a plan of equatorial mounting by my friend Mr Nasmyth which is simple and well calculated for such a latitude as the Cape but I think it would never do to suspend the observer from the eye piece for the slightest motion of his body such as the extension of his arms to adjust the focus alter the polar distance or turn the micro meter head-even his very pulsation would be so communicated to the tele cope as to be visible in the image with the high powers proportioned to such a telescope Besides a very moder ite breeze would equally prevent delicate observations and therefore the tele scope must have a revolving roof for protection from the wind and affording a status for the observer By placing the instrument a little out of the centre 50 feet might do for the dinmeter of such a dome and the few degrees of sky near the zenith thus sacrificed might be recovered by a shutter only to be used on requirement which would extend the opening over the centre of the telescope From the experience I have had in the constituction when vertical of domes 15 and 30 feet in diameter I am satisfied that the same principle of construction might be extended to 50 feet and that no very formidable difficulty would present itself here

The mounting and application of driving motion would be acadily

executed by estimate according to plan by any of our more intel

ligent engineers without any serious obstacle

But the casting grinding polishing and supporting of the great speculum constitute the grand problem the solution of which it is not easy to see For the successful accomplishment of the most essential part of the work there must be perfect unity of design and execution and therefore it must in my opinion be executed entirely under the direction of a single individual who will nevertheless be able to avail himself of any suggestions of others which he may I will mention some of the requirements which I deem judicious think demand this condition I wo specula must be cast 4 feet in diameter and not much less than 6 inches thick each weighing there and supposing the difficulties of cisting and fore about 3500 lbs grinding got over without accident there comes the greater difficulty of polishing and bringing up to the requisite accuracy of figure and most especially of defining power For this I would submit no one is competent who has not had considerable experience in the art itself the cleverest engineer would be here at fault and indeed it is a process which has so rulely been attempted on a large scale that I think it would not be easy for those best acquainted with the subject to say when the greatest practicable amount of perfection It is obvious that some machine must be used and that in all probability repeated polishings and trials must take place before the required accuracy of figure and defining power can be combined in their highest degree Both specula therefore must be figured and polished in the first instance examined and the worst of them taken again to the polisher For this examination with sufficient advantage the entire mounting of the telescope must have been previously erected in fact the whole telescope dome and clock work and all must be erected completely on the place of ope ration just as it would have to be in the place of its ultimate destiny before a satisfactory final result can be secured

Another formidable difficulty I have yet to mention—the sure support of the speculum to prevent its bending and secure its uni form action in all positions In addition to the system of levels on which the speculum is to be ground and polished and which secures this condition when horizontal another system similar or equally efficient with that I have described in the British Association Memoirs for 1850 must be applied to come into action as the telescope is depressed from the zenith and prevent the speculum cringing down as it is turned on edge Without this latter apparatus the image of a bright star gives indisputable evidence of the speculum taking an oval form from the impossibility of bringing the rays from the ends of two diameters of the surface of the speculum at right angles to each other—to focus at once Hence the intolerable an novance which I am accustomed to call crossing visible enough (if the metal otherwise define well) on Jupiter or Saturn as well as To apply this apparatus conveniently the specula should have either a number of blocks or indentures cast on the

back the latter would be best in order not to interfere with the smooth grinding of the back which would be desirable

Supposing then the telescope at last erected complete contiguous to the site of the workshop and pronounced perfect would there not be some compunction at taking it down before some experiment of its magnificent powers on the heavenly bodies should be made? However letting that pass and looking to its ultimate object and destination I don't see who is to manipulate with such a telescope but the maker—I believe that hitherto no very large reflector has done any good service but in the hands of the artist who constructed it—At least if there were an astronomer par excellence to conduct the observations the maker must accompany him and, I should say take out the polishing machine and apparatus for ienewing the surface in case of accident or deterioration of the lustre by exposure

WILLIAM LASSFLL

To Thomas Bell Fsq Secretary of the Royal Society &c

PS—The suggestion of a great altitude for the site is good Perhaps Quito would do but how is the telescope to be got there?

Sir J W Lubbock, Bart to Mr Bell

March 12th 18,3

MY DEAR SIR.

As I am requested so to do I offer the following remarks with very great diffidence not having had any experience either in mid ing or using large instruments. Besides almost every point is so ably handled in various letters from members of the Committee that the subject is pretty well exhausted. There are however one or two which have not been noticed.

1 Surely the Government will never authorize the establishment of a great national observatory at Quito or any point not in our own territory. If then Australia is also out of the question by reason of the abnormal state of that colony we have only the Cape to consider and so that point would be disposed of

2 Mr Smyth attaches great importance to elevation this I can quite appreciate but the elevation which he contemplates will I think never be reached without disadvantages which will outweight the benefit and there are two other conditions I should consider as essential—

1 The non contiguity of the sea or of much standing water 2 The non contiguity of any manufactory or large town

I confess the impression made upon me after attentively reading all the letters and especially Mr Lassell's is that it will be impossible to carry out the plan with a reflecting telescope (I mean of 4 feet diameter).

4 feet diameter) secondly that it must be equatorially mounted and sheltered by a dome thirdly that if it can be done on the mag

nificent scale apparently contemplated by the Committee we had

better begin by having it in the northern hemisphere first

I apprehend (but perhaps I may here be in eiror) there is plenty of work at the Cape for an instrument of such comparatively infe rior power as the Cambridge (America) telescope and up to this point the erection of an observatory would present no in urmountable difficulties

In Mr Nasmyth's mounting, in addition to the other difficulties noticed in the letters the chair of the observer would act at such a mechanical advantage that I suppose it might affect the tube but perhaps it is thought that a slight strain on the tube would not be injurious to the observation

I am dear Sir

Yours futhfully J W LUBBOCK

Thomas Bell Fsq

Sir John Herschel, Bart to Mr Bell

MY DEAR SIR

I am very sorry to have lept the papers relating to the telescope proposed to be established in the couthern hemisphere for the obser vation of nebulæ much longer than I could have contemplated but in truth I have been so much engaged of late that I have found all consecutive thought on the subject impossible and can now only give what has occurred to me on their perusal in a very uncon nected form

I must however preface my observations with a distinct state ment that I am by no means sanguine as to the success of the pro nect-I mean as to the attainment of results at all commensurate in scientific importance with the imposing character of the undertaking as a national one and the very large outlay of the public money which it will call for It is by no means therefore as an advocate for the measure (on which in in earlier stage of its progress I have expressed my opinion more at large) that I have assented to my name being placed on this Committee but that I may not be considered as disposed to withhold (should the project be persevered in) such slender information and practical suggestions as my expe rience in observations with large reflectors directed to this object may enable me to offer as to the kind of instrument and the mode of observation best suited to the purpose It seems above all things necessary that before proceeding a step in the affair its movers should have before them a very clear perception of the sort of instru ment required and its adaptation to the work in hand

There are only two constructions specially indicated in the papers which have come into my hands-those of Mr Nasmyth and of Io the former of these it appears to me that there Mr Smyth exist scrious objections as follows -

1 The polar axis (the mounting being equatorial) as exhibited in the figures however well trussed cannot but have some degree of spring perpendicular to its length which will ensure tremor when ever there is any wind or any movement of the observer in his box Although the telescope is supported on its centre of gravity yet owing to the different lengths of its two portions on either side of the point of support and the very different disposal of the weights the propagation of such tremors through them cannot be synchronous and must therefore result in momentary flexures to and fro of the tube giving rise to oscillations in the line of collimation and con

sequent tremulous apparent movement of the image

2 Such a frame as that of the polar axis divided down its whole length and that length a considerable one cannot but be liable to torsion since, however well the sides may be trussed they will ulti The effect of such torsion is con mately act as two flut ribands veyed entire upor the line of collimation and is the upper and longer portion of the tube will be much more exposed to wind than the lower and shorter I should expect the tremors so produced to be exceedingly obnoxious The hold of the wind on such an apparatus totally unsupported except on the centre of gravity will be most

formidable

3 As the instrument deflects out of the meridian the observer will have to look to the security of his position and to work a mechanism to keep his box vertical It does not appear by what mechanism this is to be performed The mere weight of the observer and box will not do it, and if they could they must overdo it and full beneath the tube I can imagine none free from objection and the line of collimation will be kept in a constant state of unsteadi ness and derangement from this cause which may carry it out of the reach of small corrections

4 The observer will have to balance himself in his box before elevation into the air by adding or subtracting counterpoises is insulated aloft at an elevation from which he cannot descend without the aid of an assistant at whose mercy he is and who may His position would certainly not be an cir be negligent or sleepy viable one

The speculum and its supporting frame hang on a chain by an oblique pull on the edge being sustained also by a hinge below can imagine nothing more objectionable. An enormous power miny times the weight of the mirror, would be required to be applied to this chain to keep the mirror frame tight home as screw work would do

I am hardly engineer enough to criticise Mr Smyth's gigantesque construction of a 100 feet equatorially mounted reflector of niveted iron plates which might perhaps have that sort of stability which any vast aggregation of materials may possess under moderate winds though from the extent of suiface exposed to such gusts as prevail at the Cape I should not be very confident even in this respect But there are several points which may be mentioned is objectionable about it

1st There is no provision in it for keeping one side of the mirror always uppermost and the observer in a vertical position

adjustment is es ential and I believe can only be adequately secured

by the altitude and azimuth movement

2nd Mr Smyth considers it sufficient to destroy the evils of heated air that the chamber at the mouth of the tube should be duly ventilated to keep the personal heat of the observer from passing across it and as regards the rest of the tube he does his best by a cellular structure of its parietes and by enclosing it in an outer triangular case to give a durability and uniformity to its temperature which in my opinion must infallibly secure a continuance of that slow spiral movement of the internal air by the interchange of air within and without through the upper aperture which is the greatest enemy to di finct vision in reflectors

3rd I he observer s access to his aerial chamber is by climbing up a sort of chimney with ladder steps in one angle of the triangular envelope. In his figure this chimney is $\frac{7}{18}$ of the internal diameter of the tube. For a 6 feet reflector this would afford a sufficiently roomy though very inconvenient passage but for a 4 feet size would allow barely room for a man to creep up unincumbered with

any books drawing apparatus &c

In the construction of a large reflector I would press the following

points as essential to be attended to -

lst A very perfect internal collimating telescope with means under the observer's hand of adjusting fiducially the line of collimation without the intervention of an assistant. In my Cape Observations the means of doing this most effectually most simply and to any required degree of precision are pointed out—subject of course to improvement in point of workmanship and mechanical

ariangement

2nd A perfect support of every point of the mirror on an elastic bed. I am by no means entirely satisfied (speal ing with all due respect) with Lord Rosses ingenious contrivance of triplets. It is mechanically complex weighty and after all only supports a definite number of points. I should prefer a bed composed of a great many layers of horsehan cloth or frieze or felt of such united thickness and softness that their total compression by the weight of the mirror should exceed by a great many times the minute amount of flexure undergone in the solid back upport on which they and the mirror both ultimately rest thereby annihilating the influence of such flexure on their supporting power.

3rd The mirror should be so sustained as to rest against and upon this bed, under any circumstances of inclination to the horizon with perfect freedom to rise and fill advance or retreat without change of its parallelism which may be accomplished by suspending it in the mode described in my Cape Observations (Introd Art xv) in a jointed ring from a point above its vertex. In this it must not iest on a single point at its lower edge but should be supported over a large arc of from 60° to 90° of its inferior circum ference on soft and compressible material interposed between it and the ring. Such a mode of support however necessitates the conservation of the hori ontality of a fixed diameter of the mirror.

4th I should greatly prefer a skeleton tube or one (if of iron plate) so pierced with large apertures as to allow of a completely free communication between the interior and exterior air throughout the whole length of the column except perhaps in the very immediate neighbourhood of the mirror for a foot or two from its surface where it may not be needed. Long experience has satisfied me that the establishment of ascending and descending currents of hot and cold air in a long inclined tube open at the top chimney fashion is one principal cause of indistinctness of vision and deformity of image

5th The destruction of tiemor is better secured by several cords of unequal tension or by several steadying rods of unequal strength weight and elasticity than by one single one. It is to this principle that the exceeding absence of tremor in the 20 feet reflector used by me in my observations of nebulæ is attributable. The suspension of the upper end of the tube by a tackle of pullies which by their friction and the stiffness of the cord passing over them never permits all its reduplications to have the same tension causes them to vibrate out of unison with each other and so to destroy each other s

effect in communicating or perpetuating tremor

A form of mounting has been indicated by the Astronomer Royal in which an altitude and azimuth motion of the tube otherwise free and permitting a range over the whole phere is limited to a given parallel of declination by determining the distance of the lower edge of the orifice of the tube from a fixed point (which may be called the polar point) in a line parallel to the earth saxis and passing through the common centre of the horizontal and vertical movements in the lower support of the lower edge or in the centre of gravity of the instrument (if so sustained). If the difficulty of communicating a clock movement to a tube so guided could be completely overcome there would remain that of keeping the micrometer wires in the field of view in a position invariable with respect to the parallel of declination. Mr Airy speaks of a mechanism to this effect but I have not had an opportunity of inspecting his model.

With an altitude and azimuth mounting and with in object on the meridian there could be no difficulty in communicating to the tube a clock movement in the direction and with the velocity cor responding to the parallel of declination at least for a few minutes. Were this done a photographic impression could be obtained with this as with an equatorial mounting

I should rely on photographic proces es to impress on paper a sleleton picture or the images of the stars only which might accompany or be disseminated over a given nebula or those of a cluster to be delineated and trust to the eye to fill in this skeleton for which purpose perfect fixity of the object in the field of view would be of no importance. I have no expectation that such processes could be applied to the ictual representation of the nebulous parts of such objects so as to give the true forms of nebulæ as they up pear to the eye in the telescope. The visible contour of a nebula

varies from telescope to telescope with the illuminating power of the instrument while that of a photographic impression (supposing one possible) would depend essentially also on the time of exposure which acts in this case as increase of light would do though as it does not follow by any means (and the contrary is even true for bright lights) that (time of exposure) × (intensity of illumination) is proportional to (intensity of impression) there would be no security that the gradation of light in the several parts of the impressed image would be preserved as in nature

On the other hand I have no doubt that satisfactory photographic images of clusters of stars or the stellar assemblages in nebulæ may be obtuned and multiplied and become most valuable aids in the depiction of the latter class of objects. The telescope ought there fore to be provided with fit and convenient attachments for the ne cessary photographic apparatus and the observer should be an expert

photographer

Whatever may be done in the way of delineating the forms of known nebulæ the discovery of new ones by zone observations, whether conducted by meridional sweeps or by the application of the equatorial motion as well as the revision and perfecting of the places assigned to those already catalogued in short the formation of a complete catalogue of nebulæ ought to form a leading feature of the ob civitions to be made with such an instrument and a large portion of the stocl work of the establishment

As the construction and working of the telescope must be experi mental in great measure I should regard a rehearsal of the observa tions in England as a quite indispensable picliminary to their ulti mate prosecution in the Southern hemisphere It is quite of equal importance to place on official record exact delineations and cata logued places of northern as of southern nebulæ The accuracy of such delineations could be tested on the spot, and officially reported on by a Committee appointed for the purpose and confidence thus secured to the results subsequently obtained out of the reach of such a check In a word the northern hemisphere should be first dealt with and that completely and effectually and in the process and within reach of amendment the whole course of pro ceedings might be perfected and the necessary experience acquired Five years devoted to this (of which the two first would be chiefly occupied in roughing out the work and getting the apparatus in trim and the three last in a complete resumé) in the clear climate of the south east of England would be time excellently well bestowed and would shorten the period to be spent in the south

> I remain my dear Sir Yours very truly

J F W HERSCHEL

I homas Bell Esq

Di Robinson to Mr Bell

Observatory Armagh April 10th 1853

SIE

I have received from Mr Weld a portfolio containing the Corre spondence of the Telescope Committee with a request that I would transmit to you any remarks which occur to me from its perusal These relate to the construction of the telescope its mounting and its site Before entering on them however I must express my belief that the opinion expressed by several members of the Com mittee as to the difficulty of making a 4 feet reflector is exaggerated I have seen so much of Lord Ro se's operations that I feel autho rized to say this absolutely for a 3 feet reflector with high proba bility for one of four And were the difficulty and the uncertainty even as great as tho e gentlemen suppose that is the strongest reason for pursuing this our purpose It is only by the reflecting telescope that we shall reach the remotest parts of the visible universe There is no likelihood that an achromatic of 3 feet (the equivalent of a 4 feet reflector) will be made in the next century if made it must be of enormously greater cost and will be embarrassed by the evils of flexure and the polarizing action caused by pressure It is there fore specially desirable that the reflector shall be made as perfect as possible and never was a better opportunity offered than now when we shall be authorized to experiment under the guidance of Lord Rosse Sir J Herschel Mr Lassell and Mr Nasmyth

1 As to the telescope I wish to suggest whether it may not be desirable to use Cas egrains form instead of Newtons. No light is lost for M Cullagh and others have shown that the reflexion from metals is less intener at 45° than nearer the perpendicular. I have much experience of it power with 15 inches aperture, and can mention as an important practical fact, that slight errors in the large speculum can be corrected by the small one which is ground and polished on a miniature of Lord Rosse's machine. I his construction has the great advantage of not requiring any apparatus of a complicated character to support the observer and of shortening the tube nearly one fifth.

In reference to the mode of supporting the speculum three methods are proposed. Sir J. Herschel's consists in letting it rest on an elastic bed uniformly bearing it. Lord Rosse bears it by friction balls on a system of equilibrating levers behind and a ring for the edge also connected with counterpoises, and Mr. Lassell applies a second system of levers behind the mirror which sustain it at all inclinations. The first of these is liable to this objection that the speculum cannot be polished on its bed as it must be immersed in water either of the others may be used but I would direct attention to a remark of Lord Rosse's that the speculum may perhaps be calt with ribs at the back so as greatly to diminish its weight. Were the earringed so as to intersect at the points of bearing. I im disposed to think half the metal might be saved.

Sir J Herschel speaks trongly in favour of a skeleton or open

work tube which will both diminish its weight and remove the most injurious of the influence which interfere with the definition of reflectors the circulation of irregularly heated air in the tube. In fact owing to it they never act perfectly except when they are at the same temperature as the external air. If the tube be suspended at its centre of gravity its upper portion has only to bear the small mirror and in the Newtonian the eye piece also so that it needs no great strength and its diminished suiface will give but little hold to the wind

I see no reason why any one diameter of the speculum should be kept always retical but rither the reverse. Whenever the tele scope is vertical all pressure is removed from the edge now on de pressing it if the train is restored to the same point of the edge it is much more likely to produce a permanent change of figure than if

its action is distributed over a wide range

2 As to the mounting I am decidedly for an equatorial and ee no insuperable difficulty in it if according to Lord Rosse's recom mendation we adopt the German construction and possibly also that mixture of cast and millerble non (a sort of steel) which is stated in the Report of the Commission on Railway Structures to be 1/4 stronger than cast iron Sir J Herschel's objections to the constructions proposed by Mr Nasmyth and Mr C P Smyth appear a notice in the Astronomical Society's Notices seems too compli cated to be quite satisfactory and I fear the bar apparatus at the mouth of the telescope would injure definition I may mention in proof of this, that having supported the small mirror of the Armagh Cassegrain by three very thin radial bars at 120° asunder I was obliged to remove them, is the stars were shown with three minute rays bisecting the angles

Mr La scll s opinion is certainly of great weight yet I continue to think that large telescopes should be worked in the open air. I have tried a 15 inch reflector and a 12 inch achromatic thus and also under domes and very much prefer their action in the first case. Nor need there be much apprehension from wind. Mr Cooper's equatorial gives a fair test of this the instrument has its tube half screened by a will above which 13 feet rise exposed to the unbalanced pressure of the blast, but it is very steady even in high wind. Whatever construction be adopted should (if new) be tried

first on a tolerable scale with a working telescope

3 Site—It must certainly be on our own territories unless we reject all past experience. As to latitude I should not like it near the equator we have no information as to the practical worling of equatorials there and I think the circumstances which in Europe make that instrument more liable to unsteadiness than those of altitude and azimuth would tell with more power when the polar axis is nearly horizontal. There also the poles and polar regions of the sky can scarcely be observed. On this account Simla and even Ceylon are objectionable. The Cape is unexceptionable in this respect but both from what is stated by Sii J. Herschel in the preface to his

observations and from the letter of Mr C P Smyth I doubt its fitnes as an observing station for a reflector. In particular the fine dust on which the latter lays so much stress (and which is so widely diffused in Africa that even at 1000 miles from its western shore it falls on ships) seems most inauspicious

I wish we had some precise data to estimate the effect of height the researches of Forbes with which alone I im acquainted refer to solar heat and not to light and do not enable us to separate the absorbing action of vapour and an I am inclined to believe that the first is much more opake than the other and if so elevations of five or six thousand feet are quite unnecessary as the great mass of vapour lies below From observations which I made at Munich (not 1800 feet above the sea) I think that 2000 will be fully suffi cient for I consider it absolutely necessary that an establishment such as we contemplate be easily accessible and within reach of the appliances of civilized life the very expense of its maintenance will be greatly increased if it is fixed on some remote table land or insu lated mountain summit and the rapid communication with astronomers at home becomes scarcely possible In respect to height we must also keep in mind that the region of condensation is to be On the whole I am compelled to think this element of very second rate importance or at least that it ought not to be pre dominant in deciding the question If we wait till we know the ratio of a telescope's performances at the sea side and at 10 000 feet in the same climate and then till we find a convenient moun tun we shall leave the performance of an important duty to an other generation If we can find a climate as good as that of Nice even at the sea side let us take it and I am confident a 4 feet then will do more on nebulæ than any existing achromatic on the top of the Himalaya (if an observer could live and work there) I would however suggest the Mauritius as possibly offering a fivourable I believe the central plateru is about 2000 feet high climate is described as fine and from its position to the east of Africa it will be free from dust.

Before concluding I would direct the ittention of the Committee to a remarkable passage in Sir David Brewster's letter from which it appears that the application which as President of the British Association in 1849. I made to Lord John Russell on this subject never leached him but was summarily disposed of by some irresponsible official. The leson I hope will not be forgotten by any who as the representatives of our great Scientific Societies may have occasion to communicate with Government.

I have the honour to be Your obedient Servant I R ROBINSON

T Bell Esq

Observatory April 29 1853

PS—Regarding the size of the smill mirror in the Cassegrain form—the lowest power that will use the whole pencil of a 4 feet is 220 assuming this and that the operture of the smill mirror and

the hole in the large and the diameter of the field lens of the Huygheman eye piece are the same diameter I find assuming Lord Rosse's proportion of aperture to focal length $\frac{1}{6}$

Field 15' 38"
Distance of mirrors 29 14 feet Focal length of small mirror 8 75 feet

Aperture of it and diameter of hole 0 76 feet=9 15 inches

The diameter of the small mirror in the Newtonian form is only 4 inches but the difference is insignificant in 4 feet and besides the central part of a speculum is in practice not the best

Grubb is grinding a 12 inch achromatic for the Dublin Exhibition but I scarcely think he will be ready with it. I he equatorial for it however is ready and I think no doubt will exist as to its efficiency when it is seen. He grinds the lenses by a new and very simple machine which acts without forming rings on the glass (Andrew Ross signert difficulty) and if it does as well for specula will be an advince. I shall be curious to see how this object glass acts if it succeeds there is some probability that he will try even larger sizes. But the two glass discs alone for a 24 inch would cost £1000.

E J Cooper, Esq to M1 Bell

Markree Castle April 29th 1853

SIR

I be to acknowledge the receipt from Mr Weld of Dr Robinson's remarks on the subject of the proposed Southern Felescope written after his perusal of the correspondence contained in the portfolio forwarded to me and returned by me to the Royal Society

I have felt very great diffidence in offering any observations on this matter particularly as my acquaintance with reflecting telescope is limited and I have hitherto confined the humble expression of my opinion to that branch of the inquiry relating to the site of the observatory

However as it appears to be the wish of the Committee that each member of it should be consulted I do not thinl that it would be respectful to the Royal Society and British Association were I to withhold any remark that might occur to me So far as I can un derstand the wishes of the Committee they desire—

- (1) A telescope not inferior to a 4 feet reflector to be used principally for the examination and drawing of nebulæ
- (2) The selection of a site on which such a telescope should be placed

The first of these queries involves the considerations —

- a Whether the telescope should be a reflector or a refractor
- b I he mode in which the telescope should be mounted
- c The expense not only attending its first cost but the per manency of its value and also the maintenance of it in work in order together with the establishment connected with it

(1) As regards the selection of the telescope it appears to me that the determination to have one of not le s power than 1 4 feet reflector evinced that the choice of the Committee had fallen upon a reflector in consequence of the difficulty if not impossibility of obtaining a refractor of equal light and this apparent prejudgement caused my original hesitation as to taking any part in the delibera tions of the Committee I am free to confess that I see no prospect whatever of acquiring an object glass affording light equal to a 4 feet reflector even in its mean condition but perhaps I may be excused for making some comparisons between the performances of the two instruments Previously to Sir J Herschel's voyage to the Cape I sent him drawings of the great nebula in Orion and of 51 Messier and in his reply to my letter he stated his belief that his 18 inch reflector had more light than my 13 7 inch refractor but that my refractor must be remarkable for its concentration of This opinion of Sir J Herschel arose from my sletches of the nebulæ having been made under a high power which while bringing into view minute stars invisible with a lower power obli terated at the same time portions of the nebulæ which were seen with Having compared my drawings under a low power a lower power with one he kindly sent me I ascertained that with reference to light the instruments were nearly on a par. In his Cape observations Sir J Herschel mentions his verification there of several minute stars seen by me which his 18 inch reflector had not rendered visible to him in England It would appear from these facts that a refractor giving equal light with a reflector and in juxtaposition with it would show stars better than the reflector. My belief has for i long time been that all nebulæ are clusters of stars and in a great number of them stars are visible. It is of importance to note the position of these stars for the purpose of detecting any dynamical change which may occur in the system of which they form a put The exhibition of the spiral construction in some nebulæ presents a problem of intense interest to the physicist
It remains to be seen whether the practical astronomer will be able to furnish him with any materials towards its solution. The mere outline of a ncb ila will not be sufficient as there might be an absolute permanency of form where the constituent star particle are in constant relative

In point of definition I have always thought that reflectors had the advantage but the drawings of the planet Saturn by Mr Dawes and Mr Lassell respectively (see Ast Nach No 840)—the former by the aid of a $6\frac{1}{5}$ inch aperture achromatic the latter with a reflector of 2 feet aperture—go far to fix an impression on the mind that achromatics at least of moderate size can be procured to exceed reflectors of much higher relative power. It is also worthy of consideration that Mr Lassell himself thinks that if a 30 inch object glass of similar quality to the 15 inch Munich glasses could be furnished completely mounted by any manufactory in the world the bet way would be to give the order it once. I cannot help agreeing with Mr Lassell in this opinion, and am not prepared at

present to say that uch an object glass could not be produced at Munich. But I shall be met here by an objection on the score of the expense even supposing that other objections should be with drawn. Having heard that manufacturers estimate the probable cost of object glasses as the cubes of their diameters, the expense of a 30 inch object glass would no doubt be formidable but we have already an elimate by Lord Rosse for a 4 feet reflector amounting to no less than £6000 and it must be remembered that in addition to this sum for the telescope and its mounting there must be an annual charge a ainst the Ireasury of no slight amount for the salary of the polisher. I would also deferentially submit that the permanency of the value of an achromatic is greatly superior to that of a reflector. I think that it will be admitted that the German mounting of an achromatic of the size proposed by Mr. La sell, would be far less expensive than that of a 4 feet reflector.

Having said thus much on the subject of refractors as compared with reflectors I turn to the remarks made by the several members of the Committee on the proposed 4 feet reflector It does seem to me worth while to con ider Di Robinson's suggestion to adopt the Cassegramman instead of the Newtonian form particularly if the latter should be held to involve the suspension of the observer at the mercy of his assistant I also incline to the opinion of Sir John Herschel and Dr Robin on in favour of a skeleton tube although what the latter gentleman states of my equatorial is perfectly correct I am also strongly in favour of the telescope being used in the open air not conceiving that any astronomer would think of ob crying even under a dome during the prevalence of a hurricane equatorial seems to me to be the only form to adopt with a view to satisfactory observations I cannot help considering photographic representations of the nebulæ as secondary de iderata I fear that only a rough outline could be thus obtained and I doubt much that very minute tellar points in the nebulæ would be distinguishable If my conjecture be correct these pictures would by this process only serve as rough outlines for future work

(2) Site of the Observatory -I have already tated in my former letter that I was disposed to recommend high table land in a lititude as near 45° as possible It is reasonable to demand what has led me to this choice I have myself made observations both on the sea coast and inland in various places in Europe between 67° lati tude and the southernmost part and in Africa as far south as the second catrract of the Nile viz 21° 52' The most favourable places for observation I found to be at Nice on the coast of the Mc diterranean and at Munich Throughout the valley of the Nile the weight of the dews after night fall was so great that even an achro matic telescope could not be used at an early hour In mentioning high table land I had in my mind the position of Munich the ob servatory at which place is 1660 feet over the sea. The sky here struck me to be peculiarly dark much more so than at Nicc and this position has what might be considered a disadvantage ranges of mountains within a short distance I therefore had no idea of ad

vocating a position higher than say 2000 feet and I agree entirely with other members of the Committee in their different objections to a much higher situation. There is one circumstance with regard to a very high situation that does not seem to have been taken into account except impliedly by Dr Robinson viz the effect of the rarefied air upon the observer himself. I have my misgivings as to placing an individual in so different an atmosphere from that to which he has been accustomed. The preservation of his bodily health and consequently his visual capacity is surely of quite as much importance as the perfection of the instrument he has to use So far as I am informed upon the climate and geography of Pasmania I certainly think that it is probable that it would best fulfil the conditions that seem to me to be most desirable as to site

I have the honour to be Sir

Your obedient humble Servant
EDWARD J COOPLE

Thomas Bell Esq &c &c

Mr Arry to Mr Bell

Royal Observatory Greenwich April 30th 1853

My dear Sir

I have received and now return to Mr Weld the correspondence of the Southern Telescope Committee up to the present time. In sending you some remarks in continuation of the same correspondence I cannot avoid commenting on some of the proposals of my colleagues but I trust they will understand that I have no wish to criticise any further than is necessary for conveying my own opinions

I ON THE GENERAL COURSE OF CONDUCT OF THE COMMITTEE

I think that great attention is due to the letter of Mr I assell and especially to his discussion of the question whether the Committee should decide every particular or whether the Committee should give their confidence to an observer who should decide every particular. I certainly incline as I understand Mr Lassell does to the latter course. And this was my feeling when at the Ipswich Meeting of the British Association. I expressed my opinion that no public step ought to be taken till we had decided on the observer. I conceive that all that we can do at present is to collect information to assist the observer, and all that we can do hereafter will be to hear his plans and remark on them, leaving the adoption or non adoption to him, and finally when a scheme is fully arranged to propose it to the Government.

2 I share in some degree with Sir J Herschel the want of very anguine hope of success at least for some time. And I think with

Sir J Herschel that some time ought to be given to trials in

England

3 Lord John Russell's non recollection of the former proposal to which Sir D Brewster and Di Robinson attach great importance was I suppose simply the forgetfulness of one of the ten thousand proposals which come before a Prime Minister—I have not now the British Association papers—but I understood that the Memorial was addressed to Lord John Russell—and in that case (as it was not lo-t) it certainly went to him—and I believe that a reply came from the Secretary of the Freasury—and in that case it was undoubtedly discussed at the I reasury—Board

II ON THE SITE

- 4 The station which appears to satisfy best the desires of some Members of the Committee for table land elevation with south latitude is the Mauritius—But its latitude is low (22°) and this as I understood verbally from Lord Rosse would be very injurious to the observation of South Polar Nebulæ
- 5 As very great importance 1 attached by some Members to the comparatively untried circumstance of elevation I would submit whether it would not be desnable that experiments should be made with a pretty large telescope specially for this purpose. If such a station as is afforded by a Scotch mountain would suffice I would propose the summit of Ben Lawers as preferable to that of any other mountain that I know. The ascent to within 100 or 200 feet of the top is very easy up a grassy slope without bog or erag where a horse and cart could go all the way and there is a comfortable sheltered hollow close to the top in which I found the Ordnance party encamped the last time that I was in Scotland

III On the Telescope and its Mounting

6 In the only detailed plans which have been prepared for the Committee (Mr Nasmyth's and my own) it is proposed that the observer should be suspended to the end of the telescope if New tonian. Some Members consider this likely to cause unsteadiness. It is much to be wished that I ord Rosse would institute decisive experiments on this point.

7 It appears to me very desirable that before we decide on any plan for operations out of England we should determine by experiment in England whether photography can be applied either to nebulæ or to stars. For the special purposes of this Committee as well as for astronomy in general. I do hope that Lord Rosse may be

induced to experiment on this

8 I think that Dr Robinson's proposal of the Cassegrum construction is well worthy of consideration. In reference however to the possibility of photography, I make the following remark (possibly unimportant). Supposing it likely that many photogenic rays might be lost at a second reflexion. I had arranged means in my model for receiving on the photogenic plate the image formed immediately by

the great mirror If this be done with the Cassegrainian the tube cannot be shortened as Dr Robinson propose. Moreover there will be loss of light for the Cassegrain small mirror will probably be larger than the Newtonian small mirror and cannot conveniently be made of silver as the Newtonian can. On the other hand, the Casegrain gives great facility for the location of the observer especially in my plan.

9 In my model I exhibited a gallery or ladder for access to the observer s place if su pended at the mouth of the tube so that there is not really personal danger or risk of being left to perish by

a negligent assistant

10 In deciding between different plans of mounting I attach great importance to the holding the telescope by its end

11 I hould think a skeleton tube with spiral braces very desirable

12 The evidence of Dr Robinson and Mr Lassell seems to show that a 4 feet mirror cannot afely be made with focal length less than 35 feet. This will require serious consideration

13 I think Dr Robinson's remarks are conclusive on the advantage of Lord Rosses mode of supporting the mirror yet I am sorry

not to take Sir J Herschel s

14 Dr Robinson remarks that there is no need to keep the same edge of the mirror downwards and that it may be even injurious As regards the abstract condition of a mirror I have no desire to question this but as regards the inquiry before us I thinl it is founded on a misconception. It is not abstractedly the mirror which Sir J. Herschel and my elf wish to preserve with the same line always horizontal but the apparatus that supports it edgewise. Suppose (as in Lord Rosses and Mr. Lassell's telescopes) the edge of the mirror is carried by a hoop or chain thus



then if the telescope were twisted so that the mirror and its hoop support should be in this state



the definition of objects would be absolutely ruined

15 Dr Robinson has remarked on the injurious effects produced by bars in the mouth of a small reflecting telescope apparently 9 inches aperture. Supposing that in a large telescope the arrange ment of the bars is similar and their thickness proportional then the measure of the diffraction phenomena in angle will be inversely proportional to the diameter of the mirror in linear measure, and thus a disturbance of image which would be extremely injurious with 9 inches aperture, will be absolutely insensible with 48

16 Professor C P Smyth s proposed mounting appears too large

for us to entertain at present

17 I contemplate a telescope in the open air as best

IV ON THE EXHIBITION OF RESULTS

18 I do not dony the importance of Piofessor Smyth's proposal for engraving on the spot but I am far more disposed to encourage the preparation of very careful drawings and trust to fortune for engraving them as far as might be necessary in England

I fear that I have not pre erved very strict order in the airange

ment of my remarks but I hope that they may be intelligible
I am my dear Sir

Faithfully yours

Thomas Bell Esq Secretary of the Royal Society G B AIRY

Dr Robinson to the Earl of Rosse

Observatory Armagh, May 6 1853

My DEAR LORD

I have read the remarks of Mr Airy on the I elescope correpondence and concur entirely with many of them. Others how ever appear to me less convincing and though I feel strongly how weighty his authority is yet as my acquaintance with you has made me familiar with large reflectors and a tolerably long life given me some experience of the ways of men. I submit to you my reasons for questioning in the cases where we differ

1 Mr Airy would appoint an observer and let him decide every particular. Nothing is gained by this but delay. The Committee must fix the nature of the work to be performed they are the proper persons to fix also the means of doing it. Whether achromatic or reflector be used the present Committee possess more knowledge of the subject than can be found in any one person. Let us provide the telescope choose the site and in observer will not be wanting. If Britain cannot fur nish a qualified person let us carry out free trade and seek him at Beilin or Poulkova.

2 Mr A has not very singuine hopes of success. I have and for this reason —your papers show how much a 3 feet adds to the knowledge of the Northern nebulæ which had been obtained by an 18 in, even in (pace diverim!) a bad observing climate. Assuredly

a 4 feet must do more for the Southern in the worst stition than his been suggested

- 3 My reference to Lord John Russell was meant merely as a caution to guard in any future application against irresponsible ad visers of the Minister The Royal Society's and British Association's recommendations should not be disposed of as they were in that instance
- 4 Mr A thinks the Mauritius's latitude too low for South Polar Nebulæ Our primary object is I believe the re examination of Sir J Herschel's Southern Nebulæ Now in his catalogue there are but two whose altitude is under 30° at Mauritius and one at that limit and since your 3 feet is able to resolve part of the Orion nebula (at nearly the same altitude) a fortiors in the finer climate and at the greater elevation of the Mauritius even it would be far more effective
- 5 I like Mr A s notion of Ben Lawers and think it would be a proper object for the Royal Society to examine. The observations should be made at the base as well as at the summit and the test should be the resolution of nebulæ. That of double stars is a different matter being sometimes aided even by fog. But this and similar matters need not delay the construction of the telescope
- 6 Mr A speaks of only two plans for mounting very properly rejecting Mr P Smyths as too vast for us But I think you pro posed the German form and I suggested Mr Cooper's instrument as the model At all events I do so now and think that with the use of Stirling's toughened iron and short bearings it will fulfil all necessary conditions. I may mention that Mr Grubb has one with some improvements in the Dublin Exhibition intended for a 12 inch achromatic of 20 feet focus. It seems very strong and when you (and I hope others of the Committee) see it you will be able to judge whether its type might not be preferable. Experiments on suspending the observer need not delay the preparation of the speculum.
- 7 The same may be said of photography it is not an essential part of the plan and experiments respecting it need not delay the progress of other matters—the effect of metallic reflexion in absorbing the chemical rays may be determined in a day—But I must add that I expect nothing from photography for nebulæ—it may give the places of small stars, but this object can be as well attained by attaching a camera lucida to the eye piece
- 8 In a 4 feet Cassegrain the small mirror should be 9 inches diameter—you I think would make it 4 in a Newtonian. The difference of light is unimportant—I do not know why Mr A thinks the small mirror of the Cassegrain cannot be made of silver—A mere plating is alone required and the curved figure is more easily obtained than the plane
- 10 The end support is good and steady but it remains to be proved that sufficient steadiness cannot be obtained by supporting the telescope at its centre of gravity especially if that centre be brought (as it may by using a skeleton tube) very near the speculum

As far as I can judge from description in Mi Lassell's telescope the centre of gravity is about 6 feet from the end of the box and I have not heard that he complains of tremois. It is however under cover but on the other hand. I should expect the mounting to be as firm as Mi Cooper's

14 The edge support of the speculum which I use and in reference to which my remarks were made is not a semicircle but an entire flexible ring attached to the box by three screws two of which are acting in any position. The action is very satisfactory with 15 inch mirrors. But if Mr Lassell's second set of levers be

adopted the edge support presents no difficulty

Is I have great hesitation in questioning any statement of Mr As about diffraction. Still I would submit to him whether the reasoning in his investigation on the rings (the only one on this subject which I have seen) fully bears out his conclusion that the diffraction of a system of radial bars is inversely as the aperture. The cases are not quite analogous, but in your divided 3 feet speculum, the lines of scpaiation provided every star above the 6th magnitude with a closs and a single packthread across the box of the solid one gave Rigel two tails. You can however easily fix on the 3 feet such a system of bars and try the effect. But even were this objection shown to be invalid. I still prefer the German mounting to that proposed by Mr. A as far simpler.

On the whole then I am more hopeful than Mr A important of the difficulties which he suggests can only be verified by trial and if they be examined fairly will be found not insupe rable if we once set to worl What are these difficulties in compa rison of those which you had to encounter? Have we not the benefit of your experience and may I hope also of your assistance? For I will not disguise from you that I thinl our best chance of success depends on your permitting us to cast and polish the speculum at Parsonstown under your eye and to mount and try it there (a part of the scheme which all seem to think desirable) before sending it to its destination. The mounting can be constructed by any great English machinist and easily forwarded thither and if the Com mittee share this hope and you will consent I am certain that we shall have complete success Of course we should reckon on some preliminary trials as to the form of the telescope and the mounting of the speculum

Believe me yours ever

Γ R Robinson

The Right Honourable The Earl of Rosse

May 11 1853

Memorandum —With respect to the concluding remarks of Dr Robinson I be, to observe that I should be most happy to afford the gentleman engaged in constructing the instrument all the assistance in my power in the shape of information, and also by lending him

any apparatus I might have suitable for his purpose should he think it worth while to avail himself of it. I should not on any account wish to interfere in any other way in the construction of an in trument undertaken by the Government. Besides I think it would be but fair that the gentleman who had undertaken the task should have the whole credit of it.

Rosse

Extract of a Letter from Sir William Denison Lieut Governor of Van Diemen's Land to Colonel Sabine dated Jan 21 1853

Capt Kay has just sent me a copy of his orders from the Admi ralty to break up the magnetic observatory at this place and return to England unless indeed I would take the instruments and appoint an observer to carry on such observations as might be de irable now I am most anxious to maintain an observatory here even for the moral effect it would produce were there no special material be nefits to be derived from it but when I see that in your address to the British Association you laid great stress on the establishment of an observatory in the Southern Hemisphere I have great hopes that I may reckon upon your support to a proposition which I have made to the Secretary of State to keep up and extend the present obser vatory We want a fixed point with which to connect our triangu lation which may be carried across Bass's Strait and along the coast of New Holland so as to determine hereafter the length of an Arc of 20° of latitude and upwards we want means of determining our time and of rating chronometers for our shipping in which the Colony has a great interest I have the means of erecting cheaply all the buildings which might be required and the cost of establishing an observatory would not be much I have therefore accepted the offer of the Admiralty and have appointed an assistant to take such magnetical observations as Capt Kay may think desirable and I trust that you will exert your influence to make the establishment as perfect as possible

(Signed)

WILLIAM DENISON

Dr Robinson to Colonel Sabine

Dublin June 30 1853

I have communicated with Mr Glubb as to his undertal ing the construction of a 4 feet Reflector and after discussing with him the whole matter I think that he will be quite able to do it. With the exception of Mr Nasmyth, who at present is too deeply engaged to wish to attend to such a task I know of none at all so likely to succeed in this work as Mr Grubb especially if assisted by Loid Rosse's counsel and piesence at the casting of the speculum. His premises are large enough to permit the instrument to be mounted on them, and he has a lather of sufficient power to form the 4 feet

tools and the axis of the equatorial He would make this after that modification of the German plan which has been tried by Mr Cooper on one of his own of which he will have a model ready when Lord Rosse comes to Dublin In casting the specula he would leave a small aperture in the centre to try them as Cassegrains which will not interfere with their employment as Newtonians but which can be enlarged to give the full field if the former construction be pre-In that case he would make the small mirror spherical as more easily repolished if made of silver and correct the larger one to it As to costs he thinks the instrument two specula a polishing machine and one horse power steam engine could be furnished for As however several things must be experimental I think it would be safer to ask for Lord Rosses original sum of £6000 with the understanding that the expenditure should be kept as low He thinks also, that with Lord Rosse to refer to in case of difficulties the work ought to be completed in a twelvemonth from its commencement the chief doubt being the loss of a month s annealing in case the first casting fuls Of this from my acquaint ance with Lord Rosse's proce s I have little fear

I would urge strongly on the Committee the propriety of making this offer of Mr Grubb the base of their application to Government if he be placed under the supervision of a small committee of practical men with Lord Rosse as Chairman and Treasurei I am con fident he will do the work in a way that will prove satisfactory Mr De la Rue would consent to be joined in this Committee he could also give valuable aid and if the Committee think that I can

be useful I shall be quite ready to assist

While the telescope is in progress the inquiries suggested by Mr Airy and others as to Photography and elevation of site may be instituted and when it is completed it can be tried by the Members of the Committee so fully that we may be sure of its being a per fect worling tool before it leaves the lingdom All this presents no real difficulty and the subsequent urrangements can be easily settled

Yours ever

T R ROBINSON

Mr Nasmyth to Mr Bell


Tueside Patricroft July 2 18.3

Sir

I much regret that it will not be in my power to be present at the

meeting of the Telescope Committee on the 5th July

Since I addressed the Earl of Rosse on the 15th and 30th De cember 1852 I have had the subject of the most suitable mounting for this great instrument often before me and have endeavoured to give it my most caicful consideration. I now send you for the consideration of the Committee, a rough sketch design of a system



of mounting (genuine equatorial) which I feel somewhat confident only requires to be substantially curried out to realize all the objects in view as while possessing perfect equatorial motion it would be found to be quite steady and manageable and by reason of the great simplicity of the entire arrangement it would not in any respect

prove difficult of construction or unduly costly

It will be seen that I have based the entire arrangement on that which Mr Lassell has carried out in his 24 inch Newtonian equa torial reflector the general convenience and excellent performance of which leaves little or nothing to be desired except it be in the increased rigidity of the trunnion standards which in the case of the design now submitted by me to the Committee I propose to form of two half cones of cast iron cast of suitable thickness so as that each be of adequate rigidity a point which, by the form I pro pose to give them will be attuned in a high degree of practical per These two half cones being most accurately fitted to the surface of the great hour circle plate and secured to it with suitable bolts while this same hour circle plate is in lile manner fitted and bolted to the end of the great polar axis cone (which can be made of any required degree of solidity and stiffness) would yield a support to the telescope such as I incline strongly to think could not be surpassed in rigidity by any other arrangement

Adopting in like manner the admirable system which Mr Lassell has carried out of enabling the tube of the telescope to revolve within the trunnion cage so as to enable the eye piece to be kept horizontal or in one constant parallel with the horizon, my favourite plan of suspending the observer s seat to a swivel joint whose centre of mo tion agrees with that of the eye piece becomes a matter perfectly easy to be practically carried out and on this part of the arrange ment I feel no small degree of confidence, that had it only a fair trial the result would in every way confirm the expectations I have formed of it and prove to be in practice the most comfortable and appropriate and in all respects the most convenient system of ob

serving with the proposed great instrument

With respect to the construction of the tube the more nearly we can approach to the skeleton tube system the better so as to get quit of the serious evils which result from currents of air in a close A system of parallel bars united together by cross and cross on right and left hand spiral bars would I doubt not yield a sort of lattice work tube of great rigidity and by permitting a free passage of the external air in a very great measure remove the evils which more or less attend the use of an entire tube The only diffi culty I foresee in the employment of such open work tube is the letting drops of dew fall down upon the face of the speculum must confess I do not very clearly see my way out of this difficulty as the quantity of such water resulting from the dew will be found greater than most persons who have not had experience in open air observation are aware of Were the lattice burs of such a skeleton tube wrapped round with some very bibulous cloth so that the dow might ching to them and be conducted down and out at the bottom end of the tube the ri k of dew drops filling on the face of the

speculum would be very greatly reduced

To return to the question of the rigidity of the proposed system of mounting. As any amount of rigidity and solidity can be given to a polar axis formed as represented in the diawing and the same un limited rigidity and solidity can be given to the great hour circle plate and in like manner the same with respect to the two half or segment cone trunnion standards and as this rigidity will be maintained in every position of the telescope. I feel confident that in that depart ment of the affair there is no need for doubt or hesitation and as the forms of these parts are most easy of production, and can be brought to the highest degree of accuracy of fitting by the most easy and simple class of workmanship. I trust they will recommend them selves to the Committee

The mode which I have indicated of supporting the large end of the polar axis, namely by causing its accurately turned bearing (een at the back of the hour circle plate) to roll and rest on the edges of two anti friction wheels would be as perfect in action as it is simple and easy of execution. This again is one of the arrange ments which I have borrowed from Lassell There are very many minor details which I need not fatigue the attention of the Committee with at present such as the means of giving rapid movement to the tele cope when passing from object to object or when the observer is taking up his position to work on any selected object or on returning to terra firma after a four or five hours spell for if real work is in tended to be done with this instrument the observer would not need to move from he object for the above named time at least but I trust the state of mechanical knowledge of 1853 would supply him with the means of leaving work whenever he desired to do so assistant or no assistant present notwithstanding. As I consider the plan of suspending the observer's seat to the eyepiece part of the tube is one of the grand features of my proposed arrangement I hope the Committee will not cast it aside upon any grounds short of actual experiment

I am Sir yours very respectfully

Thomas Bell, Esq

JAMES NASMYTH

Note—In page 20 paragraph 5 of Printed Correspondence, Sir J Herschel appears to have misunderstood the use and intention of the chain indicated in my first design. The object of the chain and small windlass is simply to bring the edge of the hinged cell up to the face of the end of the tube and I know from practical experience that this is a most handy arrangement. The cell is then made secure to the end of the tube by three or six bolts which maintain its position with the utmost security and correctness. The edge surface of the cell and that of the end of the tube being turned perfectly true all that is requisite to bring the metal into the most perfect adjustment is to tighten up the holding screws which secure the contact of the edge of the cell with that of the end of the tube

William Lassell, Esq to Mr Bell

Starfield 2nd July 1853

DEAR SIR

I regret that having only just returned home after my long absence I cannot with any measure of convenience attend the meeting of the Telescope Committee on Tuesday next A perusal however of the correspondence upon the subject has induced me to

offer you a few comments

Is Malta altogether out of the question? 1 With respect to site Down to 30° south declination all objects can be advantageously observed there in respect of position and as regards climate I fear a statement of the bare truth might be thought extravagant experience of the Multese sky compared with the published reports of that of the Cape lend me to conclude that the quantity of clear atmosphere in Malta is much greater and that the quality of it generally is at least equal to the best it the Cape As a lengthened trial of the telescope in England has been suggested might it not be removed to Malta? and it desirable afterwards to observe the stars down to the South Pole it might be removed to the Cape Supposing the instrument once perfect and satisfactorily mounted its transit would present no very formidable obstacle

The comparative merits of glass and metal especially regard ing permanence I have no doubt the latter can now be made is durable as the former in support of which I mention the following My two foot speculum I have within the last day or two replaced in the tube in apparently as perfect a condition of lustre as well as figure as when taken out for its journey to Malta has of course been packed and repacked and has undergone two voyages and various cartages and transhipments beside several months exposure in active service under a roof not perfectly tight and which was not able to defend it absolutely from spray during heavy storms of wind-nor from the elmost incredible deposition of moisture during the occasional visits of the Sirocco Merz's prism of heavy flint glass though never exposed except during observation an acute eye may detect some slight deterioration of the surface so that in fact the metal seems at least as invulner Io ensure this property however of the metal able as the glass the alloy must be carefully compounded by an assaying process before the casting is made

3 It would certainly be well to have a skeleton or open work tube but I do not think that the centre of gravity can therefore be got any nearer the speculum end of the tube The skeleton tube to be stiff enough will probably weigh as much as a continuous one of

sheet iron

4 In common with others I have frequently observed that the sky is not unfrequently in a very fine state when the wind is so high that observation without a roof is impossible and therefore I think a dome should be contemplated Indeed the action upon the observer of even a moderate breeze especially if at all fitful is too disturbing for delicate work By leaving an opening between the top of the

circular wall and the bise of the dome for the au but not for the weather and by making the quadrantial opening sufficiently wide the atmosphere within will be I believe sensibly free from current

and as uniform in temperature as without

5 M1 Cooper's conclusion from the very similar pictures of Saturn made by Mr Dawes and myself that the telescopes must be nearly equal in efficiency is a very natural one if drawn solely from the exhibition of this object I would however remark that the planet Saturn is perhaps of all objects in the heavens that which is most favourable for the achromatic and least so for the reflector M1 Dawes's telescope I believe every perfection exist which can be included within its dimensions and the observer the whole world knows cannot be exceeded Saturn is o bright an object that where definition is perfect the magnifying power may be carried on very disproportionately especially if some care be taken to pie serve the sensibility of the eye even until there is only just light enough left to discern the phenomena and in this way the disturb ance of the air is reduced to a minimum Mr Dawes has occasion ally used with advantage a power of 585 my common observing power being 650-not proportionate to the illumination atmospherical disturbances if according to the area would be as 57 to 4 against the reflector and on such an object would o increase by further magnifying power that no advantage would be gained by applying it Refrictors supposed equally perfect will always have the advantage over reflectors of equivalent light because the area exposed to atmospheric disturbance is less. The limited size of the former however soon places them hors de combat compaison of the two telescopes in question be made by directing them to other objects than Saturn such as Ulanus and Neptune with their satellites or the most difficult double star e g γ and η Coronæ δ Cygni ω Leonis &c their performances will be much more nearly in the ratio of their dimensions

6 Provided the site for the proposed telescope has a latitude not lower than 35°S I have no doubt that it might be well and efficiently mounted on the plan of my large equatoreal It is almost exactly a copy of the mounting of the nine foot equatoreal described in the twelfth volume of the Memoirs of the Royal Astronomical Society As it was constructed for the latitude of $53\frac{1}{2}$ I was a little apple hensive on taking it to Malta and I at first used it there with great caution and had wrought iron braces prepaied before I ventured to turn the telescope six hours from the meridian On careful exami nation however I found these quite unnecessary and very shortly removed them as they interfered with the convenient worling of the Curiosity as well as a desire to feel secure led me to measure the deflection of the uprights when in this position and I found it barely sen ible certainly not a tenth of in inch distance of the centre of gravity from the end of the telescope or the distance of the journals in the upper ends of the uprights from the box or frame in which it turns in other words the weight on the flange of the cone is seven feet. The weight of the telescope tube with its contents as ready for observation including the square

In the use of the telescope in this 10urnals is very nearly a ton trying position there was no sensible tremoi or instability the small amount of flexure which took place the load was evidently far within the breaking weight and therefore perfectly safe axis might very well be only six feet from the end as counterpoises we necessary at the object end to remove the centre of gravity so far as even feet from the speculum The reduction of one seventh of the length of the uprights with the same base would of course add materially to their strength With this alteration I am of opi nion that it would only be necessary to double (generally speaking) the linear dimensions of the parts to produce a mounting quite capable of carrying efficiently a four foot speculum Adopting the cubical ratio and taking the weights of the several parts of my mounting as a standard the weight of the hollow cone or base piece (cast in two parts if needful) would be seven tons and each of the uprights one ton and a half The construction of the uprights as well as the upper part of the cone being on the edge bar principle, it is scarcely possible to say what strain they will not bear if the iron be good and care be taken in the castings that the various parts cool equably To secure this was an important point in the construction of the patterns of the castings of my mounting If it should be thought desnable to consider this plan at all for the great telescope I would suggest some slight variations of form to add to its security but I tear I am prematurely entering too much into detail

7 One word about Cassegrannen My experience is limited to a number of trials of a telescope of this form of $7\frac{1}{2}$ inches diameter and a Newtonian of $7\frac{1}{4}$ inches both my own workmanship. The result was that the Cassegrannan was slightly inferior in light to the Newtonian but was in perhaps the same degree better than when by the substitution of a concave small mirror it was changed to the Giegorian form. On test objects such as engravings and watch dials and sometimes on planets the Cassegrannan especially and sometimes the Gregorian seemed to beat the Newtonian but the Newtonian was always superior with the higher powers and on double stars. As various figures were given to the respective metals (or at least their surfaces were repeatedly changed) with generally the same mean result I attributed the observed difference solely to the construction and not to the workmanship

The application of the system of levers for preventing flexure on edge requires certainly that the same diameter of the mirror be always vertical or nearly so. This is accomplished with perfect ease in my telescope by rotation of the tube on friction wheels in the

square frame carrying the axis of polar distance

With serious feurs of having trespas ed much too long upon your time

I remain deal Sir Very sincerely yours

WM LASSELL

To Phomas Bell Esq Secretary of the Southern Telescope Committee &c &c London

Lord Wrottesley to T Bell Esq

20 Chesham Place July 11 1853

DEAR SIR

It is with great diffidence that I venture to question the expediency of any of the resolutions adopted by my colleagues in a committee so constituted as that which I have the honour of addressing through you. I am well aware that on many of the points referred to their consideration my opinion is entitled to little weight but inasmuch as certain suggestions which I had the honour to make verbally on other branches of the subject with which I am somewhat more familiar seemed to some of my coadjutors entitled at least to be placed on record. I will without further apology venture to state very shortly my reasons for wishing that the Committee had not come to a definite resolution that the speculum of the Southern Telescope should not exceed 4 feet in diameter. I assume the truth of the following propolitions.

1st That it is the duty of the Committee to recommend to the Government the construction of such an instrument as in their judgment is best calculated to effect the object sought to be attained

regardless of the expense

2ndly That the object to be attained is that the Southern Nebulæ should be subjected to examination by instruments as powerful as that by which Lord Rosse has lately so materially advanced our

knowledge of the Northern

The last proposition may be questioned by some but it appears to me that a speedy elimination of the laws which govern these remote and mysterious sy tems is an inquiry well worthy of the attention of philosophers and that its success may greatly depend upon our taking immediate steps for handing down to posterity the forms and other peculiarities of these Southern Nebulæ by directing upon them a telescope possessing the same command of light and all the other advantages which the genius and per everance of Lord Rosse have brought to bear on the Northern I can well believe that uniformity in the means employed in both hemispheres may exercise an important influence on the result. As uming then the truth of the above propositions the speculum of the Southern I elescope should be 6 feet in diameter the objections to this size are—

1st The enormous cost of the original construction

2nd The increased expense of maintaining the telescope in worling order inasmuch as a larger proportion of copper must be used in the casting of the large speculum and this will render it more liable to become tarnished and necessitate more frequent repolishing

3rd The difficulties of mounting so large an instrument

As to the first objection I have already stated that in my opinion it ought not to induce the Committee to withhold from the Government that information which they are most competent to give as to the best mode of accomplishing a great cientific object. As to the second the same principle applies but I would remark that if the Government were zerlously to take the matter up and authorize

experiments to be made and the ingenuity of our artizans were taxed and encouraged to provide an instrument of the magnitude in question it is by no means certain that the difficulty might not be surmounted and a composition discovered as little liable to tarnish as the smaller specula. As to the third objection, we have Lord Rosse's mounting to fall back upon and ingenious as it is who can say that it may not be improved if proper encouragement be held out to makers possessed of zeal leisure and extended experience in their art? On these grounds I am of opinion that either the 6 foot speculum alone instead of the 4 foot should be recommended with the proper estimates of cost or that the recommendation should be framed in the alternative accompanied by detailed estimates for the two sizes.

I remain dear Sir yours truly

T Bell Esq

WROTTFSLLY

At a Meeting of the Committee on the Southern Telescope at the Royal Society on July 5 1853 The Earl of Rosse PRS in the Chair it was Resolved —

- 1 That the Committee approve the proposition made by Mr Grubb contained in Dr Robinson's letter of the 30th of June
- 2 That application be made to H M Government for the necessary funds
- 3 That the Presidents of the Royal Society and of the British Association accompanied by Dr Robinson who was associated with the Earl of Rosse in the former application and Mr Hoplins President Elect of the British Association be a Deputation to communicate with Government respecting the two preceding resolutions
- 4 That the Earl of Rosse Dr Robinson Mr De la Rue and Mr Lassell be a Sub Committee for the purpose of superintending the progress of Mr Grubb's undertaking

THE ROYAL SOCIETY

SUPPLEMENT TO THE CORRESPONDENCE

OF

THE SOUTHERN TELESCOPE COMMITTEE

[Printed by order of the President]

Dr Robinson to Col Sabine

July 28 1853

The copy of the telescope correspondence which you have sent me contains four letters which I had not previously seen those of Mr Cooper Mr Nasmyth Mr Las_ell and Lord Wrottesley On each of the e I wish to make some remarks

- 1 If Mr Cooper had stated that the probable value would be of an achromatic of 30 inches (£9000 for the object glass alone) it would have decided the question, even without considering the exceeding great improbability of such an object glass being obtainable on any terms. I will add that I have reason to believe that there is not existing an object glass of 12 inches and upwards perfectly homogeneous. Nor can I entirely admit that an achromatic is necessarily more permanent than a reflector. Professor Moll told me that a 6 inch Fraunhofer was more tarnished than a 9 inch Newtonian of Sir W. Herschel both being in the Observatory of Utrecht. Besides Mr Lassell's experience. I can state that a Munich prism and a 7 inch achromatic in my possession are both tarnished though most carefully covered up
- 2 Mr Nasmyth's second mounting is very much better than his first one but till has the defect of making the polar axis too long. The method of making the principal bearing of the polar axis run on friction wheels I know will not answer. It will produce what Mr Sheepshanks once called floating motion. Troughton's beautiful Equatorial at Armagh has it that of my 15 inch Cassegrain which was constructed by Mr Grubb as an experimental model of Mr Cooper's had it till the friction wheels were removed, Y s substituted and counterpoise levers applied. In Mr. Cooper's this fact can be

verified any time by increasing the action of the antifriction sector till the axis rests on it alone I may add that Mr Nasmyth makes no provision for counterpoises which however would be found essential

As to the suspen ion of the observer I dislike it very much for this out of many reasons—the observer and his box must weigh at least three cwt—this must produce deflection of the tube—different according to the zenith distance and therefore making the adjust ment of the mirrors vary with that element—An amount of displacement of the small mirror much less than would occur here unless the upper part of the tube be very strong will quite vitiate the instrument's performance

The dew cannot in any case fall on the speculum except near he zenith but I do not see why it should fall I think it more likely to trickle down the bars of the framework Bibulous cloth would I think, stop the air s escape but wire gauze may be substituted if such means prove necessary

3 Mr Lassell's suggestion of Malta would I think be attended with no advantage. The conditions at Hobarton must be nearly similar and the expense of transporting the telescope there not very much greater.

The skeleton tube will have nothing to do except supporting the small mirror and will certainly be much lighter than a tube of such sheet non as must intervene between the great speculum and

declination axis

The composition of the metal is most important but Lord Rosses

arrangements for that purpose are perfect

A dome for this telescope mu t be nearly 60 feet in diameter and I suspect would be a construction of great difficulty and expense If the Cassegrain form be used the observer can as in Mr Cooper's instrument be sufficiently protected by a surrounding screen. The action of the wind on the skeleton part of the tube will be insignificant. I must also repeat what I formerly stated that as a general rule telescopes act better in the open air than under a dome

I can scarcely assent to the opinion that doubling the dimensions of Mi Lassell's Equatorial would give sufficient strength for a 4 feet speculum. The strength of similar constructions is intersely as their bulk the proposed one would therefore be relatively only half as strong and the reduction of the standards would be very

far from compensating this

Kater long since thought that the Cas eginin had more light than the Gregorian. Tully refuted this by constructing a pur of these and a Newtonian of 6 inches. He found they had exactly the same light but that the large mirror of the Cas eginin required a different figure from either of the others. In my 15 inch Mr Grubb made the large mirror parabolic and ground the small mirror to match it. I can use it either as Newtonian or Cassegrain and am certain that the Cassegrain shows minute points—for instance the sixth star of the trapezium in Orion's Nebula—better than the other. I am therefore disposed to think that Mr Lassell had chanced

to match the Gregorian better than the Cassegrain My small mirrors I must remulk were ground on a ministure of Lord Rosse's polishing machine of course with very different proportion of stroke

I do not imagine Mr Lassell's levers of which I think very highly at all require the condition that one diameter of the mirror shall be always in the same vertical plane. In the arrangement of those which I have designed for a large reflector (which I hope to construct) the objection is met by giving them *spherical* bearings in the system of levers used by Lord Rosse which will also reduce them into a very small compass

4 Lord Wrottesley's opinion in regard to a 6 feet telescope is certainly entitled to great weight, and it is not without hesitition that I would suggest my doubts. I think we cannot value the cost as less than in the ratio of the cube of the aperture or about £10 000. This I fear we have no chance of obtaining

Lord Rosses two specula are both by accident a trifle below the true standard I do not attach any importance to this but still cannot speak with the same decided confidence as to the casting

them in the fine alloy as I would of the smaller size

The difficulty in using a reflector caused by the state of the air is as the area of the mirror in any case and (in a close tube) as the depth of air in the tube all which is eddying about. The skeleton tube will, I hope, diminish this last, but still we can scarcely expect the proportion to be less in the six and the four than $2\frac{1}{2}$. How far this may be influential in the finer climate where I hope this instrument will be established. I am unable to say but in Ireland I am sure that there are three times as many nights when a 3 feet can be used with full advantage as a 6 feet.

At the same time I see no objection to giving Government the option and I have requested Mr Grubb to furni h me with an estimate (which of course will be less detailed) for a 6 feet instrument. He sees no difficulties except the far greater uncertainty of

casting and polishing, and the increased expense

I have perhaps given you unnecessary trouble in this long letter but it may not be useless to meet any objections that might arise from the points which I have considered being supposed to pass unanswered Yours ever

T R Robinson

To Col Sabine


[For private circulation only]

THE ROYAL SOCIETY

CORRESPONDENCE

REGARDING

THE MELBOURNE TELESCOPE



CORRESPONDINCE

I General Sabine to William Lassell Esq

Burlington House London October 20 1862

MY DEAR SIR,

I enclose a copy of a despatch from the Governor of Victoria to the Duke of Newcastle respecting the erection at Melbourne of a telescope of greater power than any previously used in the Southern Hemisphere—the despatch with its accompanying papers have been sent by His Grace to the Royal Society with a request that the Piesident and Council will furnish him with a report upon the subject

You will not have forgotten the correspondence which took place in 1852 and 1853 upon the proposition which (being then President of the British Association) I had the honour of milling to the President and Council of the Royal Society, for their cooperation in representing to Her Majesty's Government the importance of establishing a telescope of great optical power in a convenient locality in the Southern Hemisphere. Your own letters formed a very important part of that correspondence and as you may not have copies of them with you I send by the same post which conveys this letter, a printed copy of the whole correspondence.

The Duke of Newcastle's communication will be laid before the Council at its first Meeting after the recess (October 24th). We may confidently anticipate that the Council will entertain the same opinion as that of the Royal Society and British Association at the former period, in respect to the importance of the objects to be obtained by the employment of a telescope of large power in the locality of Melbourne, and that they will also highly appreciate the distinction which the Colony of Victoria will acquire by this act of its Government and Legislature. But you will perceive, by the concluding sentence of the Minutes of the Board of Visitors of the Melbourne.

Observatory it is requested that the Report solicited from the Royal Society may contain 'an expression of opinion as to the most suit able construction of telescope for the purpose, both as to the optical part and to the mounting, together with its probable cost and the time requisite for its completion 'Now these are precisely the points which appear to have occupied the chief attention of those who puticipated in the correspondence of 1852 and 1853 and it is probable that the resolutions which were agreed to at the final Meeting of the

Committee on the Southern Telescope' on July 5 1853 (page 45 of the printed correspondence) may be regarded by the Council as embodying substantially the conclusions arrived at after such long and patient consideration. The summary of these appears to have been that the telescope to be recommended should be a 4-feet reflector with mounting, &c, as recommended in Dr. Robinson's letter of June 30 1853 and that it should be made by Mr. Grubb, under the superintendence of a Committee consisting of the Earl of Rosse, Dr. Robinson Mr. De la Rue, and Mr. Lassell. Mr. Grubb's estimate of the probable cost of the Telescope, two Specula, a polishing Machine, and a one-horse power Steam-engine was £5000 but as several things in the construction were necessarily experimental, it was put at £6000,—Mr. Grubb's estimate of the time requisite for its completion being a twelvementh from the date of commencement

The Council will probably desire in the first instance to learn whether any modifications have taken place in the opinions as to the telescope, &c then entertained by the four gentlemen who were willing to undertake the responsibility of superintendence. As you are at a distance and time is important I have thought it worth while to write in anticipation of such more official communications as may be written after the Council has met. You will probably hear from me again by the next mail but in the mean time Dr. Robinson has requested me to ask you if you have with you an estimate of the

cost of your 4-feet Newtonian with its mounting

Believe me, my dear Sir Faithfully yours

William Lassell Esq

EDWARD SABINE

PS It may be desirable that the person selected to use the telescope at Melbourne (who, I presume, will be Professor Wilson) should be in this country during a part at least of the time in which its construction should be in progress, and that he should avail himself of such opportunities as may be afforded of making himself thoroughly conversant with the methods, &c adopted at your own and Lord Rosse's observatories

Communications referred to and enclosed in the preceding Letter, No I

Downing Street 10th October 1862

SIR

I am directed by the Duke of Newcastle to transmit to you to be laid before the President and Council of the Royal Society a copy of

a despatch from the Governor of Victoria, respecting the erection in Melbourne of a telescope of greater power than any pieviously used in the Southern Hemisphere

It will be seen from this despatch that Sir H Barkly is desirous of obtaining the cooperation of the Royal Society towards effecting this object, and that he would be glad if they would furnish a report upon this subject

His Grace feels no doubt but that the Royal Society will readily do whatever may be in their power for encouraging science in the

Colony of Victoria

I am Su

Your obedient Servant

The Secretary of the Royal Society

T F ELLIOT

Governor Sir H Barkly to the Duke of Newcastle (Copy)

Government Offices Melbourne 23rd July 1862

MY LORD DUKE.

The Board of Visitors to the Melbourne Observatory, over which I have the honour to preside, being of opinion that the project long entertained, of electing in the Southern Hemisphere a telescope of much greater optical power than that used by Sir John Herschel at the Cape of Good Hope, would be materially advanced by an expression of interest and sympathy on the part of scientific men in highland has requested me to bring the subject under Your Grace's society, with a view to its being submitted for the Report of the Royal Society of London and the British Association for the Advancement of Science

I have great pleasure in forwarding accordingly, with the approval of my adviscis, an extract from the Board's Minutes, together with the accompanying letter from its Honorary Secretary Professor Wilson in which the reasons for this step are so fully set forth and the advantages lil ely to arise from obtaining a powerful instrument for this purpose so clearly explained as to leave nothing for me to add beyond earnestly soliciting Your Grace's good offices in the matter

It will be observed that the pecuniary cooperation of the British Government is not applied for but I need hardly say that even the smallest donation from that quarter would much facilitate raising the necessity funds

I avul myself of this opportunity to put Your Grace in possession of the Second Annual Report of the Board of Visitors, from which it will be found that a commencement has been made in the erection of the new Observatory advocated in the Report previously transmitted and I am glad to be able further to state that a sum of £4500 has since been voted by the Legislature for the completion of the requisite buildings

Should it be possible therefore to add an equatorially mounted telescope, the Astronomical Branch of the Observatory will be rendered complete and no greater expense than at present will be incurred for the Staff attached to it

I have, &c,

(Signed)

HLNRY BARKLY

His Grace the Duke of Newcastle, K G &c &c

Professor Wilson to Sir H Barkly

(Copy)

The University Melbourne 16th July 1862

SIR

I have the honour by direction of the Board of Visitors to the Observatories, to forward to You Excellency the accompanying extract from the Minutes of a Meeting held yesterday and to express a hope that you will comply with the request contained in it

Though entertaining no doubt of the importance of the results to be obtained by such a telescope as is recommended or of the conspicuous and creditable position which Melbourne would consequently occupy in the eyes of all persons in Europe who take an interest in Science the Board is desirous of obtaining an expression of opinion from scientific men in England, because it is due to those who may be asked to contribute towards its accomplishment that the importance of the object should be attested by higher scientific authority than the Board can lay claim to because also it considers that every means should be used to obtain, so far as funds will permit, the best instrument which modern skill and recent inventions render possible because finally, the Board feel that whether the cost of the instrument be defrayed wholly or partially by private contributions or a grant from the Legislature, public sympathy will be much more strongly enlisted in its favour by a statement of the interest taken in the matter in Europe and by the approval of the Imperial Government, than by any representation which the Board can make

I have, &c,

(Signed)

W P WILSON,

Secretary to the Board of Visitors

His Excellency the Governor

Extract from the Minutes of a Meeting of the Bourd of Visitors to the Observatories, held 15 July 1862

[&]quot;The attention of the Board having been drawn to the following cucumstances —

[&]quot;I That, as long since as 1849 the facts brought to light by

Lord Rosse's Telescope were judged by the Royal Society of London and the British Association for the Advancement of Science to be so important as to justify them in making an urgent appeal to the British Government for the erection, at some suitable place in south latitude, of a telescope for the examination of the multiple stars and the nebulæ of the Southern Hemisphere, having greater optical power than that used by Sir John Herschel at the Cape of Good Hope which appeal there is little doubt would have been successful but for the Russian war and the consequent expenditure,

"II That since that time, Lord Rosse reports that he has discovered systematic changes in some of the most important northern

nebulæ

"III That the interest and scientific importance of the solution of the problem of their physical structure, as well as the probability

of its accomplishment, is thus greatly increased

'IV That some of the most important nebulæ, and those presenting the greatest variety of physical features in close proximity can be observed only in places having a considerable southern latitude

"V That the geographical position and clear atmosphere of Melbourne render it peculiarly suitable for this work, and that the arrangements already made for the establishment of an Astronomical Observatory on a permanent footing offer great facilities for carrying it on

"VI That, independently of the especial object to which such telescope would be applied an Astronomical Observatory cannot be considered complete without an equatorially mounted telescope of

large optical powers

'It was Resolved .-

"1st That, in the opinion of the Board the establishment of such a telescope in Melbourne would materially promote the advancement of science

"2nd That, before applying to the Colonial Government for any pecuniary grant in aid of this object, His Excellency the Governor be requested to obtain, through the Secretary of State for the Colonies, an expression of opinion from scientific men in England as to the importance of the results to be expected from it, the most suitable construction of telescope for the purpose, both as to the optical part and the mounting—its probable cost, and the time requisite for its completion"

II William Lassell Lsq, to General Sabine, RA

Malta Nov 5 1862

My dear Sir

Your letters of the 20th and 23rd ult reached me by the same mul on the 1st inst and from the former having an extra stump on more than the weight demanded, I presume it must have been intended to come by the previous mail at bears the London Post Mark

of the 22nd The printed copy of the correspondence on the Southern Telescope in 1852 and 1853 which you mentioned having forwarded to me I have not yet received [It has arrived this evening]

It appears to me, however, that the question of the construction of a four foot equatoreal has very much altered in its bearings since the date of that correspondence inasmuch as the problem has been completely solved by the erection of an equatoreal precisely of that size and description in this island. I enter upon the subject with diffidence because I may appear to speak too much of myself, though I may think that good faith and the necessity of the case make it inevitable. I believe that the telescope I have erected is more efficient and powerful and combines more fully the desired qualities of a large telescope, than any which has yet been made

After a year s experience of its use, including some small additions to its apparatus which have been made here I have not become aware of any material errors which have been committed in its construction, nor have any improvements of moment suggested themselves which would greatly add to its convenience Some slight additions or variations I might suggest in the building of another similar telescope but none I believe of very great importance construction of the levers for the prevention of flexure, renders it not desirable to observe more than about 15° north of the zenith, though the mounting is calculated to direct the telescope within a few degrees of the pole and I have not as yet observed (at any hourangle) within 35° of it, principally because the arrangement of the revolving tower does not admit of getting conveniently at the eyepiece in such positions If required to observe there, some iemoveable outrigger to the tower would have to be contrived I found it impossible to get access to the eyepiece near the pole and the southern meridian with equal convenience, and therefore sacrificed the former to the latter

I send you by this mail a lithographic drawing of my equatoreal, should it be thought desirable to adopt its plan (Plate I) It is at least not an untried scheme, and as Melbourne is within 2° of the same latitude as Malta, scarcely any modification would be neces-In answer to your inquiry about the cost, I may say that, including every expense which ought fairly to be charged, it does not quite reach 2500 pounds And this includes steam-engine, grinding- and polishing-machine, casting apparatus observing-tower, and circular railway erecting and dismounting in Liverpool and reerecting here If I were in Liverpool the same thing could of course be done again, and for the same sum and I should be almost tempted (if it were desired) to offer my superintendence as a pure That, however, being out of the question, I should labour of love be glad to furnish any information I possess upon the subject, and to place my plans and drawings at the service (for copying) of any gentleman who may be appointed to superintend and carry out the work And here I venture to repeat the opinion expressed in my letter at page 17 of the Correspondence," that the work must be executed entirely under the direction of a single individual A committee may



determine generally upon the *plun*, but the execution I am firmly persuaded must be confided to one alone. Messrs George Forester & Co. of Vruxhall Foundry, constructed almost entirely the mounting and are I doubt not, still in possession of the working drawings made from my original sketches. The work is of the most substintial and accurate character, fit to endure with reasonable care

for ages I believe I may speak with confidence of the very great efficiency of the mounting for the most delicate worl, such as measuring in position and distance the faint satellites of Uranus, the satellites of Neptune, and the faint neighbouring stars of planetary nebulæ as well as measurements of the dimensions and forms of the latter The micrometer I use consists of thin or rather narrow bodies brass bars, moveable of course in position and distince manage to illuminate without letting any sensible light into the field and it is really a beautiful observation to see Neptune and his conspicuous satellites on the black est field with a power of 1060 while there is abundant light on the bars to allow of their being placed in any required position with respect to the objects to be measured the position and distance are read off at one observation do this with all attainable accuracy tests the driving motion have attempted occusionally to follow a practice I had with the twotoot equatoreal of making the contact more perfect and more enduring by a slight regulited pressure with the fingers upon the tube but I find this instrument too stiff in AR to allow me to do this without a painful amount of pressure and therefore, when necessary I have recourse to the slipping piece This disadvantage in one respect will be thought by some to be generally an advantage, and a very viluible one

The various storys of the tower form each a snug chamber about 1 ft 6 in square in which the observer is protected from the wind or dow though close to the exercise and has his writing or drawing materials on a full tible close to his hand. The sl eleton-tube is a great improvement upon the closed one, and I attribute in a great meisure to this form, the fact that I am very rarely driven to close the observatory from atmospherical disturbance though of course with so lirge a telescope and with high powers some vibiation is always perceptible I tened that this open form of tube would have subjected me to drops of dew falling from the bars upon the minor, and had contrived a means of obviating it but the unnoy ance does not On not more than two or three of the most dewy nights have 1 detected some half dozen drops on covering up the mirror add that if they should remain unwiped they leave no stain allow is so pure that I have as yet detected no indication of tarnish whatever

It is therefore by no me ins necessary to repolish frequently, though there is no reason for hesitation on the ground of risk for with the usual amount of eace in the operation agood and efficient surface, at least may be always depended on. The process when resorted to consumes a day and the operation of taking out one speculum and

putting in another a like period. I may be observing today until midnight, or until dawn with A, and before sunset tomorrow B shall be in its place and ready for observation—the work of two individuals

With respect to permanence of adjustment I have never touched the polar axis screw since it was flist set up nor have any observations sufficed to indicate any sensible error. The inevitable labour of turning so large a telescope about from 3 or 4 hours angle on different sides of the meridian and at various polar distances, with the apparent inutility of such an operation, has prevented my undertaking it since I do not pretend to give absolute places since I have no difficulty in finding any objects I want at once, and since when I want especial accuracy a star from some catalogue and the micrometer enable me to obtain it I believe the defining power is quite equal to that of any two-foot equatoreal, which is more than I expected originally to obtain How well it defines it is difficult to express in words, that can only be I nown by personal examination or perhaps it may in some degree be inferred from the series of drawings of the phenomena of the surface of Mars which I have made during the late opposition I acknowledge however, that I have not been able to do any justice to the number and variety and delicacy of the shades and tracery of his disk. The best magnifying power on fine nights was usually 760

The full time occupied in the construction of my equatoreal was between three and four years—and although much less divided attention might be given to the election of another than I was able to afford I do not think it could be accomplished in less than 18 months even if all went well and much diligence were used. In Mi Grubb's estimate, page 37 of the 'Correspondence' is the status of the observer included and the machinery necessary for placing him conveniently at the eyepiece in all required positions of the instrument? this is a rather formidable part of the work. Does it also include driving motion, and cost of electing for examination and taking

down?

I feel that I need to apologise for the length of this letter from which I ferr you will conclude that I have thought it better to say too much than too little

I have indeed thought it desirable to make the Committee as fully acquainted as I can in a letter with the qualities of the instrument I have put up, and have only to add that if they think it worth while to depute any competent gentleman to come over and acquaint himself with the construction, use, and optical powers of this telescope, I shall be glad to afford him the opportunity of the fullest examination, and to place what information I possess upon the subject at his disposal

Believe me to remain, My deai Sir,

Very truly yours
WILLIAM LASSELI

To General Sabine RA
President of the Royal Society

III The Rev T R Robinson to General Sabine Pres R.S.

October 23 1862

The conviction of the importance of a searching examination of the Southern Nebulæ with an instrument of great optical power, which I expressed in my letter to Lord J Russell (Brit Assoc Report. 1850), has been strengthened by the facts recently observed by D'Arrest and others in the northern hemisphere, respecting the variable character of some of these strange forms and by Lord Rosse's observations lately communicated to the Royal Society. which indicate in a few considerable proper motion and even physical It is evident that in the investigation of such variations changes time is a most important element and future astronomers will look back with unavailing regret to the present opportunity of leaving them so precious a record of half the sky if it be permitted to pass away without results As to the means of carrying out such a survey I am not aware that much can be added to what is contained in the printed correspondence Since its conclusion, Mr Lassell has successfully constructed a Newtonian of the same aperture (4 feet) as that proposed for the southern telescope This shows that there is no special difficulty in such an enterprise either as to the telescope or its equatorial mounting but I retain my original preference for the Cussegiain as for more manageable, and I may add, better adapted to photography The application of silver surfaces to form specul which has been made by M Foucault seems very promising but has not yet been sufficiently tested by experience for me to 1ecommend its trial in a case where failure would not only interrupt our hopes of a great astronomical achievement, but would also probably weaken the efforts of those who are endeavouring to diffuse a taste for science in this prosperous and energetic colony There seems a tinge of exaggeration in the account of the telescope which M Chacoinae is trying that inspires doubt and some un cert unty prevails as to the actual reflective power of the silver film Not have we sufficient I nowledge whether the process which availed to figure a glass disk of 33 inches would be equally successful for one of 18 inches or whether such a disk might not be more affected in its curvitures by changes of temperature than one of better conducting The Fouciult system could easily be adapted to the small mirror or in the Cassegrain (as has been tried successfully) this might be an achromatic combination silvered at its posterior surface But as to the great speculum, I think the usual material is safest at present T R ROBINSON

General Sabine, Pres RS

IV Sir J F W Herschel to General Sabine

Collingwood October 29 1862

My DIAR GINIRAI SABINI,

I have received and carefully read the copy of the correspondence of the present year in the matter of the great reflector for the Mel-

bourne Observatory, and the extracts from the Minutes of the Meeting of the Colonial Board of Visitors of Observatories accompanying your letter In reply to the request contained in your letter, that I should offer such remarks on the subject as may occur to me, I beg to say that my opinion as to the desuableness of such an instrument at that or some other equally well-situated station in the south hemisphere has been of late materially strengthened by the instances of change in the brightness and general appearance of nebulæ in the northern hemisphere which have of late been brought forward and which, in two cases at least, appear to be undeniably authenticated (that of the Nebula M 80, and the last Nebula of Hind) instances I am enabled to add another and if possible more striking example of change which has manifested itself in the great southern Nebula surrounding n Argus In a letter which I have lately received from Mr Eyre B Powell, late Principal of Madras College. (himself a good observer, and who has contributed very valuable observations of double stars and computations of their orbits, and whose statement of what he himself has observed during a continued series of micrometrical measures of the stars around $\tilde{\eta}$ Argus may therefore I conceive, be fully relied on,) he expresses himself to this effect

'One point I consider particularly worthy of attention, viz that while in your diagram of the Nebula the southern end of the curious oval vacuity is clearly bounded it is now decidedly open"

This oval, with its perfectly well mail ed and most completely closed southern boundary. I was at peculiar pains to delineate with the utmost precision and the course of that boundary is marked by the positions of small stars in close proximity to its edge most carefully laid down (vide my account and figure of this nebula in my Cape Observations) and as it seems impossible to east any doubt on so direct and circumstantial a statement as that of Mr Powell we have here an instance of change which must be regarded as perfectly reliable nor can I imagine anything more important to our knowledge of these wonderful bodies than to obtain as early as possible exact delineations of the present state of this and of course of all the other irregularly-shaped nebulæ of the Southern Hemisphere, by the aid of a very powerful reflector

As resaids the general form and construction of the telescope—refering to my former letter of March 1853, printed in the 'Correspondence of the Southein Telescope Committee"—I should continue to insist on the following points there specified, whatever be the construction and mode of mounting viz—Ist The use of a very perfect internal collimator—2ndly The adoption of a skeleton tube—As regards the uniform support of the mirror since it appears to be nown received maxim in the construction of large specula that they must be polished in water, and lying on their backs on the actual system of support which is to sustain them in the tube, this of course puts an end to the idea of supporting them on beds of any clastic material other than metallic and the rusting of steel springs would be fatal to their substitution—But the principle of swing suspension by

a band round the edge to tale off the distorting pressure of the vertical component of the weight on a point or on a small portion of the edge I still regard as most important and indispensable

Dr Robinson I observe in the letter sent me (which I reinclose) continues to recommend the Cassegrainian construction. Its great advantage in shortening the telescope I fully admit, but I continue to regard this as much counterbalanced by the excessive distress caused to the observer who shall have to continue observing for many successive hours with his head clevated to a great angle with the horizon, and in many cases to recline on an observing-chair. I speak from feeling experience of this inconvenience (as contrasted with the comfort of the Newtonian or the front view), and I am persuaded it will act to shorten the hours of observation from merciphysical inability to go on. But I agree with Dr Robinson in deprecating the hazard of an experiment on so great a scale as the construction of a silvered glass large mirror on the principle of Steinheil and Foucault

The only reason which would preatly weigh with me in favour of an equatorial in preference to a meridian mounting is the immense advantage such a telescope would afford for examining the physical construction of comets. In this class of observations, as in that of nebulæ, increase of illumination is the paramount consideration. The difference of appearance of one and the same comet under telescopes of high and low illuminating power must be seen to be duly appreciated. Mr Lassell appears to find his recently constructed equatorial mounting woil satisfactorily, but on this point he will no doubt communicate the result of his own experience.

Finally, if the aperture 4-feet be not already held to be irrevocably fixed upon I should feel hilf inclined to open the question of a 5 feet

for the reconsideration of the Committee

I remain,
My dear General,
Yours very truly,
J F W Herscher

PS Nov 19, 1862 —Since writing the above I have been favoured with the perusal of Mi Lassell's letter dated Nov 5 1862 (and herewith reinclosed) By this I find, 1st, that his system of levers for the prevention of flexure in the mirror does not admit of or at all events renders it undesirable to observe more than about 15° north, i.e., to the polar side of the centh and 2ndly, that the construction of his tower does not admit of getting conveniently at the eyepiece within 35° of the pole

Now these conditions would I four be fatal to the use of the instrument at Melbourne, for the observation of the southern nebulæ. The immediate neighbourhood of the South Pole, indeed, is not rich in objects of interest. There is, to be sure, a faint nebula within half a degree of the pole (h. 3176), but from thence to S.P.D. 9° 59′ (say 10°) (where there is a fine planetary nebula, h. 3241), there occur only five nebulæ, all of little interest. This region then might be sacrificed without material injury. But the two nubeculæ ire

objects of paramount importance and interest. The nubecula major extends from S P D 18° to 24°, or fron zenith dist 28° to 34° and the nubecula minor from S P D 15° to 18°, zenith dist 34° to 37°. The great nebula about η Argus itself is only 31° 13′ from the pole, and passes above the pole at Z D 20° 47′ taking the latitude of Melbourne at 38° S. Unless therefore Mr. Lassell's construction can be so very considerably modified as to allow these objects at least to be observed with every possible advantage, I fear it must be abandoned Indeed I should consider perfect facility of observing up to 10° S P D or Z D 42° south quite indispensable

J F W HERSCHEL

V The Earl of Rosse to General Sabine

Dublin October 30 1862

DEAR SABINE.

I have not received the correspondence from Mr White, but I sufficiently recollect the purport of it. The only change I am aware of, which has since taken place is the construction by Mr Lassell of a telescope similar in aperture, and very similar in mounting to the one recommended.

If M1 Lassell is quite satisfied with his mounting, I do not see why an exact fac-simile of it should not be made. There could not be anything cheaper and although I do not thind differential observations beyond the range of the micrometer could be obtained with much accuracy with it as the position of the polar axis is maintained by rollers, still for work upon the nebulæ it would probably answer sufficiently well. Upon this point as also upon the question of steadiness if there was time it might be well to consult M1 Lassell Mr Lassell, no doubt, as we do has kept his patterns and I am sure would be most happy to lend them. That would save expense

I think it essential that some one should accompany the telescope as a mechanical assistant—he having been the principal operator in grinding and polishing the specula. Some intelligent optical glass-grinder who was sufficiently educated to read and understand all that had been written on the construction of reflecting telescopes would probably answer.

Believe me to be Truly yours

General Sahme

Rossl

VI The Earl of Rosse to General Sabine

The Castle Parsonstown November 9th 1862

DEAR SABINE,

I have read Herschel's letter with much interest and agice with him in everything. The only objection to the increase of size he suggests is the expense, which probably would be more than doubled. Believe me to be

Truly yours

General Sabine

Rossl

VII The Rev T R Robinson to Major-General Sabine Castle Parsonstown Dec 4 1862

MY DEAR FRIEND,

Since my letter to you on the Southern Telescope I have been fa voured by your kindness with a perusal of letters on the same sub

ject from Lord Rosse Sir J Herschel, and Mr Lassell

Mr Lassell's communication is very interesting, as describing his success in constructing and mounting equatorially a four-foot tele scope, which seems a very sood one, and with which he is undoubtedly doing good work. But with the conclusion to which he seems to come, that this construction is the best possible, and should be implicitly adopted, I am not disposed to agree

It seems to me, if I rightly understand your wishes, that it is not our province to decide on any particular construction, but in the first instance to supply the Council with an expression of our general opinion as to the feasibility and great importance of a Southern Reflector and secondly, to give whatever practical information we have acquired since the former Correspondence. This the Council may, if they think it necessary, make the subject of a separate communication to the Melbourne Astronomer but it is, I think, highly inexpedient to bring before public men our discussions as to the best mode of doing the work

In reference to the first of these objects, I think the letters contain all that can be required, but with respect to the other Mr Lassell's letter seems to be liable to several objections, bused on some facts which he mentions and also on the lithograph which ac-

companies it

1 The upright standards between which the telescope turns are weak Mi Lassell has felt this, for there appears a transverse trussing marked removeable, obviously designed to prevent flexure when the telescope is a few hours off the meridian this I fear would be an imperfect remedy. I cannot ascertain from the drawing whether the declination axis is provided with counterpoises and friction—wheels to diminish its friction, but if not it will bear very severely on the flanches of this axis, especially in the position of 6 hours off the meridian. The flexion of these standards may interfere preatly with the adjustments of the instrument of they be not of equil strength.

2 The support of the polar axis on friction-collers at its upper bearings is as Lord Rosse has remarked, fatal to any precise determination of absolute places. Mr. Lassell appears to admit this, but not to think it of much importance, as he can always find an object which he wants, and when preater accuracy is required a star taken from a catalogue with the micrometer will give it. On this I must remark that, in the first place it is not always easy to identify the stars of comparison, and that in nebular work there will be a great waste of time unless the instrument can give position within a small fraction of a minute. Mr. Lassell seems in fact not to have taken much trouble in verifying his adjustments, and explains this by "the inevitable labour of turning so large in instrument about

from 3 to 4 hours' angle on different sides of the meridian and at various polar distances. It may be inferred from this that there is considerable difficulty in moving it. He has stated in the Monthly Notices of the Astronomical Society that the moving parts weigh 12 tons—a large mass certainly, but I think that with proper mechanical appliances its motion should not require such hard work. The counterpoise on the polar axis must make the movement in R more difficult.

3 The tower seems licketty and even dan crous. There may be guards for the observer not shown in the lithograph, but even with them his position in a dark night will be perilous. And as Mi Lassell mentions that with this arrangement he cannot observe within 35° of the pole at any hour-angle, Sii John Herschell's remarks are decisive against it. If in addition to 'the labour of moving the telescope,' the observers have to manœuvre this complicated scaffolding, the most probable result is that it will scarcely even be used except near the mendian

4 Mr Lassell's estimate of £2500 for such an instrument is, I fear, lower than any optician is likely to accept. I understand it to include the telescope, equatoreal, tower, and its railways, steam-engine, machine for polishing and grinding grinder and polisher, with two specula, besides the cost of erecting dismounting and re-erecting. If the specula be of the same proportion as Loid Rosses they will each be 2 tons their raw material will cost £400 and as a commercial speculation, I do not think any one would undertake the risks of casting annealing, grinding and polishing for less than £1000 more which leaves a very small maigin for the rest. But this concerns the Melbourne gentlemen who will of course obtain detailed estimates

5 The report of the action of the skeleton tube confirms Lord Rosses is results from one which he had applied to his three-foot telescope. I send a photograph of this latter, which I consider decidedly preferable from its great mechanical strength and large air-

way

6 There appears to be some difficulty about the levers which equilibrate the mirror in the direction of its plane so that they do not act rightly more than 15° on the polar side of the zenith. This can probably be obviated but I am induced by my own experience (certainly on a much smaller scale) to think that the plan of supporting the edge of the mirror in a flexible metallic in, will be quite sufficient even for one of four feet, and that it should be tried before recourse is made to the more complex arrangement. As to the backsupport, we know that the equilibrated levers used by Lord Rosse work very well but I cannot help speculating on an elastic bedding such as worked so well with Sin J. Herschel and recently with M. Foucault. As it must be water-proof we are limited to some structure of metal combined with caoutchous of to a piston sliding in an air-tight cylinder. For a six-foot speculum weighing 4 tons the pressure on each square inch of such a support is only 2.2 lbs

7 Mr Lassell asks if Mr Grubb's estimate includes a driving-clock, and if he has provided for the status of the observer. The

clock is included, and also a differential hour-circle. As to the other, since the eye-end of the telescope (Cassegrain) travels in a sphere of only six feet radius, an observing chair of simple construction and moderate size is amply sufficient. Lord Rosse has remarked that a skilled mechanic should take part in the polishing and afterwards accompany the telescope when erected at Melbourne. In the principle I fully concur, but perhaps it might be better if the Australian observer himself were to come over, and while the process was soing on, make himself familiar with all its details. The polishing large specula is 'skilled work' of the highest older, and I do not think it can be effectually superintended by a mere mechanic

Sincerely yours,
T R Robinson

Major-General Sabine
President of the Royal Society

VIII William Lassell, Esq, to General Sabine

Malta Dec 1 1862

MY DFAR SIR,

I have today had the pleasure of receiving your letter of the 20th ultimo, enclosing some remarks of Sii John Herschel upon mine to you of the 5th — I avail myself of the Alexandrian mail now hourly expected for a few words in reply

I fully appreciate Sir John's requirements of "perfect facility of observing up to 10°S PD or ∠D 42°S," and proceed to state how, by a slight modification of my mounting, it would be completely

satisfied

By omitting the loose cross marl ed 'removeable" in my drawing, and giving about a foot more length to the wrought-iron supports of the ends of the PD axis, the telescope would have a motion quite up to the pole itself and to ensure the effective action of the levers for horizontal support it would be only necessary when the meridional cenith-distance towards the pole became greater than about 15°, to turn the telescope on its axis 180° by the existing apparatus so that the eyepiece should point westward instead of custward, and bring the tower round to that side It would also be necessary to have a PD are on the western as well as the castern support, with tingent serew and locking upparatus, to which in this position of the telescope, the connecting-rod (being disengaged from its former position and carried round with the tube) would have now to be re-en-Thus the instrument by this slight addition would command equatorially every star above the horizon

To enable the observer to gain access to the eyepiece when the object wis near the pole above or below, it would be necessary to introduce a third rail, the same distance from the outer one which

that is from the inner, and to make the lowest beams of the firme-work of the tower to travel outwards on two pirallel rails extending from the inner rail to the new outer or third inil—thus allowing the framework of the tower to rest at pleusure either, as it now does, on the inner and what would then be the middle rail, or on the middle and new outer rail. This would ensure access to the eyepiece in every possible position of the telescope

Though I have had a very short interval to consider the subject, I feel perfectly satisfied that the above easily-carried-out additions would quite answer the requirements insisted on by Sir John Heischel

I remun,

My dear Su

Very truly yours,
WM LASSELL

General Sabine

IX The Earl of Rosse to General Sabine

The Castle Parsonstown Dec 3 1862

DIAR SABINE,

Dr Robinson has just shown me Mr Lassell's letter of Nov 5 I was not aware that his telescope would not reach the pole Probably it would be sufficient could it be made to do so at moderate distances from the meridian. I am not sure whether I should not be disposed to recommend in the first instance a common cheap wooden stand like Herschel's, or perhaps one on the same principle, but in the more substantial form of our 3-foot telescope. With the lattice tube the wind acts but little upon it. Such an instrument has done good work in Herschel's hands, and with us it is constantly employed in making lunar drawings, the want of an equatorial motion being scarcely felt. In such a case it would be only necessary to send out the specular and even that perhaps would not be necessary, as with a competent person I should think they might be made on the spot

I am only suggesting the cheapest and casiest way of bringing great power to bear upon the objects in the Southern Hemisphere and not for a moment proposing an inferior method of mounting, if the equatorial (the best) can be attained. As to the Casses un form my experience is limited to specula of 18 inches' aperture, and very few experiments have been made with them, I am quite unable to say whether they define as well as Newtonians or not

I have been reminded by Dr Robinson that in my last piper I have omitted to mention a little expedient we have long been in the habit of resorting to, especially in polishing with simple pitch that of raising the temperature of the room, and consequently of the polishing tool, above the temperature of the speculum. In this way the necessary yielding of the pitch is provided for without softening the surface in contact with the speculum. When the process is not proceeding successfully, by then raising the temperature of the room

a few degrees good contact will often be procured, and the disappointment of a failure prevented

This hint may be valuable to persons who have not so much expe-

rience

Believe me to be, Truly yours, Rosse

General Sabine

X The Earl of Rosse to General Sabine

The Castle Parsonstown Dec 9 1862

DEAR SABINE,

I have forwarded Lassell's letter of Dec 1 to Dr Robinson no reason why Lassell's mounting, modified in the way he proposes, should not answer, provided the main supports, which are to be lengthened, are made sufficiently strong-much stronger than they They, in my opinion, constitute the weak part of the are at present They are theoretically weak, and that they have been mounting found weak in practice is evident, as otherwise the moveable bracing would not have been employed The great ment of Lassell's mounting is its cheapness for it is almost all the work of a founder and boiler-maker and at Manchester and Liverpool there are special appliances which make such work cheap In the case of the German type there is much forging, turning, and fitting and therefore there is greater cost unavoidably but where expense is not an object it has many advantages Lassell, I understand, casts his specula at one melting, making use of a bell-founder's cupola, and probably is enabled to procure trained men and every thing necessary (except the mould and annealing oven) at some large bell-founding establishment In that there will necessarily be a great saving Hitherto it has been considered important that there should be two meltings, and therefore to prevent oxidation the melting-pot has been employed instead of the cupola or reverberatory furnace, but Mr Lassell seems to find the single melting sufficient the only object of the second multing is to procure an alloy more dense and more free from pores but that is a secondary object, compared to the all-important one, of eventually polishing the speculum successfully

Believe me to be,

Truly yours,

General Sabine

Rosse

XI Sir J F W Herschel to General Sabine

Collingwood Dec 10 1862

MY DEAR GENERAL SABINE,

I sent the photograph by last night's post, and I now return you Lord Rosse's, Dr Robinson's and Mr Lassell's letters

I concur entirely in the following points —

1 To recommend the supplying of a 4-foot reflecting telescope to Melbourne, the large speculum to be of metal, not glass

2 The mounting to be such as to be efficient for observing any object above the horizon with ease and safety

3 The tube to be a skeleton one

4 The cost, if possible, not to exceed £4500, but not less than £5000 to be applied for, as I really cannot imagine how it can be completed and conveyed to Melbourne and crected there for less than the former sum, leaving any profit to the artist employed

5 That it is very desirable Piof Wilson should come over to look to the construction, and to see the process of polishing and

mode of observing

6 That the means of repolishing the speculum should be fur-

nished

I have read the three letters with all due attention, but after giving every weight to what Mr Lassell says I have still misgivings about the adiptability of the equatorial constitution to the purpose contemplated, and I begin now to lean to the ide i of an altazimuth mounting in wood with a good deal of iron bracing and tying about it—the round motion to be on a circular iron iailway and a system of pushing and pulling screw clamps to tighten up any local looseness of bearing, so as it were to jam the frame in the position it is to have during the observation, and to obviate all lateral totter arising from waiping or shrinkage of wood, or expansion and contraction of I cannot help fancying that an equatoreal so constructed as to pass across the pole would require such a length of support for the declination-axis as to be a fearful element of weakness, considering the enormous weight it would have to bear in all sorts of positions, and with no possibility of counterpoising any part of it quite reconcile myself to the mode of sust uning the observer when the telescope is directed to the zenith Cortainly Mr I assell s tower would have to be advanced bodily on its honzontal bar supports in a way and to an extent that I should not like to depend on

Now in an altazimuth mounting on my father's principle, with addition of a framework for the counterpoises, there is no more difficulty or discomfort in observing in the zenith, or between the zenith and pole, or at or below the pole, then in any other direction. Any object in any part of the heavens can be equally well observed, and with a little contrivance, a slow inction to follow an object for a reasonable time without moving the framework in azimuth might readily


be devised

Such a mounting would be vory far cheaper than an iron equatorial one (in which assuredly all the parts that are to sustain weights variable in direction ought to be forged in wrought iron with the utmost care). It has been proved efficient for the purposes for which such an instrument is wanted in the southern hemisphere—viewing and delineating nebula and comets, and discovering new nebulæ, &c. It will give places quite satisfying Dr. Robinson's postulate "within a small fraction of a minute" with depend the facility (and that even when so roughly constructed as my 20-foot stand—much more so when executed as works of the kind now are) and by differential observations questions of proper motion, &c. would be

fully within its reach Any how, there must be no daring experi-

ment incurring risk of failure

From Lord Rosse's photograph it would appear that he has adopted M1 Ramage s form of wood-work, in which the lateral stays rest on a short cross-beam, and are much more highly inclined to the horizon than the front and back ladders. This (as I have pointed out in my article on the Telescope in the Cyclop Britannica) is an element of instability, and for a telescope of this size would, I think, be very objectionable. For the foundation frame I should be apt to propose something in the nature of the annexed woodcut, in which the thick



lines represent wood, and the thin iron,—the large frame ABEF ABEF being laid down first, and over it, connected by bolts, but not by any mortising or letting in to the same level, but laid on it, the cross pieces GD, HC of the transverse frame CDGH to support the lateral stays represented in projection by dotted lines, Ga, Ha, Db, Cb, attached aloft to ab the ends of the cross top beam. These cross-pieces with two others, IK JL (equally laid on the lower beams and not under-cut) would form a bed for the rails carrying the lower end of the tube and the speculum—the whole revolving on a circular rail on rollers, and the centre work being connected with the wood frame by an interior iron ring bolted on to all the beams. The whole to be strengthened by diagonal ties of iron ad libitum.

I cannot conclude this without once more expressing my strong repugnance to the Cassegrunian and Gregorian construction on the grounds expressed in my former letter. I feel certain that it would entail the sacrifice of much valuable observation from mere phy-

sical exhaustion in the observer

I remain
My dear General,
Yours very truly,
J F W HERSCHEL

General Sabine

XII The Rev T R Robinson to Major-General Sabine

Armagh Observatory Dec 15 1862

MY DEAR FRIEND.

I send with this a letter from Mr Grubb, in which he has stated some matters which he wishes me to make known to you. He has sent with it a photographic representation of his proposed construction, with references. His wish to make the aperture in the Cassegrain speculum smaller, arises from a desire to lessen the thickness of glass in the field lens of the lowest eyepiece (which he supposed to be 9 inches aperture) and for the same reason he wishes to make the aperture of this lens less in proportion to its focal length than I had assumed namely 0.5. I find that, taking this proportion 0.4, and the focal length of the great speculum 32 feet, the aperture need only be 7.3 inches, but then the field of view will only be 11 instead of 13.9 with 8.11 inches, the aperture which I had proposed

I thank you for the perusal of Sir J Herschel's letter of the 10th inst There is much of it in which I fully concur, but there are

some parts which I think are open to objection

1 Î cannot at all doubt the practicability of equatorially mounting a 4-foot telescope—even if Mr Lassell had not shown its practicability, it is a simple question of engineering—and I am sure any competent engineer, looking at Mr Grubb's photograph—will see at once that it is quite adequate to carry steadily a tube which with its speculum need not be more than 4 tons weight—Mechanically it is far stronger than Mr Lassell's—and, now that Bessemer s steel is in the market by the use of that material in the declination-axis its strength—may be doubled—I may also remark that, though the equatoreal does cross the pole—its declination-axis is of no dangerous length—and seems effectually counterpoised

2 I am at a loss to conceive why Sir J Herschel thinks a Cassegrain or Gregorian will cause such "physical exhaustion of the observer" The eye-end in Mr Grubb's plan moves in a less sphere than that of a 12-inch achiematic and I never heard that the Struves, Bond or indeed any one who uses a refractor, find such a difficulty On the other hand I know by experience that climbing lofty ladders or even walking up and down stairs for a long night's work is really

fatiguing

3 If it were a question between an altazimuth mounting and no southern telescope I would of course accept the former but I think that to adopt it without absolute necessity is a real retrogression which would be bitterly repented especially as we have no reason to suppose that the Melbourne authorities are not disposed to do their work well. Let us not raise up difficulties. It is undoubtedly true that in Sir J. Herschel's hands the 20-foot reflector has wrought wonders but there are few indeed like him, and even he must excuse me for thinking that he could have done still more with it, had its mounting been equatorial. This at least follows from my own expe-

rience On the one hand, I have worked a good deal with Lord Rosse's 3-foot, which is as steady and convenient as anything of the kind can be and with Sir James South's 12-inch achiematic on a good mounting of the same kind on the other, I am familiar with Mr Cooper's great equatoreal and I must say that there can be no doubt as to the superiority of the latter. Had it been altazimuth Mr C could not have published his Lehptic Catalogue for many years to come. I wish also to observe that I do not think a wooden mounting desirable for so large an instrument, even in these chimates it is not durable, and under the hotter sun of Melbourne it would probably be less so nor will wood and iron act well together under extreme changes of temperature

It is obvious that micrometer measures off the meridian have much

difficulty except with an equatoreal

The Cassegram has great advantage over the Newtonian in respect of celestral photostaphy. The image in the focus of the great speculum must be magnified. Now if this be done by an eyepiece there are two cycls. Glass stops a far greater proportion of the photographic rays than a speculum absorbs, and from the wide range of their refrangibility, they cannot be brought to an accurate focus. Quartz lenses would obviate the flist, but not the second. On the other hand, the second speculum of the Cassegram performs the magnifying without any help, and with perfect convergence of all rays to the same focus.

Sincerely yours,
T. R. Robinson

Major-General Sabine

XIII Mr Grubb to Dr Robinson

Dublin Dec 3 1862

MY DIAR DR ROBINSON,

The plans and estimate which about nine years since I transmitted for the consideration of the Committee, at that time formed to report on the erecting of a powerful telescope in the Southern Hemisphere, having had the honour of being approved of by that Committee (although the design was never curried into effect on account of the British Government declining to supply the requisite funds) it seems desirible, now that the same Committee are reconsidering the matter at the request of some of the spirited inhabitants of Melbourne, that I should as the successful projector on the former occasion prepare for laying before the present Committee such data as cheumstances occurring during the interval suggest

I would then first state that nothing has presented itself to induce me to alter even in details the original design, much less to disturb my faith in its entire effectiveness. I have, however, made drawings to suit the latitude of Melbourne, a copy of which on a reduced scale, together with a descriptive reference, I propose shall accompany this

Of the stability of the mounting I apprehend no doubt can arise, while its freedom of motion is ensured by the introduction of that peculiar system of equipoise first introduced in the large equatoreal exhibited by me in the recent International Exhibition will be seen that the inversion of the polar axis in the present design admits of using a comparatively small pivot for the lower bearing while the near approach of the great mass of the entire moving weight to this pivot is most favourable to increased steadiness, and to both ease and accuracy of the movement in A And if it be desired either now or at a future time to erect a telescope of 5-feet diameter (instead of 4-feet) I consider that the sizes given for the equatorial mounting would safely carry the larger telescope It is, however, an error on the right side to have more than adequate strength and stiffness in the mounting, more especially where such extra strength does not involve any undesirable amount of labour, or any extra consumption of time in the required changing of the position of the instrument

Tube —A ventilated tube appears very desirable. The only drawing of one which I have seen (Mr. Lassell's) appears to be hable to considerable flexure—in short—if theory be good for aught, it must have a good deal—to which, and not to its stiffness. I would look to account for the apparent difficulty which I understand to exist of causing a displacement of the image by a pressure by hand at the upper end of the tube the tube probably giving way at that end under the pressure, without causing the other end, including the large speculum, to follow—In the drawing which accompanies this letter I have indicated a construction for the tube viz—'latticed,'' with internal diaphragms, which combines rigidity with lightness and some approach to elegance


Details of focal length —It may seem premature to speak here of these but as some disadvantage has been suggested as pertaining to the use of a small metal of 9 inches diameter (in the 4-feet aperture of the large mirrors), I think it desirable to mention that in adopting the Cassegrain form of telescope, I consider that the focus of the large mirror need not be more than 8 diameters, or say 32 feet, and that in such case the lowest eyepiece may have a sufficiently large field (assuming the pencil it produces to be 0.2 in diameter), the diameter of the small mirror, of the field lens, and of the hole in large speculum being made 7 inches only

The supporting of the large speculum—In respect of this important point, I fully expect it will be found that there is no necessity for incurring the inconveniences and disadvantages of an elastic support. It is I apprehend conceded that the system of equilibrated support, as originally devised by me, is adequate to the support at the bail of the speculum. It appears also to be generally admitted that if the lateral support of the speculum be effected by its being suitably slung.

in an open hoop, or thus , the same part being always below, no flexure is produced. If so, then any plan by which the "suitable"

slinging of the speculum in all positions would be ensured ought to be effective, i e should not induce flexure in the speculum. Now there may be several ways of effecting this but I shall only describe that one which appears to be perfect in principle, and has been quite successful in practice in the case of a rather weak speculum, viz of 20 inches aperture and 1 25 only in thickness

This speculum previously ground to a tolerably true figure on the back with the least possible reducing of its thickness, was next ground true on edge. The speculum being supported on the lever apparatus was ground and polished, and the lateral supporting effected as shown by the annexed diagram —



in which A represents a portion of the speculum B section of a trued ring or hoop havin, 2 diameters internally, the upper or lesser diameter being such as moderately embraced the speculum, 1 single thickness of fine cloth being placed between C a second trued ring attached by screws to the inside of the speculum box, D, and finally trued after being permanently attached to D B is fitted to C not tightly but so as to be free to move up and down and B is prevented from bearing at bottom edge upon C by an elastic medium (or springs) between

This method of lateral support appears to possess the following qualifications —viz 1st It supports the speculum laterally, equally well in every position, and therefore no advantage results from keeping the speculum in the one position, nor disadvantige in rolling it into all positions 2nd Whatever portion of the speculum happens to be above is not in close contact with the surrounding hoop (B), and is therefore free to take its proper bearing on the back levels. while the opposite or lower portion (or edge) of the speculum in pressing upon the ring B discharges that portion of the ring B from contact with C It may be said that although free movement is thus provided for at top and bottom it is not so it the sides, but it must not be forgotten that in regulating the tightness (or looseness) of the speculum in its ring B, and between the rings B and C, we have the power to my desnable extent of keeping the hoop B from pressing upon the sides of the speculum (near its horizontal diameter) and therefore there is no ierson to conclude that this arrangement will not support a speculum laterally in every position of its edge with the same freedom from flexure as the best regulated hoop will in a single position

Subsidiary Apparatus —For the convenient removal and replacement of the large speculum, the apparatus intended to be furnished consists of two strong carriages, each moving on rollers (or wheels) one of these is provided with a fork raised or lowered by a strong screw it is to be applied underneath the large counterpoise the declination-axis being horizontal and left there as a support in the absence of the speculum. The other carriage is provided with a suitable table, also laised and lowered by a screw for supporting the speculum in its box while being either removed from, or attached to the tube of telescope also of apparatus for enabling the observer to reach the eye-end conveniently in all required positions of the telescope


I was surprised to learn that any difficulty had been felt with respect to such and that it could be supposed that a complicated or expensive apparatus was required. The comparatively small distance of the place for the eye from the centre of motion and the convenient height of this centre from the level platform surrounding the instrument are such that for the great mass of observations the eye of the observer when applied to the eyepiece will range within from $3\frac{1}{2}$ to 7 fect from the ground level. For this lange I propose to furnish, first a modification of the ordinary observing chair, and secondly, a carnage on which the aforesaid chair may be placed (run up upon) the carriage to be capable of being laised or lowered while the chair and observer are placed on it and to allow of the observer reclining on the chair or standing, at pleasure and with safety. For the few cases not met by the above, I think that a good step ladder with a safety rail (made on the spot) will be adequate

Hand motions—The large diameter of the telescope would cause inconvenience to the observer in reaching to the edge while the eye is applied to the eyepiece I therefore have planned arrangements for bringing the hand wheels for such motions somewhere between

the eyepiece of the telescope and that of the finder

Estimate—The residents of Melbouine having some time since desired to have an estimate including one large speculum (only) and exclusive of polishing machinery I have estimated for either such, or with the additional large speculum (ad libitum) With respect to the prices named, I desire to make a few observations I should think it impludent on my part to name a sum which would only pay provided every thing went smoothly, and no such thing happened as a failure in the casting or breakage in the completion of the specula and I should think it very indiscreet to name a sum which would curb me in executing the entire in a manner creditable and satisfactory to all concerned including myself. The recent strides in the manufacture of steel would induce me to see how far this substance might be idvantageously substituted (of course not without adding to the expense) in several parts where I had originally intended to use either east or wrought non—for example the declination-axis, and the telescope-tube Another observation I desire to make is that without wishin, in any way to detract from the ments and excellence of the workmanship of Mr Lassell's large equatoreal, of which indeed I have only seen a lithographic drawing and therefore could not





pretend to form an opinion—I say without expressing any opinion as to the workmanship I think that any one at all conversant in such matters may see that the two constructions (viz his and mine) are so entirely different in character that it would be quite impossible to judge of what one could be made for by knowing what the other cost In his instrument the steadiness whatever it may be, is attained by what I would call the brute force of tons of metal in the other no expense is spared to keep down the weight and friction to the lowest If my construction have (as I fully expect) decidedly greater steadiness, and it is moved with one-thirtieth of the force required to move the other, my labour in contrivance has not been in vain should it be put into use

My original estimate was £4500 There are some things now added, and my present estimate will be £3800 for one speculum only and no polishing machinery, or £4600 for everything as before with the present additions. The difference between these two sums, or £800, would scarcely more than cover the actual cost of the items to be furnished for it but it is not until ely that in any case I should find it desirable to cast a second large speculum, and I place the ad-

vantage of taking the second speculum with the customer

Faithfully yours, Thomas Grubb

Rev Di Robinson

References to the lithograph of Mr Grubb's proposed Telescope

A Masoniy (bed above ground)

B B Musoniy (piers)

C Polar axis

D Sector (moved by the clock), 5 feet radius

E Clock (most part imbedded in pier)

I Polir clamp Clamping to polar axis and connected with sector D it F by a differential series for slow motion in A

G II ind-wheel for quiel motion in A it acts by a pair of bevil wheels on a shift near I, having at top a spin pinion working in an internal wheel within the Hour-circle (II)

H Hour-curle, 31 mehes drameter

I Sector for relieving lateral pressure of lower bearing of polar axis its action is adjusted by a seriew acting with the intervention of a spiral spiring upon a sliding piece, in which the pivots of the sector turn

K Roller for relicving literal pressure of upper bearing of polar axis, its lever, weight &c being situate it further side of

DICI

L L Bell-crank &c for icliciting end pressure of polar axis a chain of peculiar construction is proposed for connecting polar ixis and bell-cranl

M Upper end of the lever belonging to the internal system of equiposing apparatus of declination-axis, &c

- N N N Lever, weight, &c, supporting the upper end M of the aforesaid lever
- O One of two levers relieving vertical (or rather polar) pressure of declination-axis
- P One of the two roller-frames connected with levers O,—the other frame (that next the telescope) being hidden by the declination-clamp
- Q A small part (the only visible) of declination-axis

R Declination-circle, 30 inches diameter

S Declination-clamp

T Telescope (tube $4\frac{1}{2}$ feet diameter, 27 feet long)

U Counterpoise V Quick declination motion

W Slow declination motion

X Finder telescope, 4 inches aperture

XIV The Earl of Rosse to General Sabine

The Castle Parsonstown Dec 18 1862

DEAR SABINE,

I return the copy of Herschel's letter of the 10th, and have no hesitation in saying that I fully concur in his six propositions addition I should say that whatever form of mounting may be adopted, provided the instrument is accompanied by some one thoroughly competent to repolish the specula, the results will be important Each form of mounting has its own peculiar advantages and disadvantages and the choice may be made without piejudice, to rest very much on financial considerations Su John Heischel leans to the altazimuth mounting and no one knows better what can be done with it even in its simple form without counterpoises, than he does When thoroughly counterpoised the whole stand moves in azimuth with the hand, and the telescope can be pointed without A rack which gives a slow motion makes the micrometer sufficiently convenient for observations close to the meridian

Su John Herschel suggests more framework and more wheels than we employ to that I see no objection the additional cost would be nothing and as to the additional weight the counterpoise would sustain it at the expense of a little more central friction

Su John Herschel mentions Mr Rammage's stand I have seen it. and a very rickety affair it was The wheels were much too close together, consequently it had but a very small base to stand upon The timber was slight, badly put together and there were no iron knees or iron braces

In the case of a counterpoised stand like that of my 3-foot telescope the principal strain is from the upward thrust of the counterpoise lever which acts upon a ring round the central point and so raises the whole stand leaving no more weight upon the wheels than is necessary to keep all steady

The lateral stays, to which Sir John Herschel alludes, contribute to

resist that thrust, and are not necessary to resist lateral strain, which seems amply provided against by the distribution of the four wheels upon the circular rail, the wide stretch of the ladders at the base, the breadth of the back trussing, the large scantling of the timber, and the iron knees and straps. No gale has ever brought out any symptoms of weakness and even when lifted bodily off the rail by the counterpoise-lever, there is no perceptible change of form. As to Mr Lassell's equatorial mounting, I concur in Sir John Herschel's mechanical objections to it still, considering Mr Lassell's long experience, and the positive way in which he speaks as to its efficiency, I cannot doubt but that with its faults, whatever they may be, it would still do its work in a satisfactory manner

It only remains to consider the German mounting that, I confess is my favourite and were it my own ease to be just commencing work in the Southern Hemisphere I should adopt it if financial considerations did not interfere. The fittings, however should be for the Newtonian as well as the Cassegrain lest the Cassegrain should not define perfectly. Sir John Herschel objects to the labour of observing with a Cassegram, but Stiuve, Bond in fact every one who employs a refractor has the same labour and I am not sure whether moving up and down ladders with all the clothing necessary for a night swork is not more laborious. In choosing between the altazimuth and the equatorial we must recollect that Sir John Herschel has had a life's experience with the altazimuth and that no observer is likely to be able to use it as he did for a very long time.

With the equatorial the work is far easier it will be done much

quicker, and probably much better

Believe me to be, Faithfully yours, Rosse

General Sabine

In consequence of Mr De la Rue's absence from England, the President and Officers were obliged to prepare the draft of their report to the Duke of Newcastle without having the advantage of consulting him

XV Extract from the Minutes of the Council of the Royal Society, December 18 1862

The President and Officers submitted the following Draft of a Report to be transmitted to the Secretary of State for the Colonies in compliance with His Grace's request conveyed in the Letter of Mr Elliot, dated 10th October 1862

- "Report of the President and Council of the Royal Society respecting the proposal of electing in Melbourne a Telescope of greater optical power than any previously used in the Southern Hemisphere
- · 1 The President and Council learn with pleasure that the Board of Visitors of the Melbourne Observatory have proposed resolutions, indicating their sense of the importance of erecting at Melbourne an

equatorially mounted Telescope of great optical power, and that the proposal is favourably regarded by Sir Henry Barkly, Governor of Victoria, and by His Grace the Secretary for the Colonies. In respect to the importance which the President and Council attach to such an undertaking, they need do no more than refer to the fact that in the year 1850 the Royal Society and the British Association for the Advancement of Science presented a joint memorial to Her Majesty's Government, in which they urged the establishment of such a telescope at some suitable place in the Southern Hemisphere. The scientific objects to be attained thereby are so clearly stated in that Memorial of which a copy is enclosed and in the Resolutions of the Board of Visitors of the Melbourne Observatory in July 1862, that the President and Council feel it unnecessary to do more than refer to these documents

"2 Since the presentation of the Memorial of 1850 an equatonally mounted telescope of greater optical power than that then recommended has actually been constructed by Mr Lassell at his own expense in England, and erected in Malta, where he is now occupied in making observations with it we have now therefore in addition to our previous knowledge the benefit of his experience. In referring to Mr Lussell's Telescope, the President and Council wish it however to be understood that they do not conceive that it should necessarily be copied in all respects, and that for the present they think it best to leave the details of construction in many respects

open to further consideration

"3 When the subject was previously under consideration, letters were written to some of the most eminent practical astronomers of Great Britain and Ireland, requesting them to state their opinions as to the best mode of construction—and a correspondence ensued of which a printed copy is sent herewith—After receiving the communication from the Colonial Office of the 10th of last October the President wrote to the four gentlemen who were appointed as a Committee on the former occasion to superintend the construction of the instrument (in case the Government should accede to the request) and also to Sir John Heischel enclosing a copy of the former correspondence, and asking whether their views had in any way changed in the interval—The answers received from each have been circulated among the others as was done on the former occasion, and have in most cases elected additional remuls

'4 Availing themselves of the information thus so kindly afforded them, the President and Council have to recommend as follows regarding the construction of the instrument contemplated

(a) That the telescope be a reflector with an aperture of not less than four feet This is essential as no refractor would have the

power required

"(b) That the large mirror be of speculum-metal Such mirrors can be constructed with certainty of success, and at a cost which can be foretold whereas the recently introduced plan of glass silvered by a chemical process has not yet been sufficiently tried on so larbe a scale as that contemplated

'(c) That the tube be constructed of open work, and of metal Lord Rosse has recently changed the tube of his three-foot altazimuth from a close to an open or skeleton one and it is understood that he intends doing the same with his great telescope Mr Lassell's tube is also an open one, which his experience leads him decidedly to prefer

' (d) The telescope should be furnished with a clock-movement

in right ascension

' (e) Apparatus for repolishing the speculum should be provided

"(f) With respect to the form of reflector to be adopted some difference of opinion exists, as the Newtonian and Cassegramian have each some advantages not possessed by the other. On this point further correspondence appears desirable, but as the main features of the scheme are the same in both cases, there does not appear to be any occasion to wait till this point shall have been finally decided

"5 With respect to the cost, something must depend on the solidity of the construction and the perfection of the workmanship, but if it be assumed that the workmanship shall be of the best description, and the instrument furnished, as seems desirable with polishing apparatus and a second speculum for using while the other is being polished, it is probable that the cost will not fall much short of

£5000

'6 It is estimated that the construction of the instrument will

occupy about eighteen months

'7 It seems highly desirable that the future Observer should come to England during a part at least of the time occupied in the construction of the instrument, in order that he may become thoroughly acquainted with all its details, and especially with the mode of repolishing and also that he may personally acquaint himself with the working are insements followed at the Observatories of the Eurl of Rosse and Mr Lassell who have expressed their willingness to afford him every facility"

Resolved,—That the Draft now read be adopted as the Report of the President and Council, and that the President be requested to transmit the same to the Dul e of Newcistle

Mr De la Rue having returned to England was immediately made acquirited with the previous correspondence

XVI Warren De la Rue, Esq, to General Sabine

The Observatory Cranford Middlesex W Echruary 15, 1863

MY DEAR GENERAL SABINI,

I have read the correspondence in respect of the proposed Southern telescope with considerable interest, and I return it to you under a separate cover

I think that to adopt the altazimuth mounting in the present state of engineering science would be an inexcusable retrograde step As regards the two forms of equatorial mounting submitted for consideration, namely, Mr Lassell's and Mr Grubbs, each presents certain peculiar advantages, and counterbalancing disadvantages is not a necessary consequence of Mr Lassell's plan that the telescope cannot be placed within 30° of the pole, but must arise from faults of construction in the Malta equatoreal, for his two-foot telescope can be placed in a line with the polar axi Moreover, a modification of the observing-tower would render it available for any possible position of the telescope The strengthening cross-piece (the removeable piece) between the uprights on the polar axis would not have been necessary had the mounting been made sufficiently strong Mr Lassell does not go in for great niceties of fitting, hence the remarks in his communication about its forming no part of his plan to determine absolute places I may here add that the necessary play in the supports of the great mirror allows of a minute difference of tilting which is greater in effect than any errors dependent upon flexure or from alterations in the position of the polar axis

I think that it is absolutely essential that a system of supports similar in effect to that suggested by Mr Lassell should be provided. the swinging ring does not prevent the distortion arising from the mirror bending by its own weight, when in any other position than pointed to the zenith In order that the counterbalancing levers should act properly, the telescope must rotate in a cradle so that the same radius may always be in a vertical plane. I have had no experience with the Cassegiainian form of telescope, but can imagine that this form would possibly afford means of correcting the aberrations of the large mirror by changes of curvature in the small mirror. but there would I conceive be a loss of light as compared with the On the other hand the observer would be more conveniently placed for regulating the movements of the telescope and for directing it, although during the actual time of observing he would be placed at a disadvantage in comparison with the user of a Newtonian which is undoubtedly the most pleasant to work with, from the perfect ease of the observer who may sit down in a chair looking straight before him, or at any convenient angle downwards, and is thus enabled to draw in the greatest comfort

Dr Robinson is in error in supposing that the Cassegrain telescope offers advantages for photography the truth being that the second reflecting surface must be done away with altogether and the sensitive plate placed directly in the principal focus of the great mirror. Lessening the time of exposure is of the greatest moment and everything that conduces to that end is of the utmost importance. It is very easy to enlarge the image afterwards latterly I have enlarged my lunar photographs from 1 inch (the size of the original negatives) to 38 inches

A provision must be made for the removal from time to time of the second or small mirror, if it is contemplated to use the telescope for photography Moreover the driving clock will require especial attention it must go smoothly and must be capable of rapid adjustment to lunar,

planetary and sidereal time

Mr Grubb s photograph of a plan for mounting a 4-foot telescope evinces as was to be expected from such a man, considerable originality and engineering ability, and I do not think that the Royal Society could do better than recommend that he be instructed to carry out the work. His estimate is moderate, and I should say that £5000 is a small sum for such an instrument as he would turn out of hand

I may here mention that the only disadvantage of his form of mounting is the impossibility of moving the telescope all round the polar-axis as the supports of the axis would stop it this is very troublesome sometimes. In my own plan of mounting on the German

system this is obviated

As regards the durability of metallic mirrors and the desirability of providing polishing machinery to be sent out to Melbourne I have a word to say My mirror A has been haid at work for nine years, and has been exposed to the destructive vapours of photographic chemicals for five years and a half and is as good as ever it was My diagonal mirror has been at work for fourteen years and although I have three others in reserve I do not consider it necessary to I have tal en the precaution to put boxes containing lime in my tube and those by preventing the deposition of moisture have preserved my mirrors My advice would be let the observer use the telescope and not trouble himself about acquiring the art of figuring mirrois—I defy him to acquire the art in less than from four to five years The possession of a polishing machine will be at first of about the same advantage as the possession of a complicated turning lathe would be to a gentleman desiring to become an amateur Each must buy his experience by trial and failure finest figure may be spoiled in half an hour, and without the necessary knowledge will not be readily regained Even for the most experienced the difficulties of producing critically fine figures are very great

I have had a little experience with a silvered glass mirror of small size by Steinheil. It was placed in my observatory, and care taken of it but in less than two years the silvering underwent a molecular change and broke up into minute scales. I think that glass mirrors should only be used by persons capable of resilvering them, at all events until their very general employment brings about the establishment of commercial facilities for this being readily

accomplished

I have written these remarks hurriedly, but I shall be much pleased to afford any other information which you may think I can furnish from my general experience in making and using reflecting telescopes

I am, yours very sincerely.

-

General Sabine

WARREN DE LA RUE

XVII Sur J F W Herschel to General Sabine

Collingwood February 22 1863

MY DEAR GENERAL SABINE.

I return you Mr De la Rue's letter, which I have lead with much attention

If the equatorial form of mounting can really be rendered efficient so as to carry the telescope up to and beyond the pole and reach every point of the visible hemisphere with safety and comfort, as Mr De la Rue thinls, there is no more to be said. I have still some misgivings, but I have no experience of such heavy mountings,

and in such matters experience is everything

Mr De la Rue's remark as to the play in the support of the great militor is of very great importance e no possibility of avoiding such play. The remedy is clear, and, as I conceive imperatively necessary to be applied, viz the use of a fiducial collimator as used by myself and described in Phil Trans 1833 p 488, and in my 'Cape Observations' Introduction p xiv. I wonder I did not think of insisting on this point in my previous letters on this subject. Of course the mirror must be capable of adjustment to the collimator by screws moveable at any moment by the observer at the eyepiece

I do not quite understand Mi De la Rue's remark on the system of supports for the mirror It seems to me that without a swinging no system of back support can be effectual With it a mechanism would certainly as he states, be required to keep the point

of its suspension in a vertical plane

It is very comfortable and reassuring to have both Mr Lassells and Mr De la Rue's testimony as to the permanence of polish of their specula. This being the case, the observations of the latter on the non necessity (and indeed positive disadvantage) of supplying polishing machinery appear to me worthy of all consideration.

I quite agree with Mr De la Rue in deprecating the idea of adopting silvered glass for the great mirror. It would be a most

hazardous experiment

I remain

My dear General,
Yours very truly
J F W Herschel

General Sabine

XVIII The Earl of Rosse to General Sabine

The Castle Parsonstown March 13 1863

DEAR SABINE,

I enclose De la Rue's and Herschel's letters, which I have read with much interest. As to De la Rue's I perfectly coincide with him in everything contained in the early part of his letter. Our 6-foot milion certainly tilts a little which would vitiate all absolute determination of polar distances without the aid of Herschel's colli-

mating arrangement The tilting affects also Right Ascensions, but in a very slight degree for which the collimator is also the remedy, differential observations of course affording the ultimate check

We have never made any effort to annihilate tilting Mi Grubb's ariangement of the supporting apparatus seems much better than ours with the view to that object. Some inconvenience may perhaps be felt from sudden changes in the position of Mr Lassell's polar axis. We have never succeeded in detecting strain referable to edge-pressure. As to Mi De la Rue's remarks on the durability of mirrors no doubt he is correct if the mirrors are always dry so long as they can be kept dry they are practically everlasting. My experience, however, is, that in the hands of assistants they are frequently wet and I am not sure whether with the utmost care I could take unless I were to resort to some artificial means of keeping their temperature above that of the air, I could secure them from the deposition of dew arising from sudden changes in the con-

dition of the atmosphere while they were unsecured

To employ quicklime in a lattice tube would be out of the question, and in a close tube I have never thought the action would be rapid chough to be effectual From the ascending and descending currents in a close tube I have always thought that the whole air would be so often changed that quicklime would be of no use When the speculum is covered quiel lime is effectual and telescopes under a dome are soldom dewed My remails apply to this climate how it might be in Australia I cannot tell but so long as the speculum preserves a fair polish it would be better not to meddle with it and while I recommend a polishing-machine to be sent out I should be very sorry to encourage its being employed unless when absolutely necessary I should advise also that a small polishingmachine should be sent with two 10-inch mirrors for the astro-This would be a trifle though without nomer to practise upon some instruction in addition to that to be found in books, it might be very uphill worl to acquire the necessary tact to produce a fine speculum still I think machinery affords such facilities that with a little instruction any educated man, with an aptitude for mechanical pursuits, would soon acquire the linacl so far as to succeed moderitcly

> Believe me to be Truly yours Rossr

General Sabine

XIX Warren De la Rue Esq to General Sabine
The Obsorvatory Cranford Middlesex
April 7 1863

MY DEAR GINERAL SABINE

I return you I and Rose's letter which I have read with great interest. I agree with I and Rose that the collimation-apparatus of Herschel would afford the means of obtaining reliable determination.

I cannot but think nations of position by the differential method that Mr Lassell's method of obviating the distortion of the large mirror by edge-pressure is of GREAT value for even in the case of my own 13-inch I have been able to detect a very slight effect in the image when examined by moving the eyepiece in and out of focus when the telescope was placed at different elevations mirror is suspended in a swinging hoop and each point of support (in the system of triangles) has a ball-and-socket joint so that I am suie there is no 'stickage,' but nevertheless there is a slight dis-The mirror is nearly 13 inch thick

tortion of the image I have never worked with a lattice tube, but nevertheless my mirror has become occasionally covered with moisture and I have always managed to get it dry in about half an hour by placing the lime-boxes in the tube and covering up the end Most probably with the lattice tube the millor will become very frequently bedewed and the remedy is not of easy application in such lurge telescopes as that under contemplation yet I think that it would be found to be advantageous to provide means for covering the mirror and making a short piece of the tube closed to contain a lime-box say about 18 inches of the tube, which would be amply sufficient to contain a deep narrow lime-box such as I use consists of an outer vessel which contains an inner perforated vessel holding the lime and consequently a very large drying-surface is presented by the arrangement

I do not suppose that any inconvenience can result in sending a polishing-machine with the instrument but I should certainly feel inclined to discourage its employment on the mirror supplied to the telescope until the operator had fully mastered the art of figuring mirrors by experience on a second mirror which he ought to be able to make equal to the original mirror before he attempts to touch

the latter

Again let me assure you that I am persuaded that the making of the telescope could not be entrusted to a better man thin Mi Grubb and that no one is better qualified than Lord Rosse to advise as to its construction The foregoing remarks are merely put forth as suggestions to be considered with others which will necessarily present themselves to those immediately conceined in the planning out of the telescope which is soon, I hope to prove creditable to the science of Lin land

General Sabine

Yours very sincerely WARREN DE LA RUF

 ${
m XX}$ The Rev T R Robinson to Major-General Sabine, Pres R S Observatory Armagh April 13 1863

My DEAR FRIEND,

There are some points in Mr De la Rue s two last letters on which I wish to make a few remarls especially as to his opinion that it is essential to use Mr Lassell's levels with the great speculum

If it were impossible to obtain good definition with the hoop support, the use of them would be a matter of necessity notwithstanding their complexity bull, weight, and the inconvenience (if applied as by Mr Lassell) of their requiring the ponderous telescope to be turned in its cradle when an observation is made off the meridian But my own experience that of Mr Grubb, of Lord Rosse of Sir John Herschel, of Mr De la Rue himself and even of Mr Lassell (before he contrived this support) prove that exceeding sharpness. capable of separating the very closest double stars that have been observed has been obtained without them Therefore even were the lever arrangement absolutely perfect, the correction of the very slight residual defect which can exist with the hoop support is no equivalent for the evils which I have mentioned as belonging to But in fact they are liable to grave objections, greater far than any which apply to the other They must be very hable to tremors from any vibration of the ground or agitation of the teleand there is a still stronger mechanical objection, that the resultant of the mirror s weight which is parallel to its plane passes through its centre of gravity while the plane of the opposing action of the levers though parallel to the former is distant from it by half the mirror s thickness + the distance of the lever s ends from the back This must produce a transverse strain of a kind most likely to distort the mirror and both Lord Rosse and Mr Lassell have shown that friction on the back (which acts in this very way) does act injuriously

Secondly, I do not think there can be any loss of light in the Cassegrum as compared to the Newtonian. If the small mirrors are of metal in both then, as MacCullagh, Jamin and others have shown the reflexion at perpendicular incidence is greater than at 45° if the Newtonian have a prism, one of the requisite size will absorb more light than is lot in the other telescope if (as is proposed) its small mirror be a silvered achievable which reflects 0 8 of the incident light

Ihirdly I suppose Mi De la Rue's idea of the necessity of lossening as much as possible the time of exposure in Celestial Photography arises from the difficulty of maling the driving-clock let regularly and still more from the motion of the moon and planets in declination. The last suggests the expediency of having a clock applied to the declination movement as to the other the Kight Ascension Clock ought (if it have a proper regulator) to leep a star bisected for several minutes.

With my very limited practice of Photosi iphy it would be rish to controvert the opinion of so would fixed a mister of that ait but I may mention why I had the notion that there would be some advantage in having the original picture as large as possible. I think that there must be a limit as to the least magnitude which can be impressed on even the most sensitive collodion—that for instance, if an apparatus magnifying about 20 times (as is the case with a milion of 10 feet focus when taking a lunar picture) were used to photostaph a set of Nobert's Test lines, very few of the sense would

be reverled The molecules of the sensitive material have a certain size, below which photography cannot go Subsequent enlargement of such a picture cannot develope what does not exist in it Besides, a copy which is enlarged by lenses cunnot be so sharp as one by metallic reflexion. No combination can be so achromatized that a large portion of the most refrangible rays shall not be aberrant, and though the most photographic of these do not go far beyond the line G, yet Dr. A. Miller is spectral show that others to a great distance beyond H have enough of energy to blur an outline. Now as the proposed Cassegian would give an image equivalent to a focus of 156 feet (for the moon 17½ inches diameter) and as the light of a 4-foot mirror will probably suffice for this, I hope it will be admitted that my error is not without excuse

Fourthly I still hold, after considering all that has been said, that a polishing-appriatus is necessary. The first of the two specula would of course be used until it becomes so tarnished as to impair seriously its efficiency. Then it should be changed for the second mirror, and then experiments should be made on repolishing it. As by a recent contrivance of Lord Rosse even a 6 foot can be tested while on the polishing machine these experiments would not interfere with the continuous use of the telescope, and I am confident that long before the second one became unserviceable the first would be again fit for work. But I certainly wish that there should be attached to the instrument an assistant who besides being able to observe, should be already trained to the work of polishing

I hope we shall soon hear from Melbourne and hear good tidings for as Sir John Heischel has well remarked, the days that pass before this survey of the Southern Heaven begins are each an irre-

trievable loss to Astronomy

Sincerely yours, T R Robinson

Major General Sabine, President of the Royal Society

XXI Sir J F W Herschel to General Sabine

Collingwood April 24 1863

My DFAR GINERAL SABINE,

Lord Rosse's letter of March 13, and Mr De la Rue's of April 7, are herewith returned

I am glad to see that it appears agreed, 1st that the collimitor shall be adopted 2nd that a lattice tube shall be employed

I confess I had been astonished to hear that the metal now in use absolutely resisted tarnish. It now appears however that when deaed at suffers. And that it will be dewed whenever during its exposure a change of temperature from cold to warm accompanied with a degree of moisture approaching the dew point happens is certain whether the tube le latticed or not. Therefore I see no help but to send out a polishing apparatus. But then this entails as a necessity that the object of next be a man of slill and

energy giving his whole heart, soul time, and thought to the one great work of using and leeping in order this magnificent instrument 2ndly. That he must learn to polish and must on no account meddle with the great speculum till he has perfectly familiarized himself with the operation of polishing and figuring specula by practice on smaller ones and for this I can hardly believe that a 10 inch size will be large enough. 3rdly. That the great mirror should not be opened even for inspection (further than to be satisfied that it arrives unbroken) till the whole instrument is erected and quite ready for use and that the greatest diligence should be then employed to secure a great haivest of observations while the surface is yet perfect as it is more than probable that the first attempt (and many more) to renew it will prove failures. And this is all that occurs to me on the subject of these two letters

I remain,
Yours very truly
J F W Herschel

XXII Mr Lassell to General Sabine

London July 22 1863

DFAR GENERAL SABINF

On the occasion of my tempolary visit to England I have had the opportunity of looking into some of the correspondence respecting the proposed 4 foot telescope for Melbourne and, in consequence I should be glid to be allowed to state that I do not intend to continue my observations with the telescope of this size now erected in Malta, and described in this correspondence, beyond the period of twelve or at most eighteen months from the present time and that, if this equatoreal should meet the requirements of the Melbourne Committee, I shall then be glad to place it at their disposal

I remain,
My dear Sir,
Very truly yours
WILLIAM LASSELL

General Sabine, R A

XXIII Warren De la Rue Esq, to General Sabrne (Extract)

My dear General Sabine, August 8 1863
While admitting the correctness of Dr Robinson's opinion, "that there must be a limit as to the least magnitude which can be impressed on even the most sensitive colledion," I am able to say that the minuteness of details in astronomical photographs made with a 13 inch reflector is not limited by this cause. In a 4-foot reflector the image would be nearly four times as large, and the structure of the colledion would consequently interfere in a proportionately less

degree with the perfection of the image I therefore urge on the attention of the Committee the advisability of making airangements for the removal of the second mirror and of placing the photographic

apparatus in the focus of the great miiror

My driving-clock will keep the image of a star on the wire of a micrometer for several minutes so that the difficulty in photographing celestial objects does not result in my case from imperfections in the driving clocl—it arises solely from atmospheric disturbances—I am persuaded that the proper direction to be pursued in developing astronomical photography will be to increase the aperture of the instrument in relation to its focal length and to diminish the term of exposure as much as possible by also improving the chemical part of the process

I am, yours very sincerely

General Sabine

WARREN DE LA RUE

[For private circulation only]

THE ROYAL SOCIETY

CORRESPONDENCE

CONCERNING IHL

GREAT MELBOURNE TELESCOPE

PART III

CORRESPONDENCE

I General Sabine, PRS to Professor Wilson

The Royal Society Builington House September 23 1863

MY DLAR SIR

The Council of the Royal Society have ordered the printing of the Correspondence of some of their Members regarding the Melbourne Telescope, upon which their Report to the Dule of Newcastle was based It forms a small octavo pumphlet under forty pages, with lithographs of Mr Lassell's Telescope and its mounting and of Mr Grubb's proposed Telescope and its mounting We shall receive the copies from the piess in ten days or a fortnight, when I shall hope to send you thirty or forty through the Colonial Office for distribution amongst those who you may judge are lil ely to be influential in promotin, so important a matter As I presume Sii H Baikly will have left you for his new Government, I shall send a copy addressed If either the Astronomei (Mr Ellery) or you to him at Mauritius wish for more copies you have only to write for them I do not apprehend that there would be any difficulty in recommending a properly trained and in other respects suitable assistant from this country competent to repolish the speculum in ease of need, and to both drawing the nebulæ and photostaphing (his remuneration must of course be from the Colonial funds) I have heard two persons spol en of cither of whom I should judge would be very chaible,—one is Mr Alexander Herschel a son of Sii John the other is a son of Mi Grubb who would be thoroughly at home in all particulars The estimate which is entertained here of the enormous and increasing wealth of your colony would stand very much in the way of any proposition for supplementing the Col nial appropriation

(Signed)

LOWARD SABINE

II General Sabine, PRS, to His Grace the Duke of Newcastle

The Royal Society Burlington House October 1 1865

MY LORD DUKE

Adverting to the despatch from the Governor of Victoria respecting the erection at Melbourne of a Telescope of greater power than any previously used in the Southern Hemisphere and to the Pepoit thereon furnished at your Grace's desire by the President and Council of the Royal Society. I have now the honour to request your receptance of a copy of the Communications received from the Fellows of the Society who were consulted by the President and Council on that occasion and which have been printed by direction of the Council. Should your Grace be of opinion that copies of these letters might be advantageously presented to those persons at Melbourne with whom the proposition of establishing a telescope of this description originated the Council would be happy to supply Mr. Elliot with as many copies as he should thinled it desirable to send out

(Signed)

EDWARD SABINE
President R S

III General Sabine PRS, to Professor Wilson

The Royal Society Burlington House August 24 1864

MY DEAR SIP

I did not receive your letter written officially as Charman of the Board of Visitors of the Melbourne Observatory until the day after the departure of the Southampton Mail. I hope that I am in time too the Marseilles Mail. You are already in possession of the opinion of those Fellows of the Royal Society who are generally esteemed as most competent to judge on the comparative suitability of Mr. Lassells or Mr. Grubb's Felescopes for the purposes which are contemplated at Melbourne. The opinions are expressed fully and unreservedly and several copies of the Correspondence have been sent officially to Melbourne through the Secretary of State. The decision in regard to the Telescope to be preferred rests and must rest with the Melbourne authorities. All that I am able to say is that I have no reason to suppose that any change whatsoever has tal en place subsequently in the opinions expressed in the Correspondence which is in your hands.

(Sinned)

EDWARD SABINE

At the Meeting of Council October 27, 1864, the following correspondence was presented —

IV Prof I'llrot to the Secr tary of the Royal Society

Downing Street 31st August 1864

SIP—With reference to previous correspondence respecting the large Telescope proposed to be erected at Melbourne. I am directed by Mr. Secretary Cardwell to transmit to you to be laid before the President and Council of the Royal Society, a copy of a Despatch from the Governor of Victoria forwarding a Letter from the Secretary to the Board of Visitors of the Observatory requesting that the thanks of the Colony should be presented to Mr. I assell for the offer, which it appears has been made through General Sabine to bestow upon the Colonial Government, the powerful telescope which that gentleman possesses provided that it be found suitable for the work for which it is required.

It will be observed that the Board of Visitois are of opinion that the suitableness of the instrument can be best determined by the Council of the Royal Society—ind I am to add that Mr Cardwell would be glad to learn that it was in the power of the Council of the Royal Society to accede to the wish of the Board of Visitors

I am, &c

(Signed)

PRID ELLION

The Secretary of the Loyal Society

(Copy)

V Governor Sir C Durling to Mr Cardwell

Government Office Melbourne 22nd June 1864

Sir —I have the honour to transmit herewith the copy of a Letter and Enclosure from the Secretary to the Bould of Visitors of the Observatory requesting that the thanks of the Colony should be presented to Mr Lassell for the offer, which it appears has been made through General Sabine to bestow upon the Colonial Government the powerful telescope which that gentlem in possesses, provided that it be found suitable for the work for which it is required

2 The Bould of Visitois are of opinion that the suitableness of the instrument can be best determined by the Council of the Royal Society of I ondon who have already been good enough to interest themselves in the matter and have expressed their hope that effect may be given to their views on these two points through the medium of the Sceretary of State for the Colonies

3 My advisers concur in the desire entertuned by the Board I have therefore, respectfully to express my hope that you will cause the necessary communications to be made to the Council of the Royal Society and to Mr Lassell, who is I believe a Member of that Association I have, &c,

(Signed) I have, &c,

C H DARTING

The Rt Hon Edw Cardwell, MP &c

(Copy)

VI Prof Wilson to the Chief Secretary

The University June 22nd 1864

Sir,—I have the honour by direction of the Board of Visitors, to forward the enclosed Extract from the Minutes of a Meeting held yesterday on the subject of the Equatorial Telescope officed as a present to the Colony by Mr Lassell, and to request that you will have the goodness to comply with the recommendation of the Board

The first direct intimation of Mi Lassell's liberality was in a letter from Major General Sabine President of the Royal Society of London received by the last mail in which it is also stated that Mi Lassell presents his Telescope only conditionally on its being found suitable for the work for which it is required and on its being actively used

As repaids the first of these conditions, the Board does not possess sufficient information to justify it in expressing an opinion and considers that it will be most in accordance with what is due to Mr Lassell and best for the interest of science that the same Committee of the Royal Society of London which has already til on so active a part in the matter should be requested to consider and decide upon the point

Whatever that deci ion may be however the Board feels that no time should be lost in expressing to Mr Lassell the thanks of the

Colony for his very munificent offer

I have therefore the honour to convey to you the wish of the Board of Visitors that you will have the goodness to acquest his Excellency the Governor to carry out these two accommendations through the Secretary of State for the Colonies

I have &c

(Signed) W P Wilson

Hon Sec to Board of Visitors

The Honourable the Chief Secretary

(Copy)

Extract from the Minutes of a Meeting of the Board of Visitors of the Observatory held June 21st, 1864

Resolved,—1st That the thanks of the Board be given to Mi Lassell for the offer which he has made of his Telescope for the Melbourne Observatory

2nd That the substance of this Resolution be expressed in a Letter to the Honourable the Chief Secretary accompanied by a request that he will forward it through his Excellency the Governor to Mr Lassell

31d That the Council of the Royal Society of London be requested to decide upon the fitness of Mr Lassell's Telescope for the work of this Observatory

(Signed) W P Wilson
Hon See

(Copy)

VII General Sabine to Mr Elliot

Llandovery Sept 26 1864

SIR -Your letter of the 31st of August addressed to the Secretary of the Loy Il Society on the subject of the proposed Melbourne Iclescope has been forwarded to me in the country the Royal Society being at present in iccess I notice this in explanation of the delay which has tal en place in the present reply under these circumstances I have not thought it expedient to incur the loss of time which would be involved in waiting for the re-assembling of the

Council in order to send a more formal reply

The previous correspondence on this subject printed in 1863 contained the opinions of several persons of the greatest experience in this country in the construction and use of large reflectors on the most suitable construction, both as to the optical part and to the mounting of such a telescope for the purposes contemplated at Melbourne together with its probable cost and the time required for its Full descriptions were given of Mr Lassell's reflector, and of one differing from Mr Lassell's in several particulars, which had been proposed by M1 Grubb on a former occasion when the employment of a reflector of great optical power in the southern hemisphere was under consideration. The relative merits of Mr Lassell's and Mr Grubb's telescopes for the requirements of the Melbourne Observatory were most fully and most unreservedly discussed in the correspondence printed in 1863 A copy of that correspondence was presented to Mr Cardwell's predecessor, the Duke of Newcastle and subsequently, with his Grice's approval, several copies were sent to the Colonial Office for distribution in the Colony I have now the honour of enclosing an additional copy for Mr Cardwell's perusal

Viewed simply as a scientific question, few persons after the perus il of the correspondence would, I apprehend, dissent from the conclusion that Ma Grubb's telescope was entitled to a preference for the special locality and purposes contemplated at Melbourne leaving that of Mi Lassell for continued use in the homisphere in which it was constructed either by Mr I assell himself, or by others to whom it should be his pleasure to entrust it But Mr I issell's munificent offer (of which too much cinnot be said in plaise) of freely presenting his telescope to the Melbourne Observatory if it should be deemed by the Visitors of that Observatory is fully meeting their requirements has introduced a new element, vis i monen element into the consideration, and as the question now stunds I apprehend that whitever might be the opinion of the Royal Society or of the Board of Visitors at Mclbourne the decision must remun and should properly test with those who will have to supply the money vir with the authorities and the Icalslature of the Colony

itself

It should dways be borne in mind that with a due regard to the importance of the researches in which the telescope is to be employed at Melbourne, and to the number of years in which it will probably continue in work, the first cost of the instrument itself is relatively of less importance

I have, &c

(Signed)

LDWARD SABINL, PRS

VIII Governor Sir C H Darling to Mr Secretary Cardwell (Copy)

Government House Melbourne August 7 1865

SIR

With reference to your despatch of the 6th October 1864 No 61 I have the honour to enclose the copy of a letter to my private Sc cretary from the Secretary of the Board of Visitors of the Melbourne Observatory, by which you will perceive that the Legislatine have determined upon purchasing a new Equatorial Telescope and that it follows that this Government will decline to avail itself of the generous offer of Mr Lassell to present his Telescope to the Colony

2 As you have been good enough to direct that the previous communications on the subject should be made to Mi I askell by your authority I am perhaps justified in expressing a hope that you will cause an intimation of the final decision in the mitter to be communicated to that pentleman with a renewed expression of the

thanks of the Colonial Government

3 I may tale the opportunity of stating that the sum of $\pounds5000$ has been voted for the purchase of a new telescope I have &c

(Signed)

C H DARLING

The Right Honourable Edward Cardwell, M P

IX Prof Wilson to General Sabine

The University Melbourne Aug 21 1565

MY DEAR SIR —It is with very great satisfaction that I forward to you the following resolutions of the Board of Visitors, adopted on the 15th inst —

I That the President of the Royal Society of London be informed that the Legislature of Victoria has voted the sum of £5000 for the purchase of an Equatorial Telescope one half of which has been already remitted to the Crown Agents in England, and placed at the disposal of Major Paslev, R E for the purpose, and that the Government has placed the correspondence connected with it in the hands of the Board of Visitors

II That the President and Council of the Royal Society be requested to give the Board of Visitors the benefit of their issistance in selecting a maker, settling the contract, and superintending the

construction of the telescope so as best to carry out the recommendations contained in the Report of the Royal Society to the Duke of Newcastle 18th December 1862

III That Major Pasley be requested to place himself in communication with the President and Council of the Royal Society and aft rascertaining their views to enter into such contract as will most effectually carry them out

I enclose also a copy of a letter received from the Treasury on which the foregoing resolutions are based and a copy of the letter

which I send to Major Pasley by this mail

The great interest which you have shown in this matter leads the Board of Visitors to count confidently on your further assistance in bringing it to a successful conclusion. The request contained in the second resolution is not intended to imply that in the opinion of the Board any further discussion as to the form of telescope or the maker is necessary. The Board thinks and I believe that it is also your opinion that the discussion which has already tall en place has settled that question and that Mr Grubb's proposal should be adopted. This is not distinctly expressed in the resolution because Mr Grubb's name is not mentioned in the Report of the Poyal Society, and because the Board desires to leave you free in the event of anything having happened to Mi Grubb, or of any discovery having been made which would tend to modify your opinion.

In any case the Board bearing in mind the great length of time that has chapted since the proposal for a telescope was first made, and having now received authority from the Government to act in the matter, is desirous of securing the completion of the telescope at the earliest possible time consistent with the highest attainable perfection in the instrument and considers that this end will be most effectually secured by leaving you quite free to act in the matter, and trusting to you so secure the cooperation of those eminent practical astronomers whose names you mentioned as willing to superin-

tend the work during its execution

Mr Grubb's last estimate is £4600 for the telescope complete and this I believe covers everything, including the erection in Ireland for a trial

The sum voted is £3000 and the balance £400 will be available for a spectroscope and for a photographic apparatus adapted to the telescope and will still probably leave sufficient to pay the freight to Melbourne. As these two adjuncts will not occupy long in making, it will probably be desirable not to commence them till the telescope proper is approaching completion, so that the latest improvements may be introduced into them

Irusting to your cainestness to induce you to undertal e the great amount of trouble we are imposing upon you,

I remain, my dear Sir,

Very faithfully yours, W P Wilson,

Hon Sec to the Board of Visitors

Major General Sabine, RA, Pres KS

The University Melbourne Au, 21 1800

MY DIAR MAJOR PASTIY,

I have received from the Freisury a letter (No 4265 Au., 11 1865) status, that the Crown Alents have been informed that £2457 135 0d in their hands is to be applied towards the purchase of in Equatorial Lelescope and that the balance, £251275 0d will be forwarded when required. This letter, a copy of which is enclosed also states that it is to be expended under your order and that you have been informed that you will receive further communications on the subject from the Board of Visitors to the Observatory

With reference to this matter I have the honour by direction of the Bould of Visitors to forward to you the following resolutions

of the board adopted on the 15th aust

[The resolutions are the same as in the preceding letter]

To render the present position of the mitter cleu, it is necessity to enter into a biret history of what has talen place You will probably remember that for many years I have been endersouring to induce the Government of Victoria to procure a lurge reflecting telescope to observing the nebul e of the Southern Hemisphere On the 23rd July 1862 at the request of the Board of Visitors Su Henry Bully wrote to the Dule of Newcistle to isk through him i Report on the subject from the Royal Society of I ondon This led to a correspondence amongst those bellows of the Roy al Society best acquainted with the subject in which the form of telescope most suitable for the purpose was fully discussed in all its details and the Report referred to in the second resolution was adopted on the 18th of December and forwarded through the Dule of Newcastle Subsequently Mr W I isself offered his lune telescope is a present to the Melbourne Observatory if it should be found suitable in all points and considerable time was occupied in correspondence on the subject. At list however the mutter has been decided on the recommendation of the board of Visitors the Government placed £5000 on the etimates for a new telescope and the Assembly voted it and half of this sum, which had been sent to England for the alteration of Mr I issell's telescope, is now iv illable

The Government has now inthonical the Bourd of Visitors to communicate directly with the Royal Society and the maler of the telescope in order to avoid the delay of sending the communication through the Governor and the Secretary of State is formerly and the Board relies on your good offices as one of its Members to expedite all matters of business connected with the procuring of the largers.

telescope

The form of the telescope and all details of construction have been so fully discussed by the Royal Society and the superiority of the mounting proposed by Mr Grubb of Dublin has been so clearly established, that little remains to be done besides giving him the

order I write by this mul to General Sabine on the subject, and from the interest which he has all alon, shown in it I am sure he will do all in his power to icheve you of unnecessary trouble. If as I expect, he agrees with me that the Royal Society has practically decided that Grubb's form of telescope is that which should be adopted the best plan will be to set Mi Grubb at worl at once, so that no further time may be lost

I remain,
My dear Major Pasley
Yours very faithfully
(Signed) W P Wilson,
Hon Sec to the Board of Visitors

XI I v Dr Inobinson to General Sabine

North Great Georges Street Dublin Feb 17 1865

My DIAL BRIIND

We had our first Committee Meeting to-day, and I am glad to tell you all went on smoothly. De La I ue is delighted with the details of the telescope, and much pleased with the photographs of which Howard Grubb tool a few in the rare lucid intervals, that have occurred one of which I enclose. He appears also from two stars which we saw to day to think the figure and polish of the speculum very good. To-might promises to be tolerably favourable, and it so, I see no reason why we should not agree on the heads of our keport to you to morrow, in which case I will lose no time in drawing it up and in forwarding it to you. I read Mi Verdon's letter to you it authorizes us to hope that the roof will be made but I must own I have my doubts about the economy of constructing it at Melbourne. In particular the very effective urangement of rollers on which it is proposed it should move will require first rate worl in miship

Yours ever 1 R Kobinson

General Sabine

At the Meeting of Council of the Royal Society, March 19, 1868 the Report of the Committee on the Melbourne Telescope to the President and Council, with a separate Report by Mr Lassell, was presented as follows—

The Committee were informed by Mr Giubb at the close of last year that the Telescope was ready for their final examination but the bad we then which has prevailed in Ireland ever since precluded all trials of its optical power till February 17, when they met at Mr (arubb's works in Rathmines Road

I the I closcope was not finished at the time named in the contract but the Committee have ascertained that the delay arose

solely from unfavourable weather, which not only impeded the actual work of polishing but for weels to ether mide it impossible to test the figure of the specula. They considered that it was far more important to send out a perfect instrument than to leep the exact time

2 The Committee, after minutely and carefully studying the mechanical details of the equatorial have come unanimously to the conclusion that it is a masterpicce of engineering. Its movements are surprisingly smooth and steady it can be moved to any portion of the sky even if it have to be reversed from one side of its pier to the other in less than a minute by two operators and with very little exertion.

The clock is smooth and equable in its action, it is very powerful, and quite equal to its work. Great change of rate, as from sidereal to lunar time is effected by an ingenious piece of differential gearing small changes are made by a cam adjustment moreover it rings seconds for the double object of comparing its rate with a chronometer and to assist the observer in his observations

3 The Committee are strongly impressed by the great convenience to the observer of the arrangements of the hour and polar-distance circles the facility of controlling their adjustment and the

easy access to the evenicce

4 The stability of the tube was severely tested, both in respect of its general stiffness and its power of resisting torsion, such as might be produced by the weight of the small speculum when the Telescope is off the meridian and the results were highly satisfactory

5 In large reflecting telescopes it is usual to male provision for keeping a given diameter of the great speculum always in a vertical plane. When they are equatorially mounted this is done by rotating the tube in its cradle. Here the tube does not turn, but there is a special arrangement of hoop suspension, by which, whatever diameter may be vertical it is supported in a uniform and symmetrical manner. The system of triangular levers it the back of the great speculum is also contrived so as to prevent them from exerting any pressure which might distort it. This is a matter of the highest importance and the attention of the Committee was specially directed to it. They examined it most carefully putting the Telescope in various positions of A and P D on each side of the meridian both by day and night, and could not find any sign of fleavre or any distortion of the image in any of these changes.

6 In order to test the optical power of the second speculum B (the first one A had been tried and approved by a member of the Committee on October 12 last), the Telescope was directed to the following objects —In the daytime Venus and a Andromedæ at night (which fortunately was clear and steady) Castor the Great Nebula of Orion, ζ Orions γ Andromedæ, Uranus, 1 Messier, 37 Messier, 46 Messier, and 51 Messier from which it will be seen that both the light-collecting and defining powers of the instrument were fairly tried. The powers used were 220 (the lowest which

can take in the entire pencil) 350 and 450 all negatives course one would not propose such an instrument for the measurement of close double stars work for which Telescopes such as those of Poulkova and Harvard are possibly better fitted but the Committee found that the light even of large stars was collected into small hard and perfectly encular disks free from rays and though some diffused light* surrounded them it was exactly concentric with the central disl's The 5th and 6th stars of the Trapezium of Otton were not only plainly seen, but were very bright Z Orionis was well shown, and the companion of y Andromedæ was clearly divided with the powers of 350 and 450, and the different tints of the components were evident Uranus was well seen, but was surrounded by such a multitude of very minute stars that without access to the tibles of his satellites it was impossible to know whether any of them were seen † 37 M was broken into a heap of stars so large and brilliant that it quite lost the character of a The planetary Nebula in 46 M brought out most strilingly the light collecting power of this Telescope for it (which in most lelescopes appears as a frint disl) was reverled as a ring bright even on the dazzling ground of the surrounding stars which here were as brilliant as the components of the Pleiades appear in ordinary instruments With respect to the Nebulæ it is needless to say more than that I ord Rosse considers its performance in bringing out the detuls of the Orion Nebula, 1 M (the Crab) and 51 M (the Great Spiral) quite satisfactorily

7 The Committee had no opportunity of testing the spectroscope on stellar or nebulu spectra—but they have tried it on solar and electric ones and consider that it will be very effective, from the solidity of its structure, and its large dispersion combined with a small deviation

8 The balance of the grant which will probably be absorbed by the expense of pieling the instrument for removal, was not sufficient to justify the Committee in ordering a photographic apparatus which should be worthy of the Telescope—but some trials have been made with a male shift affair? which confirm them in their opinion that it is most important to turn to account the photographic power of this magnificent instrument not only for the moon but for the planets and the sun—On two or three occasions Castor and the moon were taken with this temporary apparatus—as to the star its components impressed their images in sood measurable disks in times varying from two to eight seconds—with respect to the moon on February 1 when she was seven days old and the air good a remarlably hard and sharp picture full of minute details, was obtained, which exhibits so strongly the great photographic power of

^{*} The cause of this diffused light has since been discovered and removed + On the 19th of Lebiuary however the Committee had the advintage of the presence of Mr Lassell in the examination of Uranus among other objects with Speculum A and guided by his fumiliarity with that object they were enabled to make out stars the position of which with great probability corresponded to the places of the two most distant and one of the nearest satellites

the instrument that they would regard it as a serious loss to science if this was not most fully brought into action This is the more desirable because lunar and solar photography would utilize a considerable portion of time, during which the observing of nebulæ After full inquiry the Committee find that the cost is impossible of the necessary apparatus for this work including a micrometer for measuring distances and positions on the photopiaphs (lil e that described in the Philosophical Fransactions 1862 p 373), could be provided for a sum not exceeding £400 and they currestly hope that so They have been given to undervaluable an addition may be made stand that the Melbourne Government have resolved on putting a roof over the instrument, but that they think it can be more eco-In this case it occurs to nomically constructed there than here the Committee that the second form of roof described in Dr. Robinsons letter might be preferable to the more complex one there recommended and as it would be less costly the difference would more than cover the expense of the photographic apparatus this hope they have directed Mr Grubb to prepare a detailed plan of that apparatus and of the second form of root The Committee conclude by stating that they have no hesitation in declaim, that the instrument is perfectly fit for the worl for which it was de-They therefore consider that Mr Grubb has fulfilled his contract and have directed him to lose no time in preparing the necessary cases and packing it for Melbourne They have also instructed him to insure it against the risk of fire during its stay

The Committee feel bound to say that Mi Grubb has put a most liberal construction on the terms of his contract and after their minute examination of the excellence of the Telescope and the amount and perfection of the machinery connected with it and its manufacture they are convinced that Mr Grubb has been more influenced by the desire of producing a perfect instrument than by any prospect of pecuniary advantage and can seriecly realize the possibility of giving so much for the sum named in the contract especially when it is considered that special worls had to be exceted

for the purpose of constructing the telescope

ROSSE F R ROBINSON, D D, WARPLN Dr LA RUF

Feb 19 1868

PS March 7th 1868—I would strongly recommend that the photographic apparatus should be fitted to the telescope before it leaves Ireland

WAPRIN Dr IA RUF

XII Separate Report from Mr Lassell to General Salvine

R ty I odge Mudenhead February 28 1868

My DEAR SIR,-I have ventured to think that, having had an

opportunity of examining the mounting and appliances of the Melbourne Lelescope by day and its optical performance by night you might not be unwilling to receive from me some report of what I thinl of its performance and construction, even though that report be quite voluntary and unofficial

I may express, first my gie it admiration of the seneral efficiency and completeness of the mounting and driving-motion in which the difficulties of meeting the requirements of firmness of position, and yet of ficedom and convenience of motion are overcome more per-

feetly than I had ventured even to anticipate

Some photographs of the moon when about a quarter old were shown to me, which though taken only in an experimental and pre liminary way. I thought quite as good in relief and sharpness as any I have seen at least, that is my impression without the advantage

of ictual comparison

The only opportunity I have had of trying the optical power and general performance of the Telescope was the night of the 19th inst. which, although cloudless was obviously quite unfit to test the powers of my Telescope of large aperture A critical examination of the thouse was therefore impossible yet I saw enough to convince me that there could be no great error of figure and I had no proof that there was any which was appreciable Some of the objects we saw were the Nebula in Orion y Andromedæ 46 and 51 Messier and The two latter which had the preatest altitude were best Under the circumstances, I considered the vision highly s tisfactory and I should anticipate that in a fine and tranquil state of atmosphere the performance will justify very sanguine expecta-It is true that none of the objects were as well shown as on some occasions. I have seen them in the Telescope I had at Malta but I think it highly probable that the superiority of altitude and atmosphere may fully male up the difference

Bad as the circumstances were Uranus appeared accompanied by what I believe to have been the two brighter satellites which were indeed more conspicuous than I expected to see them—and although my own vision did not suffice to show me any points within these two a star was seen by at least two observers at such a distance as miles it probable that it was really one of the interior faint ones,

which certainly I should not expect to see on such a night

'In conclusion I freely express my opinion that the entire instrument is a great triumph of mechanical engineering and optical slill and, with the advantages of efficient working and a fine atmosphere, I trust it will still add something to our knowledge of the heavenly bodies

I remain, my dear Sir Very truly yours William Lassell

 At the same Meeting it was

Resolved —That the report now read be received and idopted, and that it be communicated to the Society, together with Mi Lissell's letter, for publication in the Proceedings—also that Mi Grubb be authorized to proceed without delay in the construction of the Photographic Apparatus referred to in the Report

XIII From Mr Ellery to General Sir Edward Sabine

Observatory Melbourne 18() Jan 4

MY DEAR SIR

The telescope has at length arrived and we are now very busy getting it erected for nothing could be done town do it till the great machine itself came to hand. It will be nearly two months before it can be fairly tried when a spacious rectangular building and its travelling roof will be completed.

Mr Le Sueur arrived nearly two months before the telescope, having come by the overland mail, and the ship carrying the tele-

scope making an unusually long passage

The principal or more delicate portions of the instrument came out in good order the specula are still in thin coats of varnish and their surfaces appear in perfect good order Some of the linge cast ings and portions of the gearing had got justed but not to in injurious extent The piers were completed on new year smorning and form a magnificent piece of masonry the stone employed bein, the grey baselt so common here (called blue stone") in blocks of from one to three tons in weight each. The building we have finally decided upon is of stuccoed brief -worl 80 feet long by 40 wide Forty in length is taken up by the telescope room which is covered by a ridged roof of iron travelling on rails on the wills and moves back on the outer 40 feet of building leaving the telescope in the open air The back 40 feet is covered by a fixed roof lower than the moveable one and will contain a polishing and engine room a capacious laboratory and an office for observer The cost of picis building and roof will be about £1700 The Government with hard economy in all other directions have still acted very liberally about this work and I only trust the telescope itself will turn out all that is expected of it The micrometer and spectrum apparitus have not arrived vet

Ir main
My dear Sir
Yours futhfully
Rotrell J Friery

General Sabine
Royal Society, London

XIV From Mr Ellery to the Astronomer Royal (Extract)

Melbourne Observatory August 13 1869

The great reflector is erected and at worl on the Southern Nebulæ This morning Mr Le Sucur picked up Winnecke's comet for the first time for we have had a long succession of bid weather

I am not satisfied with the performance of this great instrument, and I do not think the mirrors are at all perfect in figure. I have not yet seen anything like good definition of a planet with the lowest power. Of course we get plenty of hight even with the nebulæ but no definition with bright objects. The mechanism performs well and the clock works very satisfactorily for so heavy a mass as it has to move. The 8 tons of moving parts are as easily handled as far as setting and sweeping is concerned, as much smaller instruments

(Copy)

XV Rev Di Robinson to Mi De La Rue

Observatory Armagh October 25 1863

MY DEAR SIR

Like you I am much surprised that Mi Ellery complains of the

definition of the great Melbourne telescope

It is fortunate that Mr Grubb put in his contract that the telescope should be tried by the Committee before he sent it from Dublin, and our Report is sufficient to prove that in our hands it performed admirably. How it behaves under other management may be a question, and before adopting Mr Ellery's opinion that a mirror which in Dublin fully divided γ . Andromedæ does not define well at Melbourne. I would suggest that there may be other causes for this than any fault of the maker or of the Committee who passed it

I The speculum A (which I believe is now in the telescope) was never touched after you saw it on February 19. Speculum B was repolished to remove a slight diffusion of light which you noticed and which was perfectly removed by the process. Mr Grubb's command of figure is so great that I am certain this speculum also

was perfect when it left his hands *

II It is possible that the great and small mirrors are not in per feet adjustment. This adjustment is easily performed but from the construction of the Cassegr un and Gregorian, any want of it is far more sensible than in the Newtonian

III The film of variash if not removed, will, of course be injurious Mi Le Sueur in a letter to me some months ago mentioned its existence to which I replied, that if he had used strong and pure alcohol he would have found no difficulty in removing it. In

^{*} This paragraph is an answer to an inquiry by Mr De La Rue

a letter to Mr Howard Grubb he described the film as "sticky' Lac, as far as I know, is not viscid when dry, and therefore I suppose that the alcohol which he used was too weak

IV In the same letter to me he mentioned that he had been altering the position of the eyestops of the eyepieces, which is very likely to have interfered with the performance of the instrument

In my reply I repeated to him in full the proper mode of adjust ing the eyestop and recommended him to replace it in its origin il position and at the same time detailed the mode of adjusting the miriors

V It is possible that they may have serewed up too far the three great serews behind the speculum box, or the screws of the side

support so as to have put the mirror in a state of sti un

VI And lastly it is possible that Mr Ellery, though a practised observer may not have made sufficient allowince for the effect of atmospheric disturbance in a telescope of so large an aperture as I think, he has not been in the habit of observing with anythin, larger than an 8 inch achiematic, he may not easily icilize the fact that in the great Melbouine telescope the disturbing effect would be forty times greater

Without the operation of some of these causes it is difficult to conceive how Mr Ellery could find fault with this mirror until he If he expects to improve Mr has practised on a small mirror

Grubb's figure he may be weefully disappointed

As Su Edward Sabine took so much interest in the sreat Mclbourne telescope I wish you would show him this letter

My failing sight obliges me to employ in imanuclisis Yours truly

1 L ROBINSON

W De La Rue Esq, FRS

In January 1870 a communication dated Nov 8, 1869, was icceived from Mr Le Sueur giving an account of the removal of the telescope to Australia, and of the first observations made therewith It is here reprinted from the 'Proceedings' of the Royal Society, vol xviii -

A description of the great Melbourne reflector, and its history up to the time of inspection by the Committee have been con municated to the Royal Society the following additional account of the doings connected therewith since the instrument was consigned

to my care may be of interest to the Society

Mr Grubb commenced taking down the telescope at the end of April 1868 this was accomplished in no steat length of time, and without any difficulty The specula (by the advice of Mr I assell, who had found this method answer perfectly) were conted over with shellae varnish to prevent oxidation on the voy in out they were then protected in their cells and on their lever supports by strong double wood easings, and the other parts of the telescope and ma

chinery eased or otherwise protected. The only easualty which there scemed to be any reason to fear could give rise to any serious con sequences was a tilting over of the speculum cases—then great weight was perhaps a sufficient guarantee from such an event—it was nevertheless thought prudent that the telescope and machinery generally, should not be left entirely to the tender mercies of the shipping and crane labourers. I was therefore present at the shipping in Dublin on board a steam-tug hard for the purpose, and at the transshipment in Liverpool on board the Empress of the Seas'

Both these operations were performed satisfactorily, and without

any scrious cisualty

The Empics of the Seis' sailed from Liverpool on the 17th or

1 Sth of July I followed by the August Overland Mul

On my initial in Melbourne I found that beyond the selection of a site in the Observatory grounds, nothing had yet been done tow it its the erection of piers or building this was principally owing to the fact that Mi Ellery and the Board of Visitors had not considered the information which they possessed sufficiently definite to will int their placing the matter in the hands of the Worls Deput ment at had therefore been thought advisable to await my arrival

Some necessary module atoms having been made in the drawings the construction of the piers was soon proceeded with, and satisfac

torily terminated at the beginning of this year

In the mean time the Impress of the Seis with her precious engo hid inived ifter every long voying which for some time was the cause of much uncisiness parts of the instrument were unpacked and temporarily housed the whole appeared in fair order there was certainly no material damage done to anything

Arrangements being in progress for the election of a suitable building it was thought advisable to delay mounting the telescope until plut of the building was constructed little therefore was done for some time beyond setting up, is accurately as possible, the

plummer-blocks which contain the polis axis bearings

The building was commenced enly in the year, and when it was thought that sufficient progress had been made, the crane which had been used in the erection of the piers was removed to a more convenient position and the various heavy parts of the instrument litted on to the floor of the telescope room, over the walls or through a pip left for that purpose and, for convenience in after operations, in the north will and north end of west wall

The mounting was then proceeded with and satisfactorily accomplished in little more than a weel as regards the main parts, with-

out much difficulty

Attempts were made on two occasions to use the instrument tor adjustment and observation but it was found that the dust (a die adful enemy in the summer) and the sittle used by the building accumulated to such an extent as to lead to fear of considerable dainings to the bearings and more delicate parts of the machinery it was therefore deemed prudent to cover up the telescope as well as possible with turpulins and leave it in that state for some time

The building is rectangular, 80 feet long meridionally by 25 wide, with walls 11 feet high Of the meridional length the telescoperoom occupies the north 40 feet the next 12 feet are appropriated to the polishing-machine, crane, and engine the remaining 28 feet are divided into two rooms one of which is at present used as an office the other 25 by 14, is intended for a laboratory. The move able roof is 40 feet long and runs on rails laid the whole length of the walls the telescope-room may therefore be completely covered in and as completely uncovered when required, the roof in the latter case resting on the south building which on that account has a very low permanent roof

The loof is constructed of six triangular wrought iron principils, cross-braced which abut at each side on a broad horizontal plate formed of two parallel lengths of stout angle-iron, connected it various points by iron bands for additional stien, the a broad ver tical plate is bolted to the outer an le-iron piece. There are four pairs of wheels 26 inches in diameter flanched on the inside these he along the middle of the horizontal plate, the journals being

bolted to the angle iron pieces which form the plate

The roof is covered with galvanized corrugated non it is therefore on the whole a somewhat heavy affair The mechanical urangements for moving are, however simple and effective a stout iron shaft runs across the building and gears by wheel and pinion on the axles of the two south end wheels to this shaft is fixed i spoked hand-wheel, by means of which the operator readily sets the roof in motion and standing on a small platform connected there-

with is himself carried along at the same time

The design of the roof is due to Mi Merrett of the Worls de-On the whole there is much to be said in favour of this rectangular form of roof the temperature even in this climite ficquently descends too low to be pleasant but the occasional bodily inconvenience produced thereby is more than counterbal inced by perfect freedom to the observer and the gratification of knowing that the instrument is in the best possible conditions for sitisfactory Only one really serious annoyance have I found connerformance nected with complete exposure I allude to occasional heavy dew rendering it almost impracticable to use the sletching and other papers, the speculum meanwhile remaining free from deposit if precaution is taken not to work at too great an altitude

The telescope when housed has meridionally on the cast side of the pier and nearly in a horizontal direction, provision hivin, been made to prevent the tube being lowered beyond a certain smill

inclination

The piers are in keeping with the massiveness of the instrument they are constructed of large not to say huge blocks of bisilt axid to a fine surface, altogether a substantial and beautiful piece of

The height of the walls with reference to the piers is such that very little of the sky range is curtailed. The north wall cuts off objects having a lesser altitude than about 10° When resting on the east or west walls the telescope is nearly horizontal in both these directions trees interfere especially on the west side, where the ground rises. This curtailment will probably be a matter of very small importance as, with a four feet aperture, observations at low altitudes are almost impracticable, and would probably never have to be resorted to, except in the case of comets. The roof itself cuts off some of the range near the subpolar meridian. this, again, is not lil ely to be of much consequence.

The steam-engine, polishing-machine, and crane have been mounted in the room devoted to them this room adjoins and is on the same floor (raised 4 feet from the ground, and 3 to 6 feet from the floor of the other rooms) is the telescope-room. To the east end of this machine-room, and communicating therewith a small lean to boiler-house has been added in the west wall is a window which when open will leave sufficient clear space to admit of viewing a distant nearly horizontal object for the purpose of testing the millors.

The large speculum (A) was originally attached to the tube in its varnished condition on the first favourable occasion it was taken down and unvarnished—a process which proved more troublesome than had been anticipated. The lac was very refractory, and the difficulty of removal exaggerated by the extreme heat then prevalent after a process of solution in alcohol, mopping up, and washing with water frequently repeated, although there seemed no lie which would still dissolve a large number of markings caused originally by the varioush brush were apparent, and the whole surface had un unpleasant menly appearance

It was thought, however that the light lost would not prove serious and in any case it did not seem that any further operation except polishing would improve matters—the speculum was therefore remounted and tried—and although it was of course impossible to say what would have been the effect of a more perfect polish, the views given of the brighter nebula were grand in the extreme, and left nothing to be desired

By degrees, however, and without much exposure, the surface became more and more tainished, with evident effect on the performance

In the meantime the second mirror (B) had been unvariabled in this case naphtha was used as the solvent, the solution mopped up, and the surface washed with so ip and water. After a frequent repetition of this process the surface seemed clear of impurities, and though not so bright as I had frequently seen at an Mr Grubb's word shop there were no sugns of mealiness, the only unpleasant casualty being a considerable pitting of two patches some two inches square, produced by droppings from the muriate used in soldering the time cover. These pittings are deep and unsughtly but the extent of surface corroded is comparatively so small that the offeet must be inconsiderable.

The specula were exchanged about two months ago, and A put on the machine but nothing his yet been done towards repolishing as the necessary arrangements have not been got together for performing that delicate operation with due convenience Of work done, I cannot yet speak with any satisfiction since it became at all practicable to use the telescope—the history which I have to relate is a long chapter of weary heart breaking witchings with an occasional half hour's work

η Algo was the first object observed for purpose of delineation after the first nights work little (and that by snatches) was done towards it the lapse of time caused by a new inroad of worl men and a long course of extremely unfavouable weather having caused the nebula out of convenient reach. The search, which was reluctantly given up will however be again soon resumed

I enclose two sketches, 4403 and 3570 of the 1864 catalogue

4403 The horseshoe nebula is a grand object conspicuous and with shape even in the finder. In the sketch the principal stars are laid down from measured position-angles about different centres they are not as accurate as I could wish and will be reobserved differently under better conditions in no case however can there be sufficient error to influence in any material degree the configurations of the nebula or the smaller stars sketched in by eye

It will be seen that the sletch contains considerably more detail than the corresponding figure in Herschels Citalogue there appears however, to be no marked difference (with perhaps one correption) which may not be accounted for by the difference of aperture

used

The exception to which I allude is the presence of a small but conspicuous double star at the span_le of the linet which lies between the 3 and the bright streak the experiment has not been tried of cutting down the aperture to approximate to in 15-inch Herschelm, but the intuinise brightness of the principal star and the presence in the CGH of stars not more bright (No 3 of Herschels catalogue is certainly less bright) go far to show, without this experiment, that the star did not exist as such with its present brilliancy at the time of the CGH and PI 33 observations. I have not seen Mr Mason's drawing but look forward with much interest to examining it and his remails thereon.

The important position of the star, and the careful scrutiny which the knot and its neighbourhood must have repeatedly undergone, forbid the assumption that it was simply overlooded by Sir John

Herschel

The star β (I keep to Sir John Heischels numbers and letters) is conspicuously and beautifully double the companion of considerable brilliancy about 15 ma, with its present bulling and clongation it should I think, be within reach of an 18 inch

The knot is what I presume should be called itselvable—the appearance is spulling though no discrete stars can be seen, except perhaps a second faint one which is suspected at the situal Part of the streak near to the knot is also spulling but not in so marked a manner—the other portions appear of the ordinary mill y nebulosity

The fainter nebulosity (8) of the bight stied pretty well mills out the borders of the almost vacuous line which he ids up to and

past the knot On receding from the lane it becomes very faint. nor is this faintness uniform but the appearances are so fugitive that after repeated and painful effort I have been unable to catch the boiders, however, stretching to the stais as in the figure, are occasionally pretty well seen. On one or two occasions I have suspected the existence of a line between the nebulosity about the star No 10 and the lower portion of the &, this, however, requires verification

At the f end the upper and smaller semicircle is plainly marked, the lower and larger very faint, and consequently its exact figure there is certainly some very faint nebulosity leading through the groups of stars north of the three bright f end stars, but it has not been added to the sketch on account of its uncertain

figure and extreme faintness

3570 A small but beautiful spiral The two brighter knots are the prester brightness of these knots is not particularly shown in Sir John Herschel's sketch but is mentioned in the observations the general ground is only slightly nebulous

Of worl out of the regular course amongst other things, Neptune has been observed on some five or six occasions for figure and a

second sitcllite, with only negative results

In the absence of a photographic apparatus to be used at the uninterrupted focus of large mirror attempts have been made to utilize the 2nd or Cusse, run image an average exposure of near ten minutes on an eight day moon produced pictures which (by no means good) were of sufficient promise to make it worth while to resume the attempt under more favourable conditions

The time of exposure is somewhat surprising and would seem to accuse a great loss of chemical rays by a second perpendicular reflection but perhaps the more legitimate conclusion would be that the inactivity was munly due to absorption at the surface of the

luge mirior which was then very yellow

The spectroscope arrived some time ago, but has not been much used it is thought that for star work of any value some modification will be required principally the exchange of the present collimater for one of longer focal length A reater dispersion, moreover, seems desirable for nebular work however for which it was munly designed the spectroscope in its present form, which is handy and compact will be of much service

For spectroscopic work on objects having a sensible diameter, the are telescope itself labours under some disadvantages, the enormous focil length and consequent magnification of the image is a serious inconvenience in the case of funt objects and may be only partially remedied by a suitable condense. This magnifying of the image may however in some cases be advantageous. I allude to the possibility thereby afforded of viewing small definite portions of moderately bright objects unfortunately the objects with which we have to deal are seldom of such a character

Of nebulæ, Orion has been examined for purpose of practice The three lines are plantly and conspicuously seen the hydrogen line is comparatively much fainter than I had anticipated and disappears in the fainter portions of the nebula 30 Dorado shows the nitiogen line with facility the second line certainly but not in all positions, and always with difficulty the hydrogen line is suspected only I can see no trace of a continuous spectrum

 η A150 has been observed on only one unfavourable morning—the nitrogen line was seen over a considerable space—of the presence or absence of others, or of a continuous spectrum, I am unable to speak

with certainty

With respect to future operations it is intended that at first the routine work shall consist of a detailed delineation of the objects figured by Sir John Herschel or any others which may prove interesting this will take some time for even without the impediment of cloudy weather the delineation, with any degree of satisfactory correctness, of a moderately large nebula requires a considerable amount of work and careful and frequent scrutiny. It is hoped however, that this work will by practice be found less painfully difficult than it is at present

The spectroscope will be used as much as possible the moon photographed and attempts made to photograph the nebule, when a photographic apparatus has been produced and stabing photographic room &c added to the building. It is moreover, hoped that before long a refractor of some nine inches aperture may be produced to be mounted with the reflector, or, preferably, as a

separate instrument

This telescope besides being of much general use will find much and valuable employment in determining micrometrically the chief points in the nebulæ under examination with the reflector, with more expedition and accuracy than at present for spectroscopic work this telescope would be a valuable adjunct, especially if it be constructed of such comparatively short focal length as seems now to be practicable

The great interest which the Royal Society have taken in everything connected with the Melbourne reflector is my sole apology for

sending thus early such a meagle account

XVI Mr Verdon to Sn Edward Sabine

8 Victoria Chambers Victoria Street Westminster S W February 22 1870

Sir,

I am directed to express the thanks of the Government of Victoria to you and to request that you will be pleased to convey them to the Telescope Committee for the very valuable advice assistance and supervision given by you and them to the construction of the great Melbourne telescope

The institument is now on agod upon the worl for which it was intended and the Government of Victoria looks forward

to the important astronomical results which it will doubtless achieve

I am further directed to communicate to the Royal Society a report by the Government Astronomer upon the working of the Telescope a copy of which I beg leave to inclose accordingly

Referring to the requisite appliances for photographic work men tioned in Mr Ellery's report the Chief Secretary observes that whatever sum may be necessary for the construction of the apparitus will be very gladly provided by the Government

I have the honour to be,

Sir,
Your most obedient Servant
GEO VERDON
Agent-General for Victoria

Lieut General Sin L Sabine A CB, &c &c, President of the Royal Society

XVII Mr Ellery to Sir Edward Sabine

Melbourne Observatory January 3 1870

My diar Sii,

In a letter to Mr Arry I mentioned the bad definition of the large mirror (believed to be that I nown as A) which was then in the telescone Under the most favourable encumstances I never once obtained with it what I could call moderately good definition tried it on Saturn many times but could not get any detail whatever The larger division in the ring was visible, but was never distinct beyond this nothing on the ring or the planet itself could be made I have, however, never had any experience in observing with luge reflectors, nor with refractors larger than 8 inches or so and therefore may not have made all the allowances I should have done but after over twenty years constant observing with telescopes of various kinds, my statement that the definition with mirror A (?) was not good may be entitled to some weight and when this state ment is endorsed by Mi Le Sueur, who has very recently observed with large reflectors in England and Ireland, the Committee may be assured that the statement was not made with any desire to find fault or to convey anything but the actual truth of the case mirror A (?) at first had a mealy yellow appearance after the lac had been removed which was thought to be due to a little residual var-This dull mealiness increased till eventually Mr Le Sueur was obliged to change it for B(') The telescope performance is very much improved with B (?), and on several occasions I have obtained views of Jupiter and multiple stars, when the definition has been excellent

The metal in mirror A on microscopic examination, I found not to be homogeneous, the surface being as it were reticulated Masses

of good alloy, bearing a fine polish, are intersected by reticulations of a yellow alloy, which appears somewhat porous, and from which all the oxidation seems to arise. No such state of metal is presented by mirror B which is now in use

As far as regards the mechanical arrangements the telescope is

in capital order

I have given to our Government a brief report of the election of, and subsequent work with the telescope a copy of which will,

I believe be sent to the Committee

Mr Le Sueur has been fully occupied during every available month with nebular work. A few mights since he observed the spectrum of η Argus and found it to contain bright lines. C and F (hydrogen) certainly others not so distinct probably part of the nitrogen spectrum. This is a most interesting discovery with respect to a star with such a large variability. Mr Le Sueur sends these observations to Mr Stokes by this mail

I remun

My dear Sir,

Yours faithfully
ROBI L J LIIRY

Sir Ed Sabine Royal Society London

XVIII From Chief Secretary MacPherson to Mr Verdon inclosing Report from the Government Astronomer at Melbourne

(Copy)

THE GREAT MULBOURNE PULLSCOPE

Victoria Chief Secretary's Office Melbourne Jan 3 1570

SIR—The great Melbourne telescope having now been in fur working order some three or four months, it appears to be a fitting time to request that you will convey to the Felescope Committee of the Royal Society through the President General Sabine, the thinks of this Government for their very valuable advice, assistance, and supervision in the construction of the instrument which is now engaged upon the worl for which it was intended and, it is hoped, is destined to achieve important astronomical results

You will be good enough to communicate to the Royal Society the inclosed report of the Government Astronomer which although in some respects not so satisfactory as could have been desired will be read with much interest. It is unnecessary for me to say that the Government will make provision for meeting the cost of the pho-

to raphic appliances, to which reference is made

I have de de

(Signed) John MacPherson

George F Verdon Esq CB
Agent General, London

(Copy)

Observatory Dec 31 1869

Sir —I have the honour to submit for your information a report of the erection and subsequent working of the great Melbouine telescope. The telescope arrived in November 1868, and its erection at the Observatory was commenced early in January of the present year. The building for its protection was not completed till. June and the final fitting up of the telescope finished early in July.

From a report furnished by Mr Le Sueur (the astronomer in charge) I extract the following — Observations were attempted as early as April in this year but the telescope was not in fair working order till about the middle of August, since which date observa-

tion has progressed more or less satisfactorily

The principal work has consisted in examination and mapping out of nebulæ but the very unfavourable weather throughout

almost the whole season has prevented much propress

Of other worl position observations have been made of Winnecle's periodical comet except in so far that largeness of aperture may permit the following up of a comet to a late date the great telescope is of course, unsuited to that kind of worl, and bad weather at the critical time prevented a full utilization of the above-mentioned peculiarity yet it is thought that the later observations may be of value in filling in the series which will have been obtained in Europe

When fivourably situated Neptune was observed on many oc casions for examination of figure and detection of new satellite, with

negative results in both cases'

With respect to spectroscopic observations Mr Le Suem says—"The spectroscope furnished by Mr Grubb has already proved of much service for nebule worl—for star work as far as I can at present judge it is unsuitable nevertheless a very important observation has lately been made therewith, showing that the spectrum of the variable η Albo is crossed with bright lines—Io follow up this, and star observation generally, to much purpose would require a considerably modified spectroscope—The one now on hand was intended specially for nebulæ worl, and for this it is as competent as could be desired."

Nothing his yet been done in celestial photography. It was supposed that the original vote would have been sufficient to cover the expense of a suitable photographic apparatus, but the many extra expenses incident to parling shapment are exhausted the available tunds. The Royal Society of London, however, doesning it of great importance that the telescope should be fitted for photographic work kindly tool it upon themselves to order the requisite appliances which I believe are now in course of construction by Mi Grubb (the mal er of the telescope)

We are not yet informed of the exact cost of the apparatus, but it will be necessary to relieve the Royal Society of its self-

imposed buiden

In my report to the Locard of Visitors in April last Treferred to the

construction of the telescope, but could not at that time speak of its performance or capabilities but during the several months' use since then, Mr Le Sueur has tested its performance most carefully and although I have had no prior experience with reflecting telescopes of such dimensions as this, I have been enabled from frequent observations to form an opinion of its powers

With the large milror first used the telescope certainly did not perform so satisfactorily as could be desired and making all allowances for atmospheric disturbances the definition was never good but with the other milror (supposed B) it became very much better, and Mi Le Sueur speaks of its performance now is 'far more satisfactory'. The large milror first in use has become very dull from a peculiar kind of yellow tainsh, and it is highly probable that it will have to be repolished before it is fit for much service and considering the great delicacy of the operation and necessity of considerable experience in its performance it will be advisable to obtain a supplementary metal milror of 12 or 15 inches diameter which should be figured and polished not only for the practice of the astronomer in charge of the telescope but also for the training of the assisting workmen

The building for the protection of the telescope is in mo t respects satisfactory. The peculiar construction of the roof renders the exclusion of dust a difficult matter but much I believe can yet be done to improve it on this score. The rolling gear, by means of which the roof is traversed from over the telescope was somewhat defective at first but has since been made to work satisfactorily. The polishing apparatus with its driving steam engine, are in their

places and ready for use whenever they may be required

The necessary stages for testing the mirrors when on the polishing machine are now in course of crection. A photographic room has been elected in the telescope-room, and will be leady for use in

a few weeks

There are several arrangements and appliances yet required before the telescope can be said to be properly provided amon, which are more convenient observing-seats drawing stands and the erection of a platform outside the telescope-room for photo, raphic operations. Some of these are already in progress, and should sufficient means be available, will soon be completed.

I have de de

(Signed) Robert L J Llitry,
Government Astronomic &c

The Hon the Commissioners of Crown Lands and Survey

XIX Rev Di Robinson to Sii Edward Sabine

March 1870

MY DEAR SIR EDWARD,

I have read with pleasure the copies of letters from Mr Verdon and Mr MacPherson, which you have sent me, on the subject of

the great Melbourne telescope, and the accompanying report by Mr Ellery

The former acknowledges in most gratifying terms the share which the noble body over which you preside had in carrying out the grand

scientific conception of the Victoria Government

M1 Ellery's report is not less important for it shows that the difficulties and objections which always beset a great and novel undertaling are clearing away and a bright and prosperous view is opening of the future

Of the objections which were numerous many have been circulated in the Melbourne papers and some have been communicated not only officially to me and Mr Grubb but also to others in this

country through whom they have quied publicity

(1.) One of the complunts referred to in Mi Ellery's report is that a proper observing chair was not furnished along with the telescope. The Committee requested Mr Le Sueur, when in London, to examine the most approved machines for the purpose and gave him carte blanche to order that which appeared to him the most suitable. He selected the Dawes chair and it it has failed in its object, he is the only person responsible for the fulure.

(11) M1 Le Sucui thought it necessary to alter the eyestops of the eyepices from their normal position, influenced by the hope of a little increase to the field of view, but at the cost of more than

equivalent loss of light

(iii) Mr Le Sucui complained that the spectroscope which was sent out was not adapted for all spectroscopic uses, and that the Cassegram telescope laboured under some disadvantages on account

of the great size of its secondary image

The objection derived from the large size of the image may be removed by condensing the image by a convex lens, either spherical or cylindrical. The limit to which this can be done is determined by the condition that the vergency of the condensed pencil shall not exceed that of the collimators object glass. In the case before us the vergency of the rays of the second image $= \frac{1}{1}$ and that of the collimator $= \frac{1}{1}$, so that the image can be condensed to $\frac{1}{10}$ of its diameter, and its brightness increased a hundredfold

As Mi Ic Sucur has litely been doin, very good work with this spectroscope on nebulæ and planets, he has probably in some measure surmounted his difficulties and that which he still seems to feel about its application to stars will similarly disappear by the use of

the cylindrical condenser

When this spectroscope was constructed it was not supposed that a high dispersive power was available for nebulæ and the highest for which it was furnished did not give more than 5.5 degrees of dispersion from B to G. A compound prism of Mr. Chance's new delise glass can be furnished at a moderate cost, which without any alteration of the spectroscope will give double the dispersive power, probably sufficient for everything except the sun and I have directed Mr. Grubb to send one out with the photographic apparatus, which is now nearly completed

(iv) Mr Le Sueur complained that the micrometer's field of view is inconveniently small. The size of the micrometer was however, decided on after a careful discussion in every step of which he tool part and to which he appeared to assent. An ordinary micrometer with an illuminated field is quite inidmissible for neoular work and the only alternatives were one with wires illuminated in a dark field, or a double-image one. I had a strong inclination to try the latter, of which an elegant form was long since described in the *Philoso-phical Transactions* by Lamsden in which the small mirror of the Cassegiam is divided, and its segments are separated as in a heliometer. This however, has the seat disadvantic of halving the light of the images and further lessening it by requiring a diaphragm to be placed behind the small mirror twice its diameter.

In the illuminated wire minimeter the vision of nebulæ is least interfered with but the apparatus required for its illumination is bulky, and if it had been applied to the lowest power would have

attrined unmanageable dimensions

It was therefore resolved on to make it of a size which would be sufficient to determine with accuracy the places of the stars of inference and to complete the mapping of the nebulæ by means of glass gratings which on account of the great equivalent focallength

of the telescope, admit of much accuracy

In reference to a doubt which has been expressed by Mi Le Sueur in regard to the figures of speculum A and the small mirror, which he considered were jointly affected with spherical abcriation I may remark that he had himself seen many difficult test objects with that speculum in Dublin in particular he was present when the Committee tried it assisted by Mr Lassell. It was then remail able for the clean sharp disks which it gave to lunge stus. And as speculum A does not appear to have undergone any process since it left Dublin which could alter its figure, the only possible mode of accounting for the abcriation if it really existed is that he used the small speculum which he says he repolished after its arrival at Melbourne, probably without paying attention to its figure.

As to the strange deterioration of speculum As surface, I do not think Mr Ellery's explanation of it in his letter to you is probable namely that it is composed of a yellow alloy disseminated through masses of good alloy bearing a fine polish. I have never scen any occurrence of the kind and it is very unlikely as the alloy is of It cannot have been caused by any action on atomic proportions the metal of the lac varnish with which the surface was covered No such action was observed on speculum B which was similarly protected And as fortunately the piece which was cut out of the centre of speculum A had been preserved and polished I requested Mr Grubb, on hearing of the matter last August, to varnish the disk with lac varnish, such as was used with the large speculum and I have lately examined it. The vainish can be perfectly removed leaving no trace whatever on the surface and I may add that there is not the slightest appearance of the yellow alloy suspected by Mr

Ellery It is exceedingly improbable that any chemical agents could be present in the hold of the ship likely to penetrate the vannish and even if such had been present it might be expected to have

acted on speculum B as much as on A

I learn from M1 De La Rue that lac contains, in addition to the resinous matter of which it is chiefly composed (and which is easily soluble in alcohol) a certain proportion of a lind of wax which is far less easily acted on by thit reason. If the process for removing it was not circfully conducted this waxy matter would remain mottling the surface. Now I do not think the process was criefully conducted for I am informed by M1 Le Sueur that methylated spirit was used instead of pure alcohol—this does not seem to have been largely applied—and afterwards the surface was 'mopped with water'

If Mr Le Sueur had provided himself with a quantity of fine carded cotton and absolute alcohol and, souling rolls of the cotton in the spirit had gone patiently and carefully over the surface it seems very probable that he would have by these means obtained a white and builliant surface, such as we have with the disk already mentioned by

In any case however the use of water was quite improper

If the yellow stain be trinish it might yet be removed by rubbin, with slices of lemon after it has been thoroughly ascertained

that no lie can be present

Should this expedient full there is no resource of course but to repolish it. But I hope this will not be attempted until Mi. Le Sueur has had a good deal of preliminary experience. As a means of acquiring this I quite concur in the necessity of sending out for practice a disk of speculum metal of 12 or 13 inches diameter, as recommended in the report. But something more than this will be necessary. You may polish a speculum to the highest lustre which yet will show you nothing at all. It may not be purabolic, may be polished in rings of, though the general figure be correct, it may be covered with innumerable little elevations and hollows destructive of good vision.

The disk, therefore, should be mounted on its own special system

of equilibrated levels, and tested in a telescope

But the operator must keep in mind that even when he succeeds in making his speculum of 12 inches define perfectly well still he will have much to learn before he can bring speculum A to anything like the perfection which it had in Dublin

I will conclude this long letter with a few words which I hope

will be useful to the Melbourne astronomers

It is very difficult for persons who are only conversant with telescopes of moderate size to form in idea of the excessive disturbing influence which circumstances of temperature exercise on instru-

^{*} In the Industry Number of the Astronomical Society's Monthly Notices Mi Lassell states that he has removed after eight years a covering of the from his 2 feet speculum and that its brilliancy is perfect. He however used absolute alcohol

ments of such enormous aperture as this. Even in Ireland, where the annual range of the thermometer is but small, and the air is generally charged with moisture the number of nights on which even a 3 feet reflector can be used with complete success is very small and at Melbourne where these meteorological circumstances appear to take a far wider range, the difficulties must be immensely increased

It is also probable that the telescope's being enclosed under a loof may make the difference of temperature between the great speculum and the atmosphere preater at the commencement of the evening's operations than if it had been mounted in the open air. The roof should therefore be opened an hour or two before be inning to observe

The line of work which this imposes on the astronomer is evidently to delineate the coarser and more obvious details on nights of bad definition, and to devote those rarer and more precious ones to

examining the finer and more delicate characters of objects

It also may not be unnecessary to point out the great importance of always attending to the adjustments of the specula and to the firmness of connexion between those specula and the tube. The adjustments are more complicated than those of the achromatic, and more likely to alter but they are easily made and any neglect of them tells powerfully against the performance of the instrument (Signed). T. R. Robinson

XX Mr De La Rue to Sir Edward Sabine

The Observatory Cranford Middlesex W April 22 1870

MY DIAR SIR EDWARD,

As regards the additional prism requisite to give more dispersive power and some additional lenses I have no hesitation in recommending that these should be sent without delay to Melbourne

I suppose that the functions of the Melbourne I ele cope Committee have come to an end with the completion of the photographic apparatus, which was the last of the appliances they were to superintend but I presume that notwithstanding the termination of their work a recommendation from the members of it would have weight with the Victoria Government. Assuming this to be the case, I do not hesitate to recommend that a 12-inch disk ground but not polished, grinder and polisher tube and cell, on the plan of the large one and one or two secondary specula also a diagonal mulror together with some convenient stand to enable Mr I e Sucui to direct the telescope on to a star, should be sent to him for it is most essential that he should be put in possession of the means of acquiring the art of figuring the specula of the great telescope

I do not suppose that these things should be furnished without

the authority of Mr Verdon and altogether they may cost £100 but this sum is quite insignificant in relation to the object to be gained

I am
Yours most sincerely
WARPEN DE LA RUE

INC OSTILIS

hev Dr Robinson to Sir E Savine dated May 4 1870

I send a copy of Grubb's estimate for a tital Telescope for Melbouine of which I send another to De La Pue I think a very low considering that it involves an entire telescope or considerable power which if not worled in the Melbouine Observatory, could very easily be disposed of when it had done its work with Le Sueur I should not however venture to order it without your obtaining Mi Verdon's opinion on the subject

(Figned)

T R ROBINSON

The Ob avatory Cranford Middlesex W May 6 1870

MI DIII SIR EDWARD.

I quite approve of Mi Giubb's tender as to details and prices the only thin, that striles me is the desirability of having small encles and ited coarsely on brass simply for facilitating the finding of olyces. This addition would not cost much say Lo additional I write almost in the same words to Dr. Robinson

 $(S_{1,ned})$

WAPIEN DE LA PUF

The amount of the estimate was £165

 λXI Su Edward Sabine to G F Verdon, Eq., CB Agent-General, c

The Royal Society Builington House May 7 1870

MY DEAR SIR

I enclose Mr Grubb's estimate of the cost of the small reflecting Telescope proposed to be supplied to the Melbourne Government as in addition to the Great Luflector now at work together with notes from Dr Robinson and Mr De La Rue approving of the same On receiving your sanction Mr Grubb will at once proceed

(Signed)

EDWARD SABINE

XII Rev Dr hobin on to Sir Eduard Sabine

Observatory Armach May 15 1 70

My DIAR BRIIND

The cneumstances which induced Mr. De La Rue and me to be commend the more used outly to which Mr Verdon refers no these In Mr Fillery's report it is recommended that a disl of speculummetal should be supplied on which experiments should be made for the purpose of giving the Melbourne istronomers that experience in polishin, speculi without which my attempt to repolish the lar e speculum would probably be a fulure

It occurred to us however that it is essential to the success of such experiments that the operators should have the means of usertuning how for their tirds are successful for it is possible to polish a speculum to a lu h degree of bulliancy which yet from defects of its home will perform bully in a telescope. Option try the by mil ing the speculum into a temporary telescope and examining a witch deal of a critical star placed it some detined but this test is only wullible to a certain extent and when the higher degree of recuracy is to be obtained (is is the case in the instance) recon a mut ultimately be had to the observation of real stus This requires that the observer should have the means of directing the experimental telescope to any part of the sly at should therefore be provided with some sort of estind. The speculum should be supported in a way exactly corresponding to that in which the great speculum is supported in it box is etherwise the same proportion of action of the polishin machine which gives a perfect puribolic figure to the mail peculian would not do so to the luge one

Now it appeared to us unwise to endinger these experiments by in economy which is not of importance. The cost of the proposed stind will be but little more than that of my one possessing the requisite steadines and the tube is mentioned in the estimate would undoubtedly be more effective than my maleshift which could be not up for the occasion. The lever mounting is absolutely nccess u.v

Lor these reasons I hope Mr Verdon will consider that these extra matters are essential to supplying the deficiency mentioned in Mr Fllerysreport

Yours ever T L LOBINSON

Sir I duard Sabine, K C b

NIII Mr Verdon to Su Iduard Sahine

S Victoria Chambers Victoria Street Westminster S W May 15 1570

Referring to your communications upon the subject of the Mel-

bourne telescope and to the suggestions of the Committee, that the deficiencies mentioned in Mr Ellery's report should be supplied at a cost not exceeding £165 I have the honour to inform you in reply to your inquiry that in my opinion the Government of Victoria will sanction the expenditure proposed in accordance with the assurance given by the Chief Secretary in his dispatch of the 3rd of January last addressed to me the sub-tance of which I have already communicated to you

I have the honour to be
Sir
Your most obedient Servant
GEO VERDON
Agent-General for Victoria

Lieut General Sir Elward Schine KCB PRS, &c Burlington Houe W

Report of the Government Astronomer to the Board of Visitors to the Observatory read at the Annual Visitation March 31 1570

THE GREAT MELBOURNE REFLECTOR TALESCOPF

At the date of my last Peport I was unable to give any further account of this instrument than of its allival, the workmanship style of construction and partial erection which was not sufficiently advinced to admit of any test of its optical capabilities. I however mentioned several matters where some alterations and additions of no pleat importance had to be made and also to the fact that it was fortunate we had not built the piers before the telescope allived in consequence of some error in the plan for them which was sent from Dublin

The principal alterations referred to are these —

In consequence of the difference of latitude of Melbourne and Dublin where the telescope was mounted during construction the horizontal clock connecting-shaft had to be lengthened the vertical shaft leading to RA sector shortened and a new support made for it

A new journal for the upper part of the shaft for quick right ascension motion—as the original one could not be lept in position

owing to insufficient bearing

As regards the piers—in the drawings sent to us by Mr Grubb, the recess in the pier for the clock was too small by a considerable amount and had the piers been built consisting as they do of large blocks of finely cut bluestone, the south pier at least would have had to be taken down to rectify the error. The base of the piers too as shown in the drawings would not have allowed the telescope to be

* It appears from Mi Grubb's statement at page 5 of a pamphlet published by him in March 1870 that the tracing from a drawing purposely made for piers suited to the latitude of Melbourne and which had been sent out as in structions for the erection of the piers—had not been followed in their erection brought sufficiently near the vertical to admit of the acmoval or replacing the large mirrors except at such an angle as would be at the least very inconvenient. And further if the lower pier had been made according to drawing its width would have prevented the telescope being brought to the meridian on either side.

Additions had to be made to the Finder Telescope, as no convenient

means for adjusting it parallel to the large telescope had been provided. A new bearing with centering screws was therefore made to replace the original bearing which admitted of no motion. It was also found necessary to put a focusing tack and an illuminating arrangement to the finder

The final fittings of the telescole were not completed till early in July as the building for its protection was not thoroughly finished until then. Observations were, however attempted as early as April but the instrumen was not in fair working order till the middle of August, from which time observations have been carried on regularly.

The micrometer, which had not arrived at the time of the last Report reached us in July and the spectroscopic apparatus in

September

In a report on the state of the Great Telescope which I furnished to the Honourable the Commi sioner of Crown Lands and Survey in December list I referred to a photographic apparatus which I had incidentally Larnt was ordered by the Telescope Committee of the Royal Society to be made I stated It was supposed that the on, and vote would have been sufficient to cover the expense of a suitable photographic appliatus but the many extra expen es incidental to picking shipment, &c exhiu ted the avulable funds The loy il Society of London however deeming it of great importrace that the telescope should be fitted for photographic worl kindly tool it upon themselves to order the requisite appliances, which I believe are now in course of construction by Mi Grubb, the muci of the telescope We are not yet informed of the exact cost of the apparatus but it will be necessary to icheve the Royal Society of its self-imposed builden, I have hid no intelligence of this apparatus beyond that conveyed by Mr Grubb in letters to Mi I believe it is in course of construction but I have no definite knowledge of the fict, or of its probable cost when completed

The telescope has now been fairly at work for seven months, but unfortunately the frequent cloudy and hazy weather which interfered so considerably with the transit and zone observations very much limited the number of nights upon which good work could be done

At first the large mairo (called A) was mounted in the telescope but the definition with either of the small mirrors was not good and it soon got strongly tarnished subsequently in September mirror B was substituted and the telescope performed much more satisfactorily. With respect to this and other matters, Mr. Le Sucur reports to me as follows—

"The general worl with the Reflector has consisted in the exa

min ition of the nebulæ For obvious icasons those already figured have been specially ittended to and this progress has been made both in their delineation and spectroscopic examination

As might be expected the nebulæ as seen with the Melbourne Reflector in many cases differ considerably from the Cape of Good Hope drawings but is far as may be judged at present the differences do not appear to be greater than might be expected from the difference of the instruments. An exception however must be made in favour of the nebula in Algo, whose present appearance is not readily accounted for except on the supposition that enormous changes have talent place since the date of Sir John Heischel's drawing. Spectroscopic observations of the stur η in this nebula and of Jupiter have afforded interesting results.

Of worl out of the usual course Neptune was examined on many oceasions when near opposition but the closest attention tailed to detect a new satellite or to afford any su pieron of peculiarity in the figure—the position of the planet—however was unfavourable and the atmospheric conditions on no occasion unexceptionable

Winned as periodic comet was pieled up early in August but was not observed for position before October a set of observations were then made extending to October 25th, unfavourable weather preventing the following up of the object to a later date from accounts, however which have reached us it appears that the Melbourne telescope was by a few days the last in the field

I argo mirror A was tall on down and replaced by B in September the definition of A in combination with either a or b was not satisfactory—the reason for replacing it by the other, however was on account of its tarnished condition

The performence of the combination ba as regards definition was considered much better than that of Λa or Λb a however being considerably transhed was talen down and replaced by b but it was found that to use this combination with advantage a more extended motion of the small mirror sum was required a which in the meantime had been polished we therefore replaced and has been at worl satisfactorily for the last five most the b remains in statu quo. A slight mechanical alteration of the focusing arrange ments will in it out those the use this inition without refiguring its definition is equal to a s

In reference to the Melbourne telescope the President of the Royal Society of London Sir Edward Sabine in his annual address delivered on the 30th of November 1869 says. Its performance since election does not appear to have given altogether the same satisfaction at Melbourne that it did at Dublin but the defects complained of may unserpully from an imperfect I nowledge of the principles of the instrument and inexperience in the use of so large a telescope partly from experimental alterations made at Melbourne and partly from atmospherical calcumstances. Those who are acquainted with the difficulties which Sir J. F. W. Herschelexperienced at the Cape will not be surprised that they should be felt at Melbourne to a much greater extent on account of the far pleater size

of the speculum But I have no doubt that, if the instrument be kept in its original condition and as carefully adjusted as it was in Dublin, it will perform as well in ordinary observing weather. Now this would convey a wrong impression and I do not think the defective performance alluded to can in any way be accounted for by this supposition—the principles of the Cassegian telescope are fully understood no experimental alterations have been made except such as were actually required to act the telescope to perform at all and from all I can ascertain the adjustments have been far more carefully and critically made than they were in Dublin. No simpler explanation of the defect can be made than that mirror A is not good

On this point Mi Le Sueur remarks — With reference to the paragraph in Sii Edward Sabine's address to which you have called my attention I be, to state that the only alteration in the optical arrangements concerning the necessity of which there is any question

is the insertion of an opaque annular disk at small millor

'This disl at first met with much opposition on the part of Di Robinson and Mr Grubb but the former (who has had more experience with Cassegrains than any one) now access that the disl is necessary if the eyestops are retained in the places originally assigned to them by Mr Grubb

The disk can have no injurious effect on the definition ats sole disadvantage is the interception of a small percentage of light but this is in some degree counterbalanced by an increase of the field of view consequent on having the stops in a position nearest to the cycles.

lens than that which may be considered the normal one

Possibly for certain purposes the inerce c of field is not of so much consequence as the slight diminution of light but it my rate the disk solves in a ready and effective manner the difficulties introduced by the mal ers themselves who evidently intended that the stops should retain the positions which they now have. I illude, of course merely to the distance of the stop from eye lens the lateral adjustment is so simple that any error therein of sufficient magnitude to produce any disturbing effect is entirely out of the question.

The mirror A on the polishing machine will have to be repolished before it can again be used. There seems to be some peculiar condition of the metal which appears to render it more liable to tunish than the other. A kind of reticulation of the surface is apparent and, on microscopic inspection masses of good coloured speculium metal seem to be interlaced by a redder alloy that oxidizes more readily than the white part—a kind of segles ition has evidently

taken place

Nearly everything is prepared for the operation of polishing. A test-object is erected in the park at a convenient distance from the machine and a platform for testing the figure during the operation has been provided and most of the minor arrangements for preparing the polisher are complete. No proper rouge is obtainable here and a quantity was ordered several months ago from I ondon. We shall probably have to eventually make it on the spot. The preat-

delicacy and difficulty of this operation is fully appreciated. Mr. Le Sueur had the advantage of watching the process of granding and polishing in Dublin, and has since had some practical experience and as the same apparatus with which the mirrors were first prepared will be used there is no good reason why with proper one the repolishing should not be performed successfully. In the case of the small mirror α the polishing was satisfactorily accomplished a good reflecting surface was recovered, and the figure (which is a

very critical aff in) is certainly as good as at first

It is a somewhat difficult matter to speak critically of the merits of this telescope, as our only standards of comparison are other large reflecting telescopes of which there are only three in the world that icide the dimensions of this namely Herschel's Loid Rosses and Mi Lassell's and these we again of a different form which renders even a comparison difficult. I have had no experience with the reflectors in question. Mi I'c Suem however observed with Loid Rosses for some time and his impression is that even allowing for the difference of aperture (Loid Losse's being 6 feet and ours 4 feet) the definition of ours with milior A was not so good. So far as I can speak from practical acquaintance with this reflector. I was not sutafied with the perform use of mirror A in either combination of small mirrors on the planets, as well as on stars, the definition was very unsatisfactory.

Lut millor B performs very much better and the telescope will now doubtless complie favourably with others of its class and di mensions. Mr Le Sueur entirely coincides with me in this expres

sion of opinion

The experience which can only be obtained by years observing with linge reflectors is the only safe guide in forming an opinion of the comparitive ments of a telescope of this lind and that it is an experience which no one outside of Great Britain possesses at is more than probable therefore that the want of it has led ourselves and others to expect more from optical science even in its present advanced state than we had any right to and that we looked for as comparitively a perfect telescope as is sometimes obtained with smaller apertures

What has been done however, unmistal ably shows that it is capable of graspin, the worl for which it was originally intended Though perhaps not reaching that perfection for feature-work of planets which was hoped for we have no reason to doubt that it will be fully up to our anticipations with respect to celestral photography

As fur as the mounting and much initial arrangements are concerned when we consider the immense mass of the moving parts and the methods hitherto adopted for large reflectors, we have every reason to be satisfied

M: Grubb's Remarl's on the Specula of the Great Melbourne Telescope and the Melbourne Reports connected therewith b

The metallic specula supplied with G M T consist of two large mirrors (denominated A and B), and two small (a ind b). Mirrors A and B were cast from the same admixture of metals previously prepared. Speculum A is that which was generally used here during the temporary election of the equatorial mounting and which was fully tested and approved of by the Lelescope Committee of the Royal Society. Speculum B was not considered as finished at the time of the Committee meeting here for the trials. It was subsequently polished and finally approved of by Mi Le Sucur my son and myself as fully equal to speculum A. The specula were in accordance with the instructions of the Committee previous to packing coated with a solution of shell lar m alcohol, as practised by Mr Lassell.

Having thus premised I turn to the Melbourne Report for the

last year which at page 12 states as follows —

At first the large mirror (called 1) was mounted in the telescope, but the definition with either of the small mirrors was not good, and it soon got strongly tarmshed. Subsequently in September, mirror B was substituted, and the telescope performed much more satisfactorily?

All which is readily accounted for by statements in letters pic

viously received here from Mr Le Sue ii vi/ -

1st I hat he found it improcticable to entirely remove the shell-lac coating

2nd That with his best exertions, the surface remained stiely

in parts

3rd (On being questioned as to the particulars of his process and the possibility of his having used methylated spirits instead of alcohol) he idmits hiving used methylated spirits and states his process to have consisted in brushing it over the surface and then mopping well with with (He excuses the using of methylated spirits as having been overruled by Mi Ellery). In his letter to Professor Ellery published with the last Melbourne report, the process is again described, but with no essential difference. It is verbalim as follows—

Ine values was removed from mirror A in the following manner —Large meess of cloth were placed on the surface and saturated with methylated spirit—when the variash was sufficiently softened as much as possible was removed by mopping up with the incloths (this process was repeated many times) distribled water was then freely used and finally pure alcohol."

The Melbourne Board referring to the process mentioned in the above extract from Mr. I e Sueur's letter states that 'It is difficult to see how it can have had my deleterious effect upon the polish of the speculum.

the speculum

No such difficulty, however exists on considering the intionale

^{*} Excerpt from a pamphlet by Thos Grubb FRS March 23 1870

of the treatment which includes the deposition on the nolished surface of a substance diffcing essentially from the original and only soluble in very strong alcohol I cannot understand how Mr Le Sucur came to the conclusion stated in his letter, in the appendix to the report that the method he employed could not be supposed to have any deleterious effect on the polish after stating, as he had previously done that he found it impracticable to entirely remove the shell lac conting and that with his best excitions the surface remained stiely' in parts and afterwards the speculum tarnished auicl ly

The process was radically bad and it is evident by his own statement that the surface was after his attempts at cleansing it left in an unclean state and to expect under such cheumstances that it

would not tarnish and that quielly would be quite absurd*

I shall here add a few corroborative facts vi/ -After months of use at Dublin this speculum surface exhibited no tunish 2nd After the speculum arrived at Melbourne (some portion of the surface being denuded of variable probably with alcohol) it was described in the report for that you as chibiting a very fine polish" Speculum L cust of the same metal and coated with the same vainish as A has according to Melbourne reports been really ele med from the varmish and has not since shown sensible tarnish, although the soap used in cleaning it was hill ely to have dimmed it 4th The centre piece of eight inches directer cut out of speculum A forming it's central hole, was polished here shortly after speculum A had been, and on several occusions at has been coated with the lie vurnish, which after remaining for months, has been removed without difficulty simply by alcohol (but no water) and without injury to the surface which still remains in good worling order. There is abundant evidence especially in the list item of the foregoin, to show that speculum A his be

A somewhat different statement appears from Mr. Le Sueur in his letters in the appendix to the report. He say that after his cleaning process the mirror A was then family bright and appened perfectly clean close examina tion afterwards showed that a funt trace of his still remained on the surface which become consider bly tarnished after short use

He attributes the turnship which ensued not to the thin film but to the metal (although marror I of sume metal has not sensibly turnshed) and he attributes the street y mail ; which he could not remove not to his own imper fect removal of the film but (contray to all evidence) to the brush used in

laying on the varia la here

Aspecting mutto I has letter dores udstries. That the vurnish was removed from I by means of niphtha mopping is before wishing with soap and water and finally with distilled water. The muttor though at no time very bright is still in fur worling order. From the last statement (this murror having left this with in excellent polish) I conclude that it also has suffered though compared with muror A but little from the water proces thou h probably innocuous in itself appears to have the property of throwing down other sub tances upon the polished surface. Lor mistunce if on stopping the polishing machine the wet polisher be illowed to remain stationary for a short time on the speculum a distinct impression of the pitchy patches of the polisher may be observed. Mr I e Sucur had opportunities of witnessing this while here. Why he used water at all more especially in the case of speculum B I cannot explain

come unfitted for present use, solely from injudicious treatment at Melbourne

Referring again to the paragraph of the report which states

that--

'At first, the large mirror A was mounted in the telescope but the definition with either of the small mirrors was not sood and it soon got strongly turnished'

Now with respect to mirror B

This mirror B appears from the report to have been for some

time in use with the small mirror a

The only fault found apparently with the telescope so constituted is that it gives a slightly cluciform image of a stal—a fault which did not appear when mirror B was finally tested and approved of here as being fully equal in definition to mirror A. The fault is not therefore fairly attributable to the large speculum B but probably to the small mirror α which was repolished at Melbouine, as nothing short of the most scrupulous care in the supporting of a mirror on the polishing machine could insure freedom from strain during the polishing and a perfect figure when removed

The usual and palpable methods for ascertaining where the defect lies (such as turning the small mirror round in its cell or substituting the other—unrepolished—small mirror) do not appear to have been tried. Neither was examination made of whether any of the balls of the supporting levers of the large speculum had got out of place during the transit (a thing quite possible and which actually occurred in the case of another speculum lately constructed

here)

Whatever be the cause of this appearance, it must (judging from the accounts of the astronomers) be very slight. Mr. Le Sueur writing says. It is not a conspicuous feature by any means nor is it permanent, and that it most probably alose from some abnormal condition of the levers, and that once remedied, they would get rid of this cruciform image while Professor Ellery (the Govern ment astronomer) in his report states that the milion B performs very much better than A that the telescope will now doubtless compare favourably with others of its class and dimensions and that Mr. Le Sueur entirely coincides with him in this expression of opinion

XXIV Sir Edward Sabine to Mi Verdon

13 Ashley Place May 16 1870

 $\mathbf{M}\mathbf{y}$ dear \mathbf{Sir}

The accompanying correspondence originated in a letter (No 1) addressed by Mr H A Severn, of the Union Bank of Australia at Melbourne, to Mr Charles Watkins Merrifield a Fellow of the Roy il Society of London by whom it was officially transmitted to myself as President of the Society in a letter which is maked No 2 Copies of these letters were without loss of time, forwarded to the

Members of the Committee by whom the one ous and responsible office of superintending the construction of the Great Reflector for the Melbourne Observatory had been undertal en and in addition to these gentlemen at Mr De La kues suggestion to Sii John Herschel who had talen an ictive part in the correspondence which preceded the undertal ing No 3 is Mi De La Rues reply No 1 Sir John Herschels and No 5 is Dr Lobinsons

It has appeared to me the most fitting proceeding that you should be furnished with copies of these letters with a view to their being known to Mr Ellery the Superintendent of the Melbourne Observatory and I beg therefore to transmit these copies to you with

a request that they may be brought to Mr I llery's notice

I remain my dea Sir Very sincerely yours

LDW UD SALINI PRS

I S Copies have also been sent to Mr Merrifield

G F Verdon, Esq CB

ENCLOSURES

Mr Merrifield to General Sir Edward Subine (No 2)

Institution of N wil Architects
9 Adelphi Lerrae London W C
April 22 1570

Drar Sir Edward

I have received the letter of which the enclosed is a copy, from an old friend of mine whom I know to be a clever and shrewd practical man and not without experience of telescope worl. He has made his own instruments as well as used them. Beyond this I have no I nowledge as to how far his acquaintance with the subject extends. It is one of which I have myself no experience whatever

I think, however I shall be doing what is right in sending on his letter to you as it contains some statements to which you will know, far better than I do what weight to attach, and which therefore I ought not to keep from you

I report however that I am not myself expuble of forming any

opinion whatever on the subject

Believe me, dear Sir I dward,
Youis very truly
Challes W Merriceld

To General Sir E Sabine, PRS

Mr H A Screen to Mr C W Merrifield, FRS (No 1)

Union Bank of Australia Melbourne Reb 27 1870

(Copy)

MY DIA MIRITITED, As I have been rather retive (for a long time) in a fight against

the Great Melbourne Telescope, and as it is very likely that the subject will be discussed by your Royal Society, it may be 11, ht that you should know why I maintain it will and must prove a failure!

The first requirement in order that a reflector may work well is equiformity of temperature, in order that the molecules of the metal of the speculum may be at rest. Now as we very often have the temperature 136° all day and perhaps in the evening it at once (in two hours say) falls to 60° and these changes with more or less vigour so on all the year round how I ask can we expect a 4-fect metal under such cucumstances to retain it form? Were it a front view of Newtonian it certailly would stand a better chance but how can we expect the 4 feet metal to retain even a decent focus here more particularly when its errors are of course aggravated by the small convex speculum What do you suppose is the length of the focus or aberration in one metal? The least is 5 feet 6 inches, the other more Mr Le Sueur tola me this himself, and yet in the face of this tremendous distortion Ellery who is unpleasantly placed (the Government Astronomer) here pretends that it is a success and is indeed the cause of your General Sabine running away with conclusions drawn from wrong inferences n Aigo is very much smaller and we in the south are all well aware of the fact but of the displacement of the star η (of course by the translation of the solar system) with respect to the nebulæ around we are by no means so certain The big instrument so disfigured Orion that I am strongly of opinion that the conclusions arrived at cannot be confirmed. The instrument has cost us colomists £14000 and whatever it was in Ireland and however well it defined there it is beyond all doubt very far from perfect in this country

The difficulty of collimation is all but insuperable and when perfect at one elevation sets out at any other. Fincy how jolly! I suppose for the same money we could have got a 20-inch refractor!

These itemails infer to it ubject of much importance to us—to me in particular as I predicted the effect of temperature long before is was set up—and though I am contradicted those who know are gradually giving way. As I have profound respect for you and for any opinions of remails you might male in this matter, I have on that account stated only facts—I commit them to you as facts—you can therefore male any use you please of them

It is a grievous failure—it will certainly go fai to prove the error of constructing a large Cassegrain, or any kind of acflector, for this country

(Signed) H A Severn

Mr De La Rue to Sir Eduard Sabine (No 3)

The Ob ervatory
C1 n'old Middlesex W
April 26 1870

DEAR SIR EDWARD,

I return you Mr Merrifield's and the copy of Mr A Severn's letters

In the first place at is quite true that great and lapid changes of temperature do interfere with the performance of any telescope and more with that of a reflector than with that of a retractor

Change of temperature interferes chiefly by causing currents of air within the tube and about the metals and not nearly so much by any change of form of the milior. No doubt that if any one part of the milior were heated then this local heating would distort the figure but I do not believe that the changes of temperature which occur in a day would makinally affect the figure of the milior because they could only very an idually and partty uniformly increase the temperature of the metal

Rapid and great changes of temperature would affect nearly to the same extent the periormance of Cassegranian Front view or Newtonian because the chief disturbance is from currents of differently heated air passing before the mirrors and along the tube

My opinion of the value of the steat Melbourne telescope is in no way shallon by Mr. H. A. Severn's remails. By diligently working the seat Melbourne telescope much may be done to advance astronomical knowledge. Of course some day in the year will not be so good is others and the bad days may be more frequent than in Frightial accertheless good work can be done with it. I think you may send Mr. Severn's letter to Dr. Pobinson, there is nothing contained in it of which he cannot easily dispose. I suppose the cot of the great Melbourne telescope placed at £14,000 by Mr. Severn is crioneous.

Sn John Heischel could give us the benefit of his experience at the C η α with an 15 in α I would recommend the letter being sent on to him, and you are at liberty to send this also

I am,
My dear Sir Fdwaid,
Yours very sincerely
Warren De La Rur

Su J Herschel to Su Edward Sabine (No 5)

Collingwood April 28 1870

My DIAR SIP LOWILD,

Any change of temperature, if apid enough to affect the surface of a speculum to a sensible degree before reaching the interior by conduction, must of course bring the metal into a state of strain. The ques-

tion is how this will affect its optical action Much will depend on how the speculum is supported If it rest on a bed of badly conducting material as was the case with mine the polished surface will be expanded or contracted sooner than the bacl and (tal in, the case of contraction by cold at night after a hot day) the polished surface will contract in aica quicler than the back the milior will grow more concave and the focus shorter Still since the whole surface is exposed equally and the total contraction is very small I should expect that a change of focal length would be the main optical effect and that aberration (arisin, from deviation from parabolicity) though probable to some smill amount would be but an effect of the second order—a small fraction of a small quantity We had hot days and cool nights at the Cape though not to such violent extremes but I do not recollect ever having reason to complain of this form of annovance

Next suppose the mirror supported at the back on metallic points or bearings of very small area leaving perfectly free access of cold air to the back, and free circulation. In this case back and face would contract equally, and the effect would be that no general flexure of the metal, one way or other, would take place, and the focal length would therefore so far as this (much the most important) cause of distortion remain unchanged. A certain (probably slight) amount of aberration might arise from pressure on the internal mo-

lecules

What Mr Severn says respecting the actual amount of aberration 'What' (he says) do you suppose is the length of is unintelligible the focus of aberration in one metal? The least is 5 feet 6 inche the other more ' (sic in Mi Meilifield's copy) If for should be read lengthening and for one metal" be read in the case of one metal, it conveys no doubt a distinct meaning. But a longitudinal aberiation of 5 feet 6 inches produced by such a cause as change of temperature of 70° in a speculum otherwise perfect of only 32 feet focal length appears to me incredible It would require the extreme ray to be deviated by 31' from its proper direction to effect which the extreme annulus of polished surface would require to become inclined backwards from its proper inclination (tangential to the purboloid) 15' 30" to produce which change of inclination the extreme rim of the metal would require to be sprung backwards by 11 of an inch—a quantity quite preposterous—enough I should think to break the metal Morcover such an effect would require that the back should contract more than the face

By far the worst effect (and so far as my experience goes, the only formidable one) of rapid changes of temperature arises from mixture of hot and cold air in motion which the rays reflected from the speculum have to traverse before reaching the eye. This is however at least to a great extent, counteracted by the latticed structure of the tube. Still there is (if I apprehend the figure given in the "Correspondence &c rightly) a portion near the mirror not latticed. Would it weaken the structure too much to pierce this with a few large or a great many small holes. Also, would it not be advisable

just before sunrise, to muffle the large mirror up with thick blanketing and stuff the hollow in front with woollen mattresses to keep off that

terrible temperature of 130°? in the day-time?

Arter all there is the telescope and there are the observers it is by its work in its best action and not in its worst, that its as Mr Severn s tronomical efficiency will come to be estimated a priori condemnation, and his dictum 'that it will and must be a failure" may stand for whatever may be supposed to be its worth but I thin Mi Illery and Mr Lo Sueur will do well not to be di cour Led by any such denunciation but keep steadily working on and above all things (as an immediate object), send us home some careful and dependable drawings both of the nebula in Argo and that of Orion (which Mr Severn says it disfigures) as seen in it under as favourable cucumstances as the climate on the whole affords and leave us to judge of the amount and nature of the disfigurement

T remain My dear Sir Edward Yours most truly J F W HERSCHEL

Rev D: Robinson to Sir E Sabine (No 5)

> Observatory Armagh May 7 1870

My DEAR SIR EDWARD SABINE

It is a curious coincidence that so soon after my letter to you on the matter of the great Mclbourne telescope in which I referred to the misrepresentations about it, such a notable specimen of them

should have reached you!

Mr Severn in his letter to Mi Merrifield shows so great an amount of prejudice and his animadversions have been so well answeicd by Sir John Heischel and Mi Warien De La Rue that I should not have thought it necessary to notice them, but for some points showing singular recklessness in assertion, which neither of those contlemen have touched on

The first of these is his statement that at Melbourne 'the temperature often reaches 136° and falls in two hours to 60° ' and that ' these changes, with more or less vigour, go on all the year

round"

Now it is incredible that the temperature in the telescope-house can rise to anything like this during any part of the day, especially if the roof be (as I suppose) painted white The only information I have as to the temperature of Melbourne is derived from The Discussion of the Meterological Observations at Melbourne during the years from 1855 to 1863" I find there that the maximum observed during those five years was 111° on the 14th January 1862, and that the mean maximum for that month during the five years was 76°8 and the minimum 59°-civing an average diurnal range of As the maximum occurs between 1 1 M and 2 PM

temperature must evidently be much less towards sunset

If Mr Severn has not spol en entirely at random, it may be conjectured that he has given the temperature of a thermometer exposed to direct solar radiation

It is quite unnece sury to make any iemuks on his language respecting Mr Eilery or on his statement that " n Algus is not displaced (of course by the translation of the solar system) with respect to the nebula?

His assertion that "the bis instrument so disfigures Orion that he thinks the conclusion arrived at cannot be confirmed amounts only to this, that it shows that nebula in a very different way from what Mr Sevens telescopes do

That the instrument has cost the colonists £14 000 will probably

surpuse you as much as it does me

His statement that the difficulty of collimation is all but insuand that when perfect at one elevation it gets out at any other' if it have any foundation must have alisen from this, that the bolts which attach the speculum-box to the tube those which connect the two portions of the tube those which attach the tube to the declination axis or those which fix the arm of the smill millor, were not sciewed home at the time he examined it NotLing of the sort was observed in Dublin The lever which support the spcculum are so strong that any tilting of it at different altitudes is impossible The flexure of the tube tends to diminish my change of collimation which can only be produced by a lateral shifting of the mirroi in its box This cannot exceed \frac{1}{10} of in inch and it is easily computed that this amount of shifting can only produce at its maximum an error of 42 seconds

As to his statement that it is is a grievous failure, and will go far to prove the error of constructing a large reflector for this country," it is probable that it will have much less weight with the public than the good work which the telescope has already done, and is doing

I wrote to Mr Grubb about Sir J Herschel's suggestion about ventilating the lower part of the tube, and enclose his answer

Yours ever

T R ROBINSON

Sir Edward Sabine, K C B

XXV Sir Edward Sabine to Mr Verdon

[Extracts]

13 Ashley Place June 20 1870

MY DEAR SIR.

I return M1 Ellery's letter of January 3rd 1, with thanks for its

^{*} This letter refers to a private note addressed by Mr Ellery to Mr Vernon in which he describes the departmental difficulties which had arisen from Mr Le Sueur's entering on his duties as Observer

It throws additional light on the mischief which has arisen for want of Mr Le Sueur being led on his first arrival at Melbourne (several weeks I believe before the arrival of the telescope) to comprehend his true position both in the Observatory and in the Colony, his duties and responsibilities, and where he was to lool for aid in all ways and particularly in obtaining whatever might be found requisite for the successful establishment and working of so novel an Until the letter from the Melbourne Government anived a few weeks ago we had no other information than could be gleaned from letters received by Mr Grubb (the maker of the telescope) from the Colony, or from the private letters of Mr Le Sueur to Professor Stokes by whom Mr Le Sueur had originally been recommended for his present appointment From these last-named letters supplying as they did the only information which the Committee were enabled to give to the public on a matter on which great public expectation existed selections were made and printed in the Proceedings of the Royal Society

I remain, my dear Sir
Faithfully yours
EDWARD SABINE, P.R.S

VVI Sii Edward Sabine to Professor Stol es Sec R S

The Royal Society Burlington House
January 10 1871

Drar Stolis

Mi Verdon whom I happened to meet some days since told me that he fully believed that Mi Le Sueur had finally decided on resigning his post at the Melbouine Observatory. As yet I am not aware that any notification to that effect has been addressed by him either to the President of the Royal Society of to the Chairman of the Lelescope Committee from whom he accepted the appointment carrying with it instruction at the Cambridge Observatory, at Mr Oc La Rue's Observatory at Lord Rosse's Observatory, and at Mr Grubb's Manufactory all given in the view of his future usefulness at Melbouine. It is quite possible that such a communication may be on its way from Melbourne.

(Signed) EDWARD SABING PRS

XXVII S.11 Edward Sabme to Professor Stoles Sec R S

The Royal Society Burlington House
February 9 1871

DIAR PROFESSOR STOKES

I have recently been informed officially by the Agent General for Victoria that Mr Le Sueur has resigned the appointment which he had accepted in the Melbouine Observatory as Observer with the Great Telescope recently completed for that Observatory under the superintendence of a Committee of the Royal Society Mr Verdon made no statement of the causes which may have led to Mr Le Sueur's resignation of an appointment for which he had been recom-

mended by yourself, and had received in consequence of that recommendation much valuable instruction at the Observatories of Cambridge, Cranford, and Parsonstown As the continuation and completion of the "Correspondence 'regarding the Melbourne I clescope printing by the Royal Society, is now in hand and as it my be deemed desirable by the Committee of the Royal Society that some statement from Mr Le Sueur himself should appear in that publication, and as I have learnt indirectly (from yourself) that Mr Le Sueur is now in England I would venture to suggest to him through you (to whom his appointment was due), the expe diency of his furnishing the Committee with a statement, if he thinls proper to make one of the reasons which caused his resignation such statement being one that may suitably be included in the completion of the publication referred to It may be addressed either to the Committee or to myself, as Mr Le Sueur may prefer If to me it will pass at once into the hands of the Committee

(Signed) EDWARD SABING PRS

XXVIII M: Le Suem to Professor Stoles (Copy received by Sir Edward Sabine subsequently to February 9th 1871)

Melbourne Observatory May 21 1870

DEAP STR

I am sorry to inform you that, after mature consideration, I have decided to resign my office in connexion with the Melbourne Tele-

The trammelled position in which I am placed is so far different from that which in taking office I had every reason to expect and above all is so damaging to the work that I can no longer accept

its conditions

Please convey to the Members of the Committee my deep regret at feeling mysciff unable any further to carry out the mission entrusted to me if, however I had thought that the work would suffer by my abandoning it I would have endeavoured to school myself into a resigned acceptance of conditions, however in some and unsatisfactory

Nearly all the nebulæ figured in the CGH have been reviewed, and the information gathered will serve as a good groundwork for

future reference

I have taken the precaution of fully instructing as far as lay in my power the assistant workmen and others here in the manipulatory details of polishing. Since the wet weather set in I have been constantly engaged in frequent repolishings of small miliors which I have produced here. I hope moreover to repolish large mirror A the experience gained on the small ones makes me feel more confidence as to the result than I at first intempated.

Yours very truly
A LE SULLI

Abstract of Dr Irohenson's Description of the Great Well name Telescope

This telescope has been immutely described and the details of its construction explained it considerable length, in a piper published in the Philosophical Transactions, 1869 by the Lev T R Robinson, D D & L S the Chairman of the Lelescope Committee and An ibstrict of it confuning some of the T Grubb Lsq F L S most interesting particulars is given here to complete the continuity of the correspondence

Of the introductory put it seems only necessary to give the motives which induced the Iclescope Committee to select a ic flecting telescope instead of an achievatic and the Cassegrain in-

stead of the Newtoni in form of the reflector

Dr Robinson has shown that the intensity of light after two ic flections from speculum metal allowing for the light intercepted by the small mirror is 0 401 the coefficient for the intensity of light trans mitted by an achromatic is not so simple for it values with the aper ture of the object glass Its expression is exponential, which is given the constants depending on reflection it its four surfaces being com puted from Fresnel's formula, and the constants of absorption being determined by a series of photometric experiments on object-glasses and specimens of optical plass. It follows from this that an achromatic equiluminous with 1 4-fect reflector must be 34 4 inches sent there is no probability that such an object-slass could be con structed if practicable its cost would be enormous and the diffi-The selection of the culty of mounting and uans it very sreat Cassegrain construction was not made without considerable discussion it has been little used probably in consequence of Newton's objections to it the principal of which was that less light is itfleeted by its small minor at in incidence nearly perpendicular than in the Newtonian where the incidence is 45° This is true for re In these as his flecting surfaces lile glass but not for metals been shown both by theory and experiment, the reflection decreases from the perpendicular incidence to one depending on the incidence of maximum polarization and then increases till at 90° the reflection M Jamin has shown that for speculum metal the intensity of red light is at a perpendicular incidence 0 692, but for 45° only For the other 13ys the intensities are less, but follow the same law so that the advantage is actually in favour of the Cisse grain its principal defect is the magnitude of the second image which is misnified by the small speculum from 5 to 6 times therefore is unfit for photo, inplut purposes and requires eyepieces of great focal lengths to give the lower manifying-powers but this is far more than counterbulenced by the observer being always near the ground, and requiring to shift his position but little for considerable movements of the telescope, while in the Newtonian of equal power, the observer must be supported by an apparatis moverble through a large space in azimuth and near the zenith requiring an elevation of little less than 40 feet the employment of which is laborious and may be dingerous

For a Cas ega un on such a scale Dr. Pobinson did not think at safe

to trust to the formulæ usually given in treatises on optics, and determined its constants on the following assumptions. In the Cassegrain it is necessary that an eyestop should be placed behind the eyepiece (supposed to be Huygheman) at a distance from its second lens a little more than half the focal length of that lens and of a diameter equal to the image of the large speculum formed by the small one and the eyepiece

(1) The eye placed close to this views the list image at the distance V=the distance of minute vision. Knowing V and the distance of the eyestop from the lens it is easy to deduce the positions of the 4th 3rd and 2rd images with respect to the field lens of the eye-

prece

(2) The opening of the large speculum should be is large as the

aperture of the small one

(3) The aperture of the field lens of the lowest power should be of the same size, that the largest possible field of view may be obtained

(4) The lowest power must be such that the eye may tale in the whole of an emergent pencil

(5) The aperture of the small mirror must be able to receive all

the light reflected by the large one

From these considerations a quadratic equation is found giving in terms of I nown quantities the tocal length of the field-lens of the lowest power and from this the other constants of the telescope are determined, except the focal length and aperture of the gicut speculum, which are selected by the optician

Of these quantities M the lowest magnifying-power is found by dividing the aporture of the great speculum by the breadth of the emergent central pencil at the cyestop. According to Sir W. Heischel this breadth cannot exceed 0.2* and therefore M=240

n the ratio of the aperture to the focal length of the lenses 15 generally made by options 0.5

There is some doubt about V but the value (8 inches) adopted by Sir W Heischel seems entitled to most confidence

- is nearly equal to the diameter of the emergent pencil

The constants computed for the telescope were—

Lai se speculum focal F=366I arge speculum apertui e A=48Smill speculum focal f=7471Smill speculum apertui e a=905

Distances of 1st and 2nd images

From the second speculum

$$d = 33231$$

$$d = 33231$$

$$d = 33231$$

Towest power, focal $f = 16\ 10$ M=240 field of view $\theta = 14\ 32$ equivalent focus=1994†

Fin uch a telescope as the Great Melbourne Telescope this can only be true for famt objects as a star of the first or second migritude is so builting that the pupil contracts to a diameter considerably less than this but the telescope was primarily intended for nebular

the extra nity of the field of view some of the rays about a minth of the whole would be lost. But this may be obviated by main a somewhat larger than the

computed value in the Great Melbourne Telescope about a seventh

As soon as these were decided on the contract (which, beside the telescope and duplicate large speculum included an apparatus for polishing and a steam-engine for worling it) was signed at the close of February 1866 and the worl was unsed rapidly forward. Of this the most important and at the same time the most difficult put, was the formation of the large specula. The alloy of which they were cast was Lord Rosses, composed of four equivalents of copper to one of time it possesses more power of resisting tarnish than those which deviate a little on either side of this proportion and is probably as reflective as any. The liability of good speculum includes the tarnish is much eveggerated when due precautions are not tall on

(1) The operations of casting and innealing were conducted essentially is described by Lord Rosse, with such modifications as the cast required or as were indicated by experience. The plan for lateral support of the speculum proposed by Mr. Grubb requires that the speculum should be cast with a central band about \(\frac{1}{2}\) inch thick and \(\frac{1}{2}\) of the speculum s thickness in breadth. The edge of the mould was therefore formed not of saud but of a strong sheet-inon hoop. Inches deep and of the same diameter as the bed of hoops which in initiation of I ord Rosse formed the bottom of the mould. It was stronglhened internally with rings of angle-inon and its lower edge turned true and it was lined with form moulded to the required shape. When this was fully dried it was a tached by clamps to the bed of hoops, and the joint luted with a little wet loam.

(2) A peculiar arrangement was applied to support the mould It was at first attempted to cast the speculium with its central opening by attaching to the centre of the bed of hoops a core 5 inches in diameter there was reason to suspect that the waves of melted metal which were formed as it passed this core did not unite per teetly at least in the direction where they met there were seen that surface mail mass (called by Lord Rosse crowns feet.) which

indicated such imported union

To provide for a more regular diffusion of the melted metal over the mould, the cast from frame supporting it was made to turn it the end next the crueible parallel to that of the endle which shall be presently noticed. The other end was a used or lowered by a wedge driven by a rich and prinon under the floor which again was a trivided by a vertical shaft at a convenient distance from the east ing. As the central core interfered with the free flow of the metal it was rused 1½ inch above the surface of the mould and properly supported there

Fig. 1 is a plan of the casting- and annealing 100m. 30 feet long by 16½ wide. A the hot health for heating the bed of hoops which (15 described by I ord Rosse) forms the bottom of the mould at consists of four low pillars of brief with intermediate grates for coke fires

b is the melting-funnce it is similar to the common briss founders furnce. Its internal dimensions are 42 inches square by 69 inches from the top to fire-bus with a central pillar rising 15 inches above them to support the crucible.

C is the mould as laid for a casting and at

D is a chane which commands A B, and C it also commands I the open chadle seen in section (fig 8), in which is placed the

crucible full of fused metal previous to pouring

F is an inclined causeway leading to the mouth of the annealing-This oven was constructed with great care it is circular to ensure uniformity in the cooling of the enclosed speculum, and is strongly bound with a massive band of iron to prevent its cracking Upon a thick foundation of rubble-work were laid several courses of bird with a layer of sheet iron interposed to prevent moisture using from the ground and on this were constructed the fireplace and flues for heating the bed of the oven This bed is formed first of several courses of fire bricks, on which are laid fire-tiles 12 inches squire previously ground separately to the required curve and then set so as to form a continuous bed of the radius required for the under side of the speculum. The circular wall of the oven is 27 inches thick and some details of its construction are shown in hgs 1 & 8 The system of flues below the bed, of which one or more can be readily stopped if required, gives great facility for heating it equably and the wall and arched roof of the oven (which was covered with 10 tons of sand) are heated by a mixed fire of col e and turf burning in the oven itself the combustion being regulated by its independent air-hole damper and chimney For the quick opening and closing of the mouth of the oven, a series of east-iron stoppe s were provided coated internally with loam and with removeable handles outside These when in situ complete the circle of the wall and give great facilities for opening and closing the oven when the speculum is introduced

A single crueible of cast non-holds enough of metal for a casting it was east with the precautions indicated by Lord Rosse. Its internal dimensions are 25 inches diameter, 32 inches depth. The bottom is round and its thickness is from 2 inches there, to 11 inch at top. It easily holds 30 cwt of the alloy, 27 cwt being required

for a 4 feet speculum

The speculum A was cast September 22 1866 For eight previous days the unnealing-oven had been he ited up to a full red The furnace was lighted the evening before and the charging the crucible commenced at 2 Au At first the alloy was supplied slowly for fear of cracking the cast iron crucible, and the cutive 27 cwt was fused at 11 am During the last hour of this period the bed of hoops, which had been wished with two parts immal charcoal and six of plumba, o mixed with ale had been heated on tne hearth A (fig 1) till blue The crucible was now hitted by the come from the furnace, and to insferred to the condle 1 (fig. 1) The tielle of the crane was now shifted from the crucible to the ciadle and tilted till the metal reached its lip—the metal was once more poled and skimmed and by a spidly turning the winches of the crane the pouring was effected. When the metal covered half the mould on one side and at the other rose to the edge of the loimring it its lowest pirt, the mould was rapidly lowered to be horizontal the pouring continued without interruption, and the fluid covered the entire surface with an unbroken wave. The entire time was sixteen seconds. When sufficiently cool the central cook was removed, and the speculum, still on the bed of hoops, was drawn to the oven s mouth. This was effected by a powerful crab placed outside the building acting on a chain passing through the opposite side of the oven and hooked to a bight of chain passed round the bed of hoops the latter was now close to a step formed at the oven a mouth, and the bottom of the speculum was on a level with the oven s bed. The bight of chain was then raised to the loam ring, and the bolts which fastened this to the bed of hoops being removed, the ring and the speculum were drawn into the oven off the bed.

The iron stoppers of the oven already described were set in their places hot bricks were placed outside of them, and the whole luted up. All other apertures including the entries to the chimneys were circfully stopped. In doing this a thermo couple of platinum indiaron wire was inserted so that its joint was nearly over the centre of the speculum, and its elements were connected by copper wires with a galvanometer in Mr Howard Grubb's office, where witch could be lept of the cooling. The initial deflection was 73, and in 23 days it showed that the temperature was nearly that of the

ıtmosphere

Speculum B was cust November 24 without any change and both dists turned out exceedingly perfect but it is little to have got a perfect disk of metal unless it can be figured and polished with equal perfection. For a long time it was believed that these processes could only be successfully done by the hand feeling the action but Loid Rosse found that it could be performed as well and with more certainty by machinery. In this he was followed by Mi I is sell and Mi Wairen De La Lue, and though their methods differ the general principle is the same. The speculum revolves slowly on its ixis while the polisher traverses it more rapidly describing a track which is some continuous curve and crosses it in every possible direction.

Mi Grubb's machine is remarkable for its simplicity, and the

precision and smoothness of its action

Fig 9 is an isometrical view of the guinding and polishing machine A A are strong A shaped castings connected by three collared stay-bolts and nuts and hiving V shaped bearings at top, in which turn the circular ends or trunnions of the hollow prism shaped easting B. This easting is bored through its centre and a circle on its upper side truly faced to it is fitted a spindle with a large face plate, whose under surface applies to the trued surface of the hollow beam for steadiness and which serves to carry the speculum. The lower end of the spindle carries the wheel C by which circular motion is given to the speculum. C being driven by the wheel and pulley D by means of a belt driven from the shaft. To

Let word contusion the roter neo numbers we the same as in the 1 lates in Phil Trans 1869

the framing are attached the brackets L, E, which carry the plate F1 the plate can be raised or lowered to suit different heights, and it carries the horizontal shaft G which, by means of two pairs of bevel wheels of equal numbers, drives the two vertical shafts with their cranks H H. These cranks are adjustable as to length. The rods (I, I) act conjointly upon the lower end of the vertical bar K, and this bar entering a central hole in the grinder (or polisher) produces the requisite horizontal movements in either process. It may be seen that by the adjustment of the strokes of the cianls H, and of the length of the rods I a motion can be produced varying from nearly a straight line through a series of ovals to a circle of any extent and either concentric with, or eccentric to the underlying speculum

The vertical bu K passes at its upper end through a hole in a bar attached to the roof of the building and besides producing the horizontal motion mentioned performs another important office. To the lower end of the bar attaches by a cross ley, a flanged soci et which support the triangular piece I and at its upper end the bar is attached to a lever with adjustable weights, so that a pull upwards in the direction of the bar to any desired amount is provided and thus any portion of the weight of the grinding or polishing-tool in excess of that desired is relieved. The figure shows the details of the system of support as applied to the grinding tool. The central piece L being upheld by the bar K, supports the three straight bars M, and these again support the six triangular pieces N. Thus any portion of the entire weight of the tool is supported from eighteen points.

The following arrangement was provided for the quiel and convenient tital of the speculum while undergoing the process of polishing. To the hollow beam B is attached the apparatus O P Q O being a massive toothed sector P an endless seriew worling in the same and Q a which and pinion with a hand-which. This part of the apparatus serves either to retain the speculum in a horizontal position for polishing &c or for quickly bringing it to the vertical, when by the opening of doors purposely provided in the building, the speculum can be tested on a day object sufficiently distant, and again by a reverse motion of the which the speculum squielly restored to the horizontal position for continuing the process if required this facility of testing the figure is of the highest importance to the case and certainty of polishing without it one would be working in the dul

The first operation on the specula was to cut out with a crown six and sind the disks of metal $1\frac{1}{2}$ inch thick which closed them central apertures. The front was then ground roughly to the upproximate curve. The back was ground flat, and the offset on the code ground true. Then the speculum was placed on the supports to be hereafter described on which it was ultimately to remain, and the granding of the front was completed.

The number was a dist of cust non of the same diameter is the * Better had it been pherical and concentre with the front

speculum and of the same curvature (convex of course) Its surface is divided into squares of about 3 inches, with half inch spaces. It was at flist charact with sand and water, and afterwards with very fine emery and water. The pressure in granding was on an average 112 lbs, and the number of strokes of the machine 32 in a minute and of considerable extent. The speculum revolves once for 14 stroles. The rough granding occupied 650 hours and the fine minding 520 hours.

The polisher is built up of a great number of slips of fine deal laid in layers and crossed each layer being firmly glued and nailed to the next. The face was turned to the requisite curvature, and strongly variabled. This is coated with pitch adjusted to the requisite hardness by Mi Nasmyth's test, this material was rolled into slips of uniform thickness and cut by pressure into $\frac{7}{8}$ inch squares while still soft, and those were applied to the surface of the polisher by softening one side of them over a gase or spirit flame—the intervals between the squares were $\frac{5}{8}$ inch. It is needless to 50 into the details of polishing which have been fully described by Lord Rosse and Mi Lassell beyond remarking that both the pressure and the lengths of the strokes are about $\frac{1}{8}$ of what are used in the grinding

The small specula were polished on a similar machine

As the large specula must be parabolic for the purposes of photography the small ones must be specially figured to match them but in this there is no difficulty

One of them is of Lord Rosses alloy one of Mr Kingsleys alloy, which differs from the other in containing $\frac{1}{4}$ of an equivalent of zinc. This undoubtedly gives a whiter image—and if it be as little liable to tainish as Loid Rosses, will be preferable

The third is of silvered glass, not on Foucault's plan but of a construction described originally by Mr Grubb in 1857. It is an ichiomatized combination of crown and flint the outer surface of which is of a curvature which prevents the formation of a false image. The hinder surface is coated with a thick deposit of silver. It is expected that this will reflect more light than either the metallic specula or one of Foucault's silvered mirrors.

The uncertainty of the polishing process arises from the pitch not being of a proper hardness and from the hygiometric state of the ui. It must be always a very delicate operation though Mr Grubb seems to have reduced the difficulties to a minimum.

But a speculum however perfect cannot perform well unless it be supported behind and laterally so as to avoid any irregular strain on it. For the back support nothing has been found better than the system of equilibrated levers contained by Mr. Grubb for the Aimagh Cassegrain.

Higs 12 & 13 show this arrangement. In fig 12 A shows one of the primary levers, on the ends of which are supported on their centres of privity the two secondary levers B, exhibited in the second and third of the diagram

These is an support six tertiary levers shown in the compartment C of which the four tringular are triple, and the two straight are

double These tertrary levers support the speculum by intervening balls to avoid transverse friction

Fig 13 taken from a photograph, gives a general view of the levers. They are made of steel for strength and lightness, and by a happy device of Mr. Howard Grubb, the secondary levers instead of being as usual placed between the primary and tertiary are placed above the latter nearly touching the under side of the speculum. The balls of the tertiary ones acting when necessary, through holes in the secondary, the result of this is that the distance between the back of the speculum and the bottom of the box is only $3\frac{1}{2}$ inches

Mr Glubb's method of lateral support is shown in fig 10 D is the section of the ring of wrought iron trued after being attached

to the inner side of the speculum box

E another ring of the same material, which fits with a slight looseness on D, and also on the ground edge of the speculum When the telescope is inclined, the speculum pressing on the lower part of the ring E must bring its highest part into close contact with the ring D while the lower part of L is removed out of contact with D which virtually places the speculum under the same conditions as if it were held in a flexible band of the form of the

letter U supported at its upper ends

The tube consists of two parts as shown by fig 15 the lower which is made of strong sheet iron is connected below to the speculum box by three strong bolts. Between two of these is a slit through which, by means of guides passing through two openings above it a cover which fits closely to the top of the speculum-box can be introduced to protect the speculum when not in use. Then also the large eyepiece is replaced by a vessel containing quick-lime to absorb moisture. The upper part of the tube is latticed work made of slips of steel each crossing of which is secured by a rivet. Strong iron rings are rivetted to each end and four strong diaphragms similarly attached at equal distances in its interior. As a proof of its stiffness may be mentioned that a weight of 112 lbs hung at its extremity caused only a deflection of $-\frac{1}{00}$ of in inch

The Finder has 4 inches aperture

The equatorial which carries this huge telescope is not less remarkable. It will be seen in fig. 15 that the polar axis is inverted from its usual position, so that the declination axis and the circles

ire near the ground

The axes are exceedingly massive but from the bountiful arrange ment of their counterpoises, their motion is very easy. That shown at K relieves the upper pivot of the polar axis from its lateral fraction. The same thing is done for the lower pivot by a sector shown, though imperfectly (fig. 15) below the circle 1. This sector is carried by a sliding frame, which is forced up by a screw acting through steel springs so as to relieve any desired portion of the lateral pressure which is about six tons. The pressure on the lower pivot of the polar axis, which is about five tons, is relieved by the apparatus shown at L. The result of these arrangements is that the instru

ment is turned round this axis by a force of 5 lbs at a leverage of

twenty feet

The declination-axis has also its three sets of counterpoises weight of it, with the telescope and counterpoises may be conceived as the resultant of three rectangular components,—one parallel to the polar axis, one parallel to the declination axis, and one perpendicular to both Of these the first counterpoise only appears in fig. 15 the others being concealed in the cube But they are described with great minuteness in the paper

As the size of the rollers is limited by the dimensions of the cube they are not quite so effectual as the counterpoises of the polar axis for it requires 12½ lbs acting at the leverage of 20 feet to turn the telescope round its axis Still one man can raise the telescope from the housen to the zenith in 20 seconds. In reversing it from one side of the pier to the other two men are necessary for quick work as it must be moved in P D as well as in A They do it in 45

seconds

The fixed and differential R circles are seen at R They are 34 inches diameter divided on an alloy of palladium and silver, to one minute, and the verniers read one second

The P D cucle P, of 30 inches diameter divided on the same alloy, reads by its vermers to ten seconds Besides the quick and slow movements of the two axes in which there are several novelties, the clock for moving the instrument in R requires some notice

Its position in the pier is shown (fig 15) at Z, and its governor it hg 31 a is a double fork-shaped frame of gun-metal, in which hang the two T-shaped pieces b and b carrying the balls A and A, 5 mehes diameter, of hollow brass filled with lead These, when not in action are retained near their working angle 45° by the piece

Attached to the steel bars are small brackets, d and d carrying sciews with divided heads, e and e, the extremities of which terminute in small cups to contain pieces of hard leather These, when the balls attaining their speed fly out, rub on the disk B and thus inevent any increase of speed. The lower bearing of the governor s spindle is attached to a sliding-piece C which is raised up by a mechanism, which moves an index in front of the clock frame plaving round a graduated arc, and kept in any desired position by a pin and a circle of holes When the clock is adjusted to side eal time, small differences as in the case of planets, are corrected by the mech mism just mentioned

For the moon, the change to mean lunar time is made by a set of differential wheels, which are brought into play in an instant, and

the final adjustment to the moon's rate made as above

The clock is connected by the shafts and gearing, e (fig. 15), with

t screw worling on the teeth of the clock sector D

The sector, of sun metal 5 feet radius, is fitted to turn accurately on a portion of the polar axis immediately above the hour circles hati fordingly preclutions were taken in cutting the teeth of this sector, which are believed to be as exact as many dividing engines The framing of this sector carries at 3 feet radius a tangent screw communicating with the A clamp by a nut of peculiar construction When this clamp is free the instrument can be moved in A by the quick motion G When clamped, if the clock-work is in motion the telescope follows the object but it can be moved independently by the trapent screw vide fig 22 (See the paper in Phil Pians)

Mr Grubb had intended to supplement this clock-motion by a contrivance controlled by an ordinary seconds pendulum, which was to add or subtract motive power but this was not found necessary. The clock has great excess of power over any resistance lilely to come into play and it was found that doubling its actual driving-

weight (200 lbs) accelerated its rate by 3 to

The telescope has nine powers rangin, from 220 to 1000. It has also a micrometer, whose wires and bars are illuminated in a dark field by a peculiar apparatus. In this the light of a lateral lamp is received upon a concave speculum inclined at an angle of 45°, and placed so far in front of the wires that the rays of the lamp come to a focus on them. There is an aperture in the centre of this million of such size as to transmit to the eye all the light reflected by the large speculum. Now, in the Cassegian it has been already mentioned that there is an eyestop so adjusted as to exclude all light but that which comes from the great speculum therefore it is evident that no direct light from the mirror can reach the eye while the wiles will be seen illuminated. The light of the lamp is modified by coloured shades to any degree of intensity

The micrometer has powers from 300 to 600

Photograph—Some photograms of moon and stars til on with a temporary apparatus were considered by the Committee to be of such good promise that they directed a very complete one to be provided similar to that used by Mr W De La Rue with only such modifi-

cations as the great bulk of the telescope males necessing

The small speculum is of course removed before upplying it Fig 35 is a plan, and fig 36 half section half elevation of it AAA is the angle-iron forming the upper end of the telescope to which is attached the steel tripod frame BBB by the thumb serems is a tripod supports the pair of briss tubes e f the steel aims being connected with the outer tube e by the sum met il rings C and D (fig 36) The frame carrying the prepared plate is attached by a convenient arrangement to the upper end D is worled by a level and shaft K shown more fully in the next figures (fig. 37 and 35)

The adjustment for focus is made by the milled head g ($h_n \to 0$) wording the rack and pinion h, while a scale of divisions s is used to register the exact position of the focus. Fig. 37 is a plan and fig. 35 is an elevation of the exposing shutter. B, B B ($h_n \to 7$) are as before, the three aims of the tripod frame. C is the lower of the two gun metal rings to which those are bolted. To this ring is attached by the two mill headed screws h h the gun metal h and h (shown hatched in the figure) which carries the shaft h in h h h to which is attached the thin sheet h is shuffer h as the shaft lettered h in h h h which is acted on from below by the lever h (h h h) and a pair of pirallel cords passing down the

side of the tube. This shaft, in turning through 90° communicates a similar motion to the shaft c, which carries the shutter by the pair of cranls b b and the connecting rod d. As it is desirable to be able to open the shutter from either the right or left side to give a greater or less exposure to a particular side of the moon, this shutter is so airanged that by taking out the two screws F L the frame D which curries the shutter F can be turned round 180° and fixed in that position while the connecting rod d being disconnected by taking out the stud x, is thrown to the other side and attached to the spare crank b at the other end of the shaft c

At the same time the edge of the shutter can be adjusted parallel to the terminator of the moon by the rocking piece G. The necessity of at least the advantage of this arrangement was shown in the experimental trials already mentioned for it was found that to obtain tolerably uniform pictures of the whole moon many times more exposure was required for the parts near the terminator than for the bright edge. The apparatus includes a photographic micrometer similar to that described by Mr W. De La Rue in his. Account of the Solu Eclipse of July 18, 1860," Phil Trans. vol. clip. 373 for tabulating the photograms.

Spectroscope —The spectroscope with which the telescope is provided differs from the ordinary construction only in being furnished with Mi Grubb's compound prisms which with a considerable dispersion have a small deviation. They are composed of Chance's extra dense flint to which are comented outer prisms of light crown glass. The instrument is of remailable computiness and solidity.

The weight of the moving parts of this huge telescope is 18 1701bs of which the great speculum and its box and support are 3500

IIII LND

11

-

1

